

UNCLASSIFIED

UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: PREDE--ETC(U)
JUL 80 H L MURPHY DCPA01-77-C-0227

JUL 80 H L MURPHY

DCPA01-77-C-0227

NL

1 of 3

AD A 097915

**UPGRADING BASEMENTS FOR COMBINED NUCLEAR
WEAPONS EFFECTS: PREDESIGNED EXPEDIENT OPTIONS II.**

Final Technical Report

July 1980

Contract No. DCPA01-77-C-0227
FEMA Work Unit No. 1155C

APR 20 1981

A

Approved for public release; distribution unlimited.

DTIC FILE COPY



81 4 17 005

H. L. MURPHY ASSOCIATES

Box 1727
San Mateo, California 94401
(415) 348-2180

March 12, 1981

To: DISTRIBUTION LIST
For: Murphy, H. L., Upgrading Basements for Combined Nuclear Weapons
Effects: Predesigned Expedient Options II, SRI International
Final Technical Report for U.S. Federal Emergency Management
Agency, July 1980

E R R A T A

| <u>Page</u> | <u>Comment</u> |
|-------------|--|
| A1-22 | In 4th line from bottom: Correct spelling to "static". |
| A2-9 | In footnote: Insert parenthesis to change to "... table) is ...". |
| A2-20.1 | In 4th column, heading: Correct spelling to "Length". |
| B2-8 | In Figure B2-1A: Correct arrow for "Cap Block" to run to block that is on top of "Post". |
| D1-13 | In definition of "ksi": Change "kip" (within parentheses) to "ksi". |

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM | |
|--|-------------------------------------|---|-------------------------|
| 1. REPORT NUMBER (none) | 2. GOVT ACCESSION NO. AD-AC97915 | 3. RECIPIENT'S CATALOG NUMBER | |
| 4. TITLE (and Subtitle) UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: PREDESIGNED EXPEDIENT OPTIONS II | | 5. TYPE OF REPORT & PERIOD COVERED Final Technical Report | |
| 7. AUTHOR(s) H. L. Murphy | | 6. PERFORMING ORG. REPORT NUMBER 6876 | |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS SRI International (formerly Stanford Research Inst.) Menlo Park, California 94025 | | 8. CONTRACT OR GRANT NUMBER(s) DCPA01-77-C-0227 'C | |
| 11. CONTROLLING OFFICE NAME AND ADDRESS Federal Emergency Management Agency Washington, D.C. 20472 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS FEMA Work Unit 1155C | |
| 14. MONITORING AGENCY NAME & ADDRESS (if diff. from Controlling Office) | | 12. REPORT DATE July 1980 | 13. NO. OF PAGES 272 |
| | | 15. SECURITY CLASS. (of this report) UNCLASSIFIED | |
| 16. DISTRIBUTION STATEMENT (of this report) Approved for public release; distribution unlimited. | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from report) | | | |
| 18. SUPPLEMENTARY NOTES | | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) | | | |
| Protective Shelter, Nuclear Weapons Effects Natural Disasters Shelter Upgrading Basements for Shelter Expedient Upgrading of Basement Shelter Combined Nuclear Effects Shelter | | Shelter, Nuclear Attack Shelter, Natural Disasters Nuclear Attack Shelter Upgrading Basements Design, Shelter | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) (See reverse side.) | | | |

DD FORM 1473
1 JAN 73
EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED
SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

19. KEY WORDS

20 ABSTRACT

By: H. L. Murphy*

This report covers the results of the latest phase of a 3-phase project, with the overall objective of developing a set of expedient and engineered techniques, for upgrading the air blast and related effects resistance potential of basements in existing buildings. The purpose of upgrading such basement spaces is to provide shelter when needed by persons in: host areas, where the bulk of the population is expected to be during an attack, that are located at and beyond the 2-psi air blast range, using selected target aiming points and Mt-range bursts; and, risk areas, where shelter is needed that is within 15-minutes travel time of each key worker's place of work and provides potential shelter for 30- to 50-psi air blast ranges, in terms of peak free field overpressure.

Chapters of this report's main text are devoted to discussions of: background; general principles applicable to upgrading basements; closures for all basement shelter openings/apertures, in terms of principles for providing them; needs to be met in strengthening the structure over shelter candidate basements; some techniques and materials that can be used for such structure strengthening; and, shelters for key workers. In general, the main text of this report is intended for the artisan, the appendices having the more extensive, technical data and discussions.

The titles of the appendices are: Blast-Resistant Design/Analysis General Approach; Plywood Stressed-Skin Panels (Two-Sided Only) as Closures - Design and Fabrication; Plywood Stressed-Skin Panels (Two-Sided) as Beam-Columns; Plywood Use for Closures - Design; Wood Beam and Column Design - Simply Supported; Home Basements Upgrading in Host Areas; Blast-Resistant Design/Analysis of Steel Members; and, Structural Steel Local Availability and Use for Blast Shelter Upgrading.

The suggestions, guidance and technical help of M. A. Pachuta, G. N. Sisson, and D. W. Bensen, FEMA, are gratefully acknowledged, as are the contributions of former colleagues C. K. Wiehle, E. E. Pickering and J. E. Beck.#

* H. L. Murphy Associates, Box 1727, San Mateo, CA 94401 (415-348-2180)

James E. Beck and Associates, 4216 Los Palos Av., Palo Alto, CA 94306

SRI International



UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: PREDESIGNED EXPEDIENT OPTIONS II

Summary

Final Technical Report

July 1980

By: H. L. Murphy
Consulting Civil Engineer*

For: Federal Emergency Management Agency
Washington, D.C. 20472

Contract No. DCPA01-77-C-0227
FEMA Work Unit No. 1155C

SRI Project 6876

Approved for public release; distribution unlimited.

FEMA Review Notice:

This report has been reviewed in the Federal Emergency Management Agency and approved for publication. Approval does not signify that the contents necessarily reflect the views and policies of the Federal Emergency Management Agency.

333 Ravenswood Ave. • Menlo Park, California 94025
(415) 326-6200 • Cable: SRI INTL MPK • TWX: 910-373-1246

*H. L. Murphy Associates, Box 1727, San Mateo, CA 94401; 415-348-2180

| | |
|--------------------|-------------------------------------|
| Accession For | |
| NTIS GRA&I | <input checked="" type="checkbox"/> |
| DTIC TAB | <input type="checkbox"/> |
| Unannounced | <input type="checkbox"/> |
| Justification | |
| Distribution/ | |
| Availability Codes | |
| Avail and/or | |
| Dist | Special |

A

SUMMARY

This report covers the results of the latest phase of a 3-phase project, with the overall objective of developing a set of expedient and engineered techniques, for upgrading the air blast and related effects resistance potential of basements in existing buildings. It is recommended that any serious user of this report have copies of the reports covering the first two phases at hand. The purpose of upgrading such basement spaces is to provide shelter when needed by persons in host or risk areas or elsewhere. As stated in the second phase report, some work results were reported there for which the work was actually performed under this third phase's funding.

The first two phases of work were performed under a policy guidance that called for exploiting the inherent ultimate blast resistance of the slab over the basement selected for upgrading consideration, that is, upgrading work that would strengthen the remainder of the floor support system to a level equaling the inherent strength of the floor slab. The hoped for result was shelter adequate for, say, 8 to 15 psi blast free field overpressure. Exceptions were made, of course, such as the case of a large basement cut in half by a long-way interior corridor, and covered on each half with a rather long span, one-way slab running between corridor walls and outer walls; the basement cover slab's potential blast resistance could be upgraded considerably by simply running added support walls parallel to the interior corridor and supporting each existing one-way slab at its midspan.

In this (third) phase of the project work, shelter guidance for selection of candidate basements for upgrading has been re-oriented to meet the CRP (Crisis Relocation Plans). The CRP requires shelter in two kinds of specific geographic areas, which are located by study of selected attack areas in the United States and relative air blast ranges from the targets:

1. Host areas, where the bulk of the population is expected to be during an attack, that are located at and beyond the 2-psi air blast range, using the selected target aiming points and Mt-range bursts. Circumstances have required, in certain cases, a policy exception to provide shelter at and beyond the 3 psi range; the appendix on Home Basement Upgrading for Host Areas is specifically aimed at meeting this shelter need.

2. Risk areas, where shelter is needed that: (1) is within 15-minutes travel time of each key worker's place of work; and (2) provides potential shelter suitable for 30 to 50 psi air blast peak free field overpressure. Such shelter is discussed in Chapter 7.

The remaining chapters of this report's main text are devoted to a more complete background discussion; a discussion of general principles applicable to upgrading basements; a discussion of closures for all

basement shelter openings/apertures in terms of principles for providing them; a discussion of the needs to be met in strengthening the structure over shelter candidate basements; a discussion of some techniques and materials that can be used for such structure strengthening; and, a discussion of shelters for key workers as just mentioned. In general, the main text of this report is intended to be understandable to the non-engineer/architect and to provide help, for such a person as an artisan semiskilled in carpentry, in dipping briefly into several of the technical appendices to use them without having to either study or understand completely each entire appendix.

The titles of the appendices are: A. Blast-Resistant Design/Analysis General Approach; A1. Plywood Stressed-Skin Panels (Two-Sided Only) as Closures - Design and Fabrication; A2. Plywood Stressed-Skin Panels (Two-Sided) as Beam-Columns; A3. Plywood Use for Closures - Design; B1. Wood Beam and Column Design - Simply Supported; B2. Home Basements Upgrading in Host Areas; D1. Blast-Resistant Design/Analysis of Steel Members; and, E1. Structural Steel Local Availability and Use for Blast Shelter Upgrading.

Acknowledgments

Through suggestions and guidance, the technical help of M. A. Pachuta, G. N. Sisson, and D. W. Bensen, U. S. Federal Emergency Management Agency, was freely given and is gratefully acknowledged. Similarly acknowledged are: the work of a colleague, J. E. Beck,¹ in assisting specifically in preparing Appendix A2, as well as contributing pieces, plus advice in technical discussions, used in many places in this report; considerable work earlier in this project phase by another colleague, C. K. Wiehle; and the work of E. E. Pickering² in preparing Appendix E1.

¹ Formerly at SRI International and currently the principal of James E. Beck and Associates, Palo Alto, California.

² Consulting Civil Engineer, Menlo Park, California.

SRI International



UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: PREDESIGNED EXPEDIENT OPTIONS II

Final Technical Report

July 1980

By: H. L. Murphy
Consulting Civil Engineer*

For: Federal Emergency Management Agency
Washington, D.C. 20472

Contract No. DCPA01-77-C-0227
FEMA Work Unit No. 1155C

SRI Project 6876

Approved for public release; distribution unlimited.

FEMA Review Notice:

This report has been reviewed in the Federal Emergency Management Agency and approved for publication. Approval does not signify that the contents necessarily reflect the views and policies of the Federal Emergency Management Agency.

333 Ravenswood Ave. • Menlo Park, California 94025
(415) 328-6200 • Cable: SRI INTL MPK • TWX: 910-373-1246

*H. L. Murphy Associates, Box 1727, San Mateo, CA 94401; 415-348-2180

The information presented in this publication has been prepared in accordance with recognized engineering principles and is for general information only. While it is believed to be accurate, this information should not be used or relied upon for any specific application without competent professional examination and verification of its accuracy, suitability, and applicability by a licensed professional engineer, designer, or architect. The publication of the material contained herein is not intended as a representation or warranty on the part of SRI International or H. L. Murphy Associates, or of any other person named herein, that this information is suitable for any general or particular use or of freedom from infringement of any patent or patents. Anyone making use of this information assumes all liability arising from such use.

CONTENTS

| <u>Chapter</u> | <u>Page</u> |
|--|-------------|
| 1. INTRODUCTION | 1 |
| Acknowledgments | 2 |
| 2. BACKGROUND | 5 |
| Open Versus Closed Shelters | 10 |
| Appendices | 10 |
| 3. UPGRADING EXISTING BASEMENTS - GENERAL | 11 |
| 4. CLOSURES | 13 |
| 5. STRUCTURE STRENGTHENING NEEDS | 15 |
| A. Wood and Steel Existing Bending Members | 15 |
| B. Reinforced Concrete Existing Bending Members | 15 |
| C. Existing Columns | 17 |
| D. Existing Exterior Basement Walls | 18 |
| 6. STRUCTURE STRENGTHENING TECHNIQUES AND MATERIALS | 19 |
| Wood Availability and Use | 20 |
| A. Plywood Stressed-Skin Panels (Two-Sided) as Closures | 21 |
| B. Plywood Stressed-Skin Panels (Two-Sided) as Columns & Beam-Columns | 24 |
| C. Plywood Panels as Closures | 25 |
| D. Wood Beams | 26 |
| E. Peak Blast Resistance - Side-On versus Head-on | 27 |
| F. Steel Plates, Sheets, and Shapes | 27 |
| 7. SHELTER FOR KEY WORKERS | 29 |
| REFERENCES | 35 |

Appendices

- A. BLAST-RESISTANT DESIGN/ANALYSIS GENERAL APPROACH
- A1. PLYWOOD STRESSED-SKIN PANELS (TWO-SIDED ONLY) AS CLOSURES -
 DESIGN AND FABRICATION
- A2. PLYWOOD STRESSED-SKIN PANELS (TWO-SIDED) AS BEAM-COLUMNS
- A3. PLYWOOD USE FOR CLOSURES - DESIGN
- B1. WOOD BEAM AND COLUMN DESIGN - SIMPLY SUPPORTED
- B2. HOME BASEMENTS UPGRADING IN HOST AREAS
- D1. BLAST-RESISTANT DESIGN/ANALYSIS OF STEEL MEMBERS
- E1. STRUCTURAL STEEL LOCAL AVAILABILITY AND USE FOR BLAST SHELTER
 UPGRADING

TABLES

| | | |
|---|---|----|
| 1 | CONTENTS, TABLE AND FIGURES LISTS FROM REFERENCE 1 | 7 |
| 2 | RESULTS FROM EXISTING STRUCTURES EVALUATIONS OF ELEVEN NSS BUILDINGS | 30 |

FIGURE

| | | |
|---|---|----|
| 1 | TYPICAL TWO-SIDED PLYWOOD STRESSED-SKIN PANEL | 23 |
|---|---|----|

Chapter 1

INTRODUCTION

This report covers the results of the latest phase of a 3-phase project, with the overall objective of developing a set of expedient and engineered techniques, for upgrading the air blast and related effects resistance potential of basements in existing buildings. Reports covering the first two phases are References [1 and 2].¹ It is recommended that any serious user of this report have copies of both references at hand.² The purpose of upgrading such basement spaces is to provide shelter when needed by persons in host or risk areas or elsewhere. As stated in the footnote on page 1 of the second phase report [Ref. 2], some work results were reported there for which the work was actually performed under this third phase's funding.³

The first two phases of work were performed under a policy guidance that called for exploiting the inherent ultimate blast resistance of the slab over the basement selected for upgrading consideration, that is, upgrading work that would strengthen the remainder of the floor support system to a level equaling the inherent strength of the floor slab. The hoped for result was shelter adequate for, say, 8 to 15 psi blast free field overpressure. Exceptions were made, of course, such as the case of a large basement cut in half by a long-way interior corridor, and covered on each half with a rather long span, one-way slab running between corridor walls and outer walls; the basement cover slab's potential blast resistance could be upgraded considerably by simply running added support walls parallel to the interior corridor and supporting each existing one-way slab at its midspan.

In this (third) phase of the project work, shelter guidance for selection of candidate basements for upgrading has been re-oriented to meet the CRP (Crisis Relocation Plans). The CRP requires shelter in two kinds of specific geographic areas, which are located by study of selected attack areas in the United States and relative air blast ranges from the targets:

- Host areas, where the bulk of the population is expected to be during an attack, that are located at and beyond the 2-psi air blast range, using the selected target aiming points and Mt-range bursts. Circumstances have required, in certain cases, a policy exception to provide shelter at and beyond the 3 psi

¹ Brackets are used herein to indicated sources in the References list at the end of this report (main text).

² Available for purchase from NTIS, Springfield, Virginia 22151.

³ For example, original Appendices A1 and A3 herein.

range, meaning that Appendix B2, Home Basement Upgrading for Host Areas, is specifically aimed at meeting this need for shelter against 2-3 psi air blast peak free field overpressure.

- Risk areas, where shelter is needed that: (1) is within 15-minutes travel time of each key worker's place of work, and (2) provides potential shelter suitable for 30 to 50 psi air blast peak free field overpressure. Such shelter is discussed further in Chapter 7.

The remaining chapters of this report's main text are devoted to a more complete background discussion; a discussion of general principles applicable to upgrading basements; a discussion of closures for all basement shelter openings/apertures in terms of principles for providing them; a discussion of the needs to be met in strengthening the structure over shelter candidate basements; a discussion of some techniques and materials that can be used for such structure strengthening; and, a discussion of shelters for key workers as just mentioned. In general, the main text of this report is intended to be understandable to the non-engineer/architect and to provide help, for such a person as an artisan semiskilled in carpentry, in dipping briefly into several of the technical appendices to use them without having to either study or understand completely each entire appendix.

Acknowledgments

Through suggestions and guidance, the technical help of M. A. Pachuta, G. N. Sisson, and D. W. Bensen, U. S. Federal Emergency Management Agency, was freely given and is gratefully acknowledged. Similarly acknowledged are: the work of a colleague, J. E. Beck,⁴ in assisting specifically in preparing Appendix A2, as well as contributing pieces, plus advice in technical discussions, used in many places in this report; considerable work earlier in this project phase by another colleague, C. K. Wiehle; and the work of E. E. Pickering⁵ in preparing Appendix E1.

⁴ Formerly at SRI International and currently the principal of James E. Beck and Associates, Palo Alto, California.

⁵ Consulting Civil Engineer, Menlo Park, California.

Chapter 2

BACKGROUND

The Introduction section of the second phase report [2] has been updated and is used below.

Because of their inherent shelter potential, basements of substantial buildings having a concrete slab first floor (supported by either steel or reinforced concrete beam-girder-column systems) are the natural choice for relatively high degrees of protection. The first floor (floor over basement) concrete slab ordinarily has a rather high degree of air blast (collapse) resistance, because for normal use it must withstand individual point loads, as well as general area loads. The supporting beams and girders become progressively weaker, in that order (in ultimate or collapse strength), however, as the tributary areas served increase in size and thus the effect of normal use point loads decreases for these heavier supporting members. Columns may or may not be relatively weaker depending on the height of the building. It is frequently found that the first floor slab itself will resist about 10 psi peak "side-on" air blast pressure or more, but that this potential is degraded rather seriously by weaker beams and girders, and sometimes columns. In addition most basements have exterior openings, and all have interior openings, permitting air blast to enter (assuming that the air blast wave passes through or destroys the building above the basement). Thus, the general principle to be followed is to exploit the relatively high floor slab resistance, through closing openings as well as applying strengthening measures to the other portions of the first floor system and possibly to the basement column system. If the first floor slab does not have an acceptable level of inherent blast resistance, upgrading the basement may still be well worth considering but should be balanced against the cost (in materials, elapsed time and manpower used) of alternate schemes for shelter (e.g., expedient/field shelters; constructed R/C (reinforced concrete) and/or corrugated metal ducts (see Chapter 7); mines, etc.).

The measures available for upgrading existing basement space for shelter purposes may be categorized as either "expedient" or "engineered." Expedient measures are those that can be accomplished in a relatively short period of time (say two to three days) during a crisis build-up period by building occupants using readily available materials. Expedient measures may be pre-engineered with resulting designs distributed in advance in "how-to-do-it" drawings and instructions. Engineered measures also require longer periods of time and the services of professional engineers for evaluation and design, perhaps tailored to a specific building or a specific type of building.

Upgrading measures considered include prevention of air blast entry into the shelter space, reduction of air blast loading on exposed areas, strengthening of floor system structural members, provision of debris

protection, provision of "last resort" shelter in case of floor system collapse, and other protective measures. Both closed and open shelter situations were considered as were post-attack considerations.

For the expedient case, the most common vulnerability problems were examined and principles of protection are given. Specific building features requiring protection are illustrated and suitable methods of protection and materials are presented. The degree of protection afforded by the various methods and materials are given. Suggested local sources of materials and required tools are also given. The expedient section is prepared in "how-to-do-it" illustrative manner so as to permit ready application by non-engineer building occupants and other untrained personnel.

For the engineered case, the air blast resistance characteristics of suitable basements in existing buildings are described along with upgrading principles and techniques. Methods of evaluating individual buildings for basic first floor system air blast resistance are discussed. Upgrading design guidance for various building features is given. Specific detailed evaluation and design procedures for the more complex upgrading problems are given in appendices. Several examples of existing buildings are also given, with basement upgrading measures applied.

It is intended that this report, together with the first- and second phase reports [1,2] serve as a basic reference and guidance for civil defense planners, building owners, occupants charged with upgrading shelter space for themselves, engineering enterprises, and others concerned with the air blast upgrading of existing buildings before or during a strategic population relocation, or other civil defense shelter program. The information contained herein will also be useful for expedient upgrading, on an opportunity basis, of buildings used for temporary shelter in the population relocation or "host" areas.

Many of the matters mentioned above were covered in the first-phase report [1] for which an overview is provided by including that report's Contents, Table and Figures lists; see Table 1. Figures 1 through 11 of the earlier report [1] provide schematics or concepts for closures and structural strengthening; the later work reported in Reference [2] and hereinafter includes engineered/predesigned data for use in closures and in structure strengthening.

For technical readers such as civil engineers and architects interested in strengthening of basements for combined nuclear weapons effects shelter, recommended reading includes the Appendices herein plus References [1 and 2] for existing basements, and References [3 and 4] for basements under design or planning.

Table 1 CONTENTS, TABLE AND FIGURES LISTS FROM REFERENCE 1

| CONTENTS | | |
|---|-----|----|
| PREFACE/SUMMARY | iii | |
| TABLES | xi | |
| FIGURES | xii | |
| 1 INTRODUCTION | 1 | 16 |
| Objective | 1 | 16 |
| Work Performed | 1 | 19 |
| 2 BACKGROUND | 3 | 19 |
| Situation | 3 | 22 |
| Application | 4 | 24 |
| Vulnerability Problems | 6 | |
| A. Closed Shelter | 6 | |
| B. Open Shelter | 7 | |
| 3 EXPEDIENT UPGRADING PROTECTION PRINCIPLES | 9 | |
| Introduction | 9 | |
| Prevention of Air Blast Entry (Closed Shelter Mode) | 9 | |
| Air Blast Loading Reduction on Basement Exterior Surfaces | 10 | |
| Air Blast Structural Strengthening | 10 | |
| Debris Protection | 11 | |
| Additional Radiation Protection | 12 | |
| Open Shelter Protection | 12 | |
| Other Protective Measures | 12 | |
| 4 METHODS AND MATERIALS | 15 | |
| Prevention of Air Blast Entry (Closed Shelter Mode) | 15 | |
| A. Window and Door Openings | | 16 |
| B. Ventilation Structures | | 16 |
| C. Truck Loading Docks | | 19 |
| D. Elevator Shafts | | 19 |
| E. Stairwells | | 22 |
| F. Utility Penetrations | | 24 |
| Air Blast Loading Reduction on Basement Exterior Surfaces | | 24 |
| Air Blast Structural Strengthening | | 26 |
| G. Exposed Wall Areas | | 26 |
| H. Floor Systems | | 29 |
| Debris Protection | | 33 |
| Open Shelter Protection | | 34 |
| I. Avoidance of Blast Concentration | | 34 |
| J. Provision of Internal Blast Protection | | 35 |
| Post-Attack Considerations | | 36 |
| K. Ventilation | | 36 |
| L. Lighting | | 37 |
| M. Communications | | 37 |
| N. Emergency Exit | | 38 |
| O. Additional Fallout Radiation Protection | | 38 |
| P. Fire Protection | | 38 |
| Materials and Sources | | 38 |
| Q. Blocking and Strengthening Materials | | 39 |
| R. Tools and Equipment | | 41 |
| S. Desirable Stockpiled Materials | | 42 |
| 5 BUILDING BASEMENT UPGRADING EXAMPLES | | 43 |
| 1: Blast Strength Likely Order Among R/C Floor Members | | 45 |
| Objective | | 45 |
| Background | | 45 |
| A. Effect of Type of Support Beam on Floor Strength | | 46 |
| Discussion | | 46 |
| B. All Floor Cases | | 50 |
| C. Flat-Plate and Flat Slab Floor Systems | | 57 |
| D. Reinforced Concrete Slab Supported by Steel Beams Floor Systems | | 58 |

Table 1 (continued)

| | | | |
|---|----|--|-----|
| Comments | 59 | Analysis | 100 |
| II: Emergency Operating Center (EOC), Livermore, California | 61 | Design - Blast Upgrading Expedient Options | 100 |
| Introduction | 61 | A. Blast Loadings | 100 |
| Description of Building | 62 | B. Open Shelter Potential | 102 |
| Analysis | 64 | C. Closed Shelter Potential | 103 |
| A. Floor Slab Over Basement | 64 | D. Sources of Indigenous Labor and Material | 104 |
| B. Mechanical Room Interior Wall | 66 | E. Design of Blast Closures and Joist/Girder Supports | 104 |
| C. Stairwell Interior Wall | 66 | F. Materials/Labor Summary | 106 |
| D. Summary | 67 | V: West Pavilion, Stanford University Hospital, Stanford, California | 107 |
| Design - Blast Upgrading Expedient Options | 68 | Introduction | 107 |
| E. Blast Loadings | 68 | Description of Building | 107 |
| F. Open Shelter Potential | 69 | Analysis | 109 |
| G. Closed Shelter Potential | 69 | Design - Blast Upgrading Expedient Options | 109 |
| H. Sources of Indigenous Materials and Labor | 70 | A. Blast Loading | 109 |
| I. Design of Blast Closures | 74 | B. Open Shelter Potential | 110 |
| J. Materials/Labor Summary | 74 | C. Closed Shelter Potential | 110 |
| K. Blast Upgrading Engineered Options | 74 | D. Sources of Indigenous Materials and Labor | 111 |
| III: Hamilton AFB (California) Building No. 424 | 75 | E. Design of Blast Closures | 112 |
| Introduction | 75 | F. Materials/Labor Summary | 112 |
| Description of Building | 78 | 6 ADDITIONAL WORK NEEDED | 115 |
| Analysis | 78 | Overall Objectives and Status | 115 |
| A. Floor System | 80 | Building Types | 115 |
| B. Exterior Wall | 83 | Expedient Upgrading | 116 |
| C. Summary | 84 | Engineered Upgrading | 116 |
| Design - Blast Upgrading Expedient Options | 84 | Report | 117 |
| D. Blast Loadings | 84 | REFERENCES | 119 |
| E. Open Shelter Potential | 85 | BIBLIOGRAPHY | 121 |
| F. Closed Shelter Potential | 88 | APPENDIX A - Literature Search | A-1 |
| G. Sources of Indigenous Materials and Labor | 89 | APPENDIX B - Design of Wood Beams - Slaply Supported | B-1 |
| H. Design of Blast Closures and Beam Supports | 89 | | |
| I. Materials/Labor Summary | 91 | | |
| J. Blast Upgrading Engineered Options | 92 | | |
| IV: Middlefield Parking Garage | 97 | | |
| Introduction | 97 | | |
| Description of Building | 97 | | |

Table 1 (concluded)

| | |
|--|-----|
| TABLE | |
| 1 Floor Element Data | 51 |
| 3 Expedient Blast Protection for a Truck Loading Dock | 20 |
| 4 Expedient Blast Protection for Elevator Shafts | 21 |
| 5 Expedient Blast Protection for Stairwells | 23 |
| 6 Expedient Blast Protection for Floor Penetrations | 25 |
| 7 Reduction of Blast Loading for Exposed Basement Walls | 27 |
| 8 Strengthening Exposed Basement Walls | 28 |
| 9 Provision of End Support | 30 |
| 10 Additional Column Support | 31 |
| 11 Slab-Beam-Girder Strengthening | 32 |
| 12 Histogram and Cumulative Frequency Distribution of the Mean Collapse Overpressure for the Floors Over Basement Areas of 36 Buildings | 47 |
| 13 Comparison of the Cumulative Frequency Distributions of the Mean Collapse Overpressure for Floor Systems by the Type of Support Beams | 49 |
| 14 Collapse Overpressure for Floors Over Basement Areas Versus Design Live Load | 54 |
| 15 Livermore EOC Photographs | 63 |
| 16 Livermore EOC Basement Floor Plan | 65 |
| 17 Livermore EOC Blast Closure Locations | 71 |
| 18 Hamilton AFB Building 424 Floor Plans | 76 |
| 19 Hamilton AFB Building 424 Photographs | 77 |
| 20 Reconstruction of Likely Design Calculations for Hamilton AFB Building 424 | 86 |
| 21 Plan View, Middlefield Underground Garage | 88 |
| 22 Middlefield Underground Garage Interior Structural Detail Photograph | 99 |
| 23 Plan View, Middlefield Parking Garage, Showing Strength Zones | 101 |
| 24 Photograph and Ground Floor Plan of West Pavilion Building of Stanford Hospital | 108 |
| FIGURES | |
| 1 Expedient Blast Protection for Basement Windows With or Without Window Walls | 17 |
| 2 Expedient Blast Protection for Ventilation Structures | 18 |

Open Versus Closed Shelters

Some vulnerability problems of open and closed shelters are discussed starting on page 6 of Reference [1], as indicated in its Contents list reproduced herein in Table 1. Certain matters, however, are worth brief mention here.

Open shelter requires that all materiel in the shelter be fastened with sufficient strength to resist the anticipated entering blast wave, or else such items of materiel may well become missiles causing injury or death. An alternative is to surround the materiel items that pose potential missile hazards with a blast resistant barrier, so that the blast wave does not strike the items. Dealing with such potential missile hazards can be expensive (in terms of materials, elapsed time, and manpower), varying with the type of structure: for example, a parking garage might be provided with such missile hazard reduction on a cost-effective basis, whereas a potential shelter space with many pieces of equipment of varying degrees of fixity could well dictate against considering open shelter.

Closed shelters can be provided with aperture closures (see Chapter 4) and, within the range of air blast peak free field overpressures considered in this study, that is up to 50 psi, materiel will generally not require fastening in place; exceptions would be made in the case of overhead items by insuring that the fastenings are adequate to take any shock or vibration hitting the overhead structural members.

For host areas, where shelter against air blast up to 2 or 3 psi (see Chapter 1) are contemplated, work in anchoring materiel items might be expected to be modest in cost.

Subject to these brief comments, this report generally contemplates the use of closed shelters, unless specifically mentioned otherwise. A parking garage, for example, could well be the exception because of the problems of providing closures for the vehicle entrances in contrast to the cost of anchoring down or removing materiel items.

Appendices

The appendices of this report include several that are new to the work and others that are extracts, revisions, or provided totally by reference to a previously published appendix. Because of the manner of their development, the appendices are not numbered in the order of their use (as perhaps they should be).

Chapter 3

UPGRADING EXISTING BASEMENTS - GENERAL

This report is concerned with upgrading work for nuclear effects shelter in existing building basements, that are fully or partially below ground level and that can be bermed with soil up to the level of the first floor slab. If floor-level berming simply cannot be accomplished for the entire basement, the lessened radiation protection, as well as the need for increased blast protection of exposed wall portions (peak reflected pressure from a blast wave hitting a wall head-on is approximately three times the peak blast free field overpressure), must be considered. Generally, use of only part of the basement for closed shelter is more costly (in terms of available resources) than use of the full basement, because of the need for blast resistant interior walls around the partial basement shelter.

Radiation protection upgrading, whether for fallout or initial nuclear and thermal, usually requires simply additional mass in or on the floor over the shelter, plus of course the berming mentioned above. This can be bagged material or loose soil (easily placed on the floor slab), in sufficient amount for the required level of protection generally stated in full policy statements only briefly mentioned earlier. Use of part of the (ultimate/collapse) strength of the overhead slab will, of course, reduce the strength available for blast resistance. Calculations involved in such portioning of the overhead floor strength are illustrated by examples in Appendix B2 on upgrading home basements, but would be similar for a floor over higher blast level shelters.

Blast resistance needs to be considered in upgrading can generally be described under the following three categories:

(1) Peak air blast free field overpressures up to 2 or 3 psi: As briefly mentioned earlier, this level of blast resistance applies to host areas used under the CRPs (Crisis Relocation Plans). In home basements, one can assume that the interior pressures will have a long enough rise time to reach the peak pressure, to allow handling the blast loading as a statically applied but very short duration load - stated another way, to consider the blast load as an impact load only in terms of duration, not in terms of an instantaneously applied load. Further, one should consider the ultimate/collapse strength blast resistance of the floor over the basement, not with the usual design factors of safety. These matters are discussed in more detail in Appendices A and B2.

(2) Blast resistance equalling a free field overpressure that will fully tax the inherent blast strength of existing slabs over the basement shelter to be upgraded: Although this level of blast resistance is not current but earlier policy, as discussed above, this level may represent the most that can be done for many basements considering the

available time and material sources, and/or may be the most cost-effective shelter when considered against constructing other shelter, such as expedient shelter schemes [5,6], buried conduits/large pipes, etc. This blast resistance level should work out to roughly 10 psi for a sizable number of existing basements or, say, 6-15 psi as a range.

(3) Blast resistance of 30-50 psi peak free field overpressure, the level needed for risk areas as shelter for key workers, again under CRPs (Crisis Relocation Plans): Work to date has indicated a low probability of getting this protection level of shelter in existing buildings, unless a truly high level of manpower and material resources is spent and, even then, serious questions need to be first answered by tests concerning the blast resistance that can be expected from existing exterior basement walls. This shelter level and related problems are discussed further in Chapter 7.

Another general or common technical matter that should be mentioned at this point is that of bearing between existing members and upgraded members, and their loads and supports. Bearing problems are discussed frequently in the following portions of this report, in terms of specific building materials, but two points are worth making at this juncture: first, if two different materials, or two different strength levels of the same material (e.g., wood), must bear on each other, the required common bearing area will, of course, be determined by that required for the weaker material; and, second, bearing damage, even destruction, may be acceptable in *upgrading design*, because of the 1-shot/1-time loading assumed for nuclear shelter design and the energy absorbed in damaging components such as the wood cribbing members or the wood wedges under columns.

For the last general upgrading suggestion, the reader/user of this report is encouraged to review Reference [1] for its eleven upgrading schemes shown in pages 15-33, specifically Figures 1 through 11 of that report. While these figures are not to scale and are thus called upgrading schemes herein, the following chapters and appendices will give the reader/user the means to "size" the members, whether beams, columns, or beam-columns, at least in some of the materials contemplated for use.

Chapter 4

CLOSURES

Closure is used herein to describe the upgrading covering put over all apertures or openings in the existing basements selected as potential shelter, whether the opening is for a window, door, ventilation, utility, or other, whether small or large (for a 2-in. pipe or a double door). In planning for each closure, shelter ventilation should be continually kept in mind, and the closure be planned for its ability to remain open as long as possible if such is needed for ventilation; for example, a vertical opening might use a steel plate, guillotine-type closure, that need only be tripped to fall into place, perhaps the quickest operating of any closure type.

Vertical closures should be avoided to the maximum extent possible, simply because they usually involve dealing with the blast load's peak reflected pressure rather than its side-on pressure on the surface of the ground, the difference being an approximate three times increase in peak pressure level, if one has to deal with reflected pressure created by the blast wave striking a vertical wall, or going down a window-well and striking an end wall. This ratio of reflected to side-on pressure varies considerably with conditions, but to handle the simple situation of a blast wave travelling along the ground and striking a vertical surface head-on, with a reasonable distance to travel to clear around the vertical surface, the ratio is approximately 3 to 1 (at least in the range of free field overpressures of interest herein); more precise ratios may be obtained by referring to the scale shown on page B1-26 of Appendix B1. Perhaps the commonest example that might be used would be that of a window-well, serving the basement of a building from large to single family residence in size; a closure of the guillotine-type might well be mounted on the outside of the exposed basement wall to drop down over the well opening into the building, but such planning would require this closure to bear the multiple-reflected pressure caused by the blast wave entering the window-well. A simpler and far better solution might be to put a closure over the top of the window-well, preferably at ground surface, and cover it with berming material (soil, sand, whatever); the closure might be a plywood panel or a steel plate, among others. In later chapters, where the sizing of the closure, beam, column, etc., is described, the anticipated peak applied blast loading is used, leaving it to the reader/user to make this peak applied blast loading the one that is felt by the closure or structural member, whether it be the peak reflected (head-on) blast loading or a peak side-on blast loading.

An easily overlooked item in the matter of closures is that of the need for examining the blast resistance/strength of the frame around the opening to be protected - in other words, can that frame support the loading to be transferred from the closure to the frame? For example, openings built into reinforced concrete floor slabs usually have extra

reinforcing steel to support their perimeter. Any doubts about the adequacy of the frame to support the closure must usually be handled by some upgrading supports specifically for the frame: For example, there may need to be some timber framing around the door opening, which framing is next supported by some diagonal members blocked on the floor to other walls or to interior footings, etc., (see Figure 8 of Reference [1] for illustration of this diagonal bracing for a wall; it would be similar for a door frame or any other component requiring added support).

Frames that support the closure on two opposite sides only, call for a closure that acts as a one-way bending member that primarily experiences bending stresses along its span between the two support edges. Similarly, a closure supported on four sides is termed a two-way bending member; at the risk of being premature, passing mention is, nonetheless, made here that a two-way bending member gains little in blast resistance over a one-way member spanning the shorter span of the opening, if the longer span is more than 2 to 3 times the shorter span of the opening (more on this later). For a closure supported on three sides, the purposes of this upgrading report are best served by treating such a closure as being supported only on the two opposite sides and ignoring the support given by the third side, at least for sizing (design/analysis) purposes.

Fastening blast closures in place is a matter worth brief mention: If the closure is to resist blast (we do use closures for radiation resistance soil alone, of course), and the blast is expected to apply head-on to the plate as with a reflected blast loading, the situation is good for a closure lying on the blastward side of the frame, because there is little tendency for the closure to move sideways and it needs be held in place only to the extent required for positioning prior to blast loading. If the blast is expected to hit the closure side-on, then the fastenings would probably include cleat-type blocks on some or all sides of the closure to prevent sliding, as well as the fastenings to maintain closure position prior to blast loading. The negative blast wave that usually follows the blast wave's transit has been purposely ignored; if it's considered a problem in a specific instance, then the fastenings must be adequate to meet the negative blast phase.

Chapter 5

STRUCTURE STRENGTHENING NEEDS

This chapter deals briefly with the strengthening needs of members in the existing structure, that is the basement that has been selected for upgrading for nuclear protective shelter.

A. Wood and Steel Existing Bending Members

Wood and steel existing structure bending members have a considerable advantage for upgrading over existing reinforced concrete (R/C) members. For example, because of their material homogeneity, steel or wood beams/girders/floor stringers can have added intermediate supports at any chosen location along their length (assuming they are prismatic), whereas an existing R/C bending member can have added supports only where appropriate after considering whether the principal tensile reinforcing steel is located near the bottom or top face of the member, a serious restriction for the R/C members. One exception should be made for wood bending members, in contrast to steel members: the wood member might have been carefully placed so that a tight wood knot (falling near midspan and located near one edge of the member) is placed so that the tight wood knot is near the top (compressive) face of the member under bending stress, rather than near the bottom (tensile) face of the member under bending load; for such a case (perhaps uncommon), problems to be dealt with are similar to those in upgrading R/C bending members. Assessing the benefits of added (upgrading) interior supports under an existing wood beam, for example, does require consideration of each criterion for sizing (designing/analyzing) the member, because the mode of failure may change (from flexural to horizontal shear) in shortening the effective span of the member. For examples in wood bending member upgrading, see Appendix B2.

B. Reinforced Concrete Existing Bending Members

Reinforced concrete existing members entail much more difficulty in terms of providing added (upgrading) interior supports in beams: Perhaps the foremost problem is that of finding out how much reinforcing steel is imbedded in the concrete and where it is located. Certainly some assumptions can be made but they are an inadequate substitute for seeing a set of as-built plans, which may indeed be available from the building owner or the files of the building department of the city/county building department.

For upgrading R/C beams, assumptions can be made: The center third of a single-span, simply-supported beam will behave at least as strong as a shorter simply-supported span, if supports are added at the third points of the existing beam. This means that the blast loading resist-

ance of the center third of the beam has been increased roughly nine times over its strength prior to upgrading. For a R/C beam continuous over several simple supports, any span might be similarly examined; if a quarter of the span length, centered on the midspan, has added (upgrading) columns, that quarter-span portion of the beam span might have its blast resistance increased roughly 16 times its strength before upgrading.

Once these easy assumptions have been made and utilized, though, things may get sticky for further upgrading, in the absence of details on the as-built reinforcing steel and its placement: However, in the beam portions between the upgraded midspan portion and the original column supports, one might put in equally spaced columns at a spacing at or less than 3 times the overall depth of the R/C beam. This approach amounts to treating each segment of the R/C beam, outside of the midspan portion just discussed, as if each new short span of such ends is a concrete pedestal (lightly reinforced). Conversely, if one has as-built details on the reinforcing steel amount and location, such things as a better approximation of lengths for the midspan portions just described, the possible membrane action of the reinforcing steel based on its imbedment lengths, etc., will allow some refinement of the location of added (upgrading) columns.

Existing structures evaluation (ESE) techniques developed by Wiehle, Bockholt, and Beck [7A,7B,7C,8] are complex and detailed, but do deal with these analysis problems peculiar to all R/C members. Similar thinking to that just described for R/C beams may be used for R/C one-way slabs, and sometimes R/C two-way slabs.

While R/C flat slabs apparently offer an upgrading potential, R/C flat plates were examined⁶ for upgrading, especially against punching shear of columns through the flat plate; the upgrading considered was to put vertical supports around each column, but even at various distances (from close to each column out to one-quarter of their span) the flat plate's predicted blast resistance was increased very little by such upgrading.

The ESE work specifically in connection with 11 selected NSS buildings scattered throughout the United States is described in Chapter 7.

Related testing and analytical work under FEMA support has been, and continues to be, done by others [9A,9B,9C], including not only the R/C member types discussed above, but also including R/C waffle slabs, flat plates, flat slabs, etc.

The following paragraphs were prepared by J. E. Beck who has just completed a report on the "as built" strength of building floor systems [8] and is currently analyzing an additional 25 buildings along with further model verification/upgrading work:

⁶ For this project by C. K. Wiehle using his ESE techniques.

The best (R/C) candidate members for upgrading are those members with spans of 18 ft or greater that can be upgraded by intermediate supports at third or quarter points. Furthermore, analytical results therein indicated that if upgrading is accomplished by putting intermediate supports at about 6-ft spacing, an R/C slab about 6-in. thick can resist an overpressure of approximately 30 psi blast, and a slab about 8-in. thick can resist approximately 50 psi.

"Most R/C slabs are designed to have a span-to-thickness ratio of 24. Therefore, slabs having clear spans greater than 12 ft will normally have a potential resistance greater than 30 psi, and slabs having clear spans greater than 18 ft have a potential resistance greater than 50 psi.

"The predicted upgrading potential of R/C slabs is based on the calculated capacity of one-way simply-supported slabs with reduced spans (about 6 ft). Although it is true that the steel reinforcing in an "as-built" structure may not be at optimum points for upgrading, it is still probable that the calculated simply-supported strength of each upgraded center portion is representative of the strength of the slab. This will also be true even at ends that are designed as fixed and, therefore, may at first glance appear weaker. This statement is based on the following observations:

"(1) The detailing of a fixed joint requires twice the moment capacity of the center of the slab, and compression steel at least equal to 1/3 the central steel is present in this section.

"(2) If the joint is designed as fixed, it will act as a simply-supported beam straddling the top of the support member and will have approximately the strength of a simply-supported element having a free span equal to the clear distance between the supports."

C. Existing Columns

ESE work on R/C columns has indicated that they are adequate for much heavier blast loads than their (normal-use) design loads, and especially in the case of a multistory structure, say, 4 stories or higher, where the superstructure may be expected to allow most of the blast loading to blow through between floors rather than subject the basement columns to higher blast loadings due to such things as overturning considerations. Further, the upgrading just described for beams makes clear the plan to add a large number of columns, meaning that each original/existing column will have its contributory blast loading area on the first floor considerably reduced in size, and thus its individual column loading considerably reduced. The need, therefore, for increasing the strength of reinforced concrete columns for upgrading is small to nonexistent. Similar thinking may be applied to columns of other materials existing in the basement to be upgraded into a nuclear protective shelter, in that the remedy is simply to have existing columns share the anticipated blast loading with additional columns.

Column footings in structures to be upgraded pose no significant problems in that those under existing columns will have their load shared as just described for the columns themselves; for columns added in upgrading work, a recent test [10] at the U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi, involved loading a square column consisting of four 4x4s (actual 3.5x3.5 in.) strapped together and bearing on a "typical" concrete floor slab over compacted gravel over compacted soil, with the results indicating that this column could carry a static load initially peaking at 50 kips then increasing to a new peak of 84 kips and degrading somewhat, but always above 50 kips for a loading of some 10 minutes (many, many times the duration of a nuclear blast loading). This loading amounts to roughly 2,000 psi on the column and footing. At the peak loading, displacement of the footing was 1.0 in. and its displacement at the time the tests was stopped was about 1.45 in. The test will be reported in a forthcoming WES technical report, of course, but these results were gratefully received by those who have planned extensive upgrading work, where many additional columns have been planned for use supported on a "typical" basement floor slab with nothing more than a couple of wedges under the column (for erection convenience).

D. Existing Exterior Basement Walls

Exterior basement walls, whether plain CMUs, reinforced CMUs, or brick, or certainly R/C construction, have been generally accepted as having sufficient blast resistance capacity for host area shelters, and those shelters contemplated where the inherent strength of the main slab over the basement is to be exploited (say, 8-15 psi air blast peak free field overpressure). However, serious concern over the adequacy of exterior basement walls, including walls of R/C construction, has been expressed when upgrading for higher blast resistance, especially as high as 30-50 psi, is contemplated. As a result, a FEMA research technical project officer, at a recent meeting with structural research contractors at WES, included in the discussions the need for static and dynamic tests of "typical" exterior R/C walls (fully and partially buried). The purpose of the proposed tests is not to see whether design procedures apparently used were adequate (they may be conservative), but more specifically to determine the blast resistant capacity of such walls in terms of absolute ultimate behavior (through collapse), that is, to answer the question of whether or not the soil transmitting the blast loading to the exterior basement wall will indeed follow and force the wall inward beyond an acceptable displacement, closely approaching collapse. Meanwhile, planning for upgrading potential, especially for overpressure levels greater than, say, 15 or 20 psi: must be conservatively evaluated as requiring strengthening of the exterior basement walls; or can be optimistically continued on the basis that the exterior basement walls would not fail because the soil will not move fast enough to push the wall inward further than acceptable. This matter impinges seriously on the direction of Chapter 7, Shelter for Key Workers (30 to 50 psi air blast peak free field overpressure).

Chapter 6

STRUCTURE STRENGTHENING TECHNIQUES AND MATERIALS

This chapter concerns meeting the upgrading needs perceived for a particular shelter candidate basement, as described in the preceding chapter.

The chapter deals with bending members (lateral loads only) such as beams, closures, girders, etc.; columns (axial loads only); and beam-columns (both lateral and axial loads). It deals with these three kinds of structural members by sizing the members to meet the need. The sizing may be done: by determining from the need the size of member required (design), and whatever material; or by assuming a particular member's availability and finding its strength capacity (analysis), then comparing the capacity with the need. The aids available herein, as described below, may be oriented to both design and analysis depending upon which way they are entered for use. One may, for example, know the load to be met on a given floor over a basement and the contributory area to be served by a column, then look at a table of column strengths and find which column(s), if any, will meet or exceed the need, using a table/graph/chart of column strengths (thereby using a little design with a little analysis!). Above all, the reader/user should not let terminology deter him/her from using the material presented (the author hereby invites comments on any simplification needs encountered).

Appendix A has been prepared for the artisan or the professional engineer/architect as an attempt to introduce the terminology basic to the structural problems in handling impact/dynamic loads, such as air blast, meeting loads that are applied in zero to a very short time and that have a short duration (of the order of seconds).

A very useful aid in reading graphs (such as those encountered in the appendices of this report, as well as those used in such civil defense training such as that given for Fallout Shelter Analysis) may be easily prepared and will prove very useful if given a trial: obtain an ordinary drafting (plastic) 45-degree triangle, clear, of about 6 to 8 inches on the two equal (short) sides; use any straight edge, a careful eye, and any sharp pointed instrument to scribe lines parallel to each of these two sides, perhaps a quarter-inch in from the edge although this is not critical; and, use a sharp pencil to darken the bottoms of the scribed lines, then wipe off the excess graphite. The aid then can be used on a design graph where multiple curves must be either read directly or interpolated between (for a particular value described by the curves or spaces between them), in order to read values from the abscissa (bottom) and ordinate (vertical) sides of the graph.

This chapter is organized first by materials to be used (wood and steel in various forms), then by specific strengthening applications, such as the aforementioned beams (bending members), columns, and beam-columns.

Wood Availability and Use

Appendix C, Typical Stockage - Local Lumberyards, Reference [2], is short and is recommended for complete reading by the reader/user.

Specifically, the predesigns reported on below (Appendices A1 and A2) used generally available stress graded lumber in one relatively strong and one relatively weak grade and species for each of two size ranges - one pair of grades for 2x3s⁷ and 2x4s (Light Framing; Construction grade for strong, and Standard grade for weak) and one pair of grades for 2x6s and 2x8s (Joists and Planks; No. 1 grade for strong, and No. 2 grade for weak). These choices are shown in Table 1B, Appendix C [2],⁸ complete with the predesigns' stresses as underlined in that Table and used below (Appendices A1 and A2). Tables 1A and 2, Appendix C [2], show the complete list from which the grade choices were made. (A later complete list is provided by Table B1-2, Appendix B1 herein.)

Lumberyards have shirt-pocket size booklets, published by grading associations (list in Reference [2] of Appendix B2 herein) giving stress grading data by lumber kind, type and size; see also Reference [11].⁹ In any case, try to use construction grades/stress-graded wood members; if stress data are unknown, simply use the tables/figures that follow (e.g., as in Appendices A1 and A2) and choose those calling for "lower strength stringers" or similar notation.

Although specific data have not yet been published/distributed, strong indications are appearing, among the professional engineers/architects in the research community, that lumber grading in too many areas and instances to be ignored, has not been up to standards achieved in the past; there may be well-founded reasons for this (the increasing proportion of second growth timber in the market), and thus not quality of work alone. At any rate, an artisan familiar with wood, even only casually, can use the shirt-pocket size grading booklets and their data, as mentioned above, plus some careful reading, to check or redo the grading work on any wood materials that become available for upgrading use. The regrading may not be as precise as that done by one regularly working in the field, but that is not the point here. Further, the artisan (e.g., one semiskilled in carpentry) need not follow upgrading guidance alone but, for an example, can see to it that, if he/she must use a wood member as a beam and must use one that has a sound knot near an edge, the sound knot is put in the top edge of the (single-span, simply-supported) beam (compressive stress) rather than in the bottom edge (tensile stress).

⁷ Nominal (actual) dimensions are 2x3 (1.5x2.5), 2x4 (1.5x3.5), 2x6 (1.5x5.5), and 2x8 (1.5x7.25) inches.

⁸ Delete "Select Structural" in left column of table.

⁹ Copies of References [11] and [12], one each, are furnished with each copy of this report sent to Distribution List addressees shown herein.

For plywoods, the predesigns (Appendices A1, A2, and A3) used primarily plywood grade Underlayment Interior (American Plywood Association (APA)) in Species Groups (of both face plies) #1 and #3, but the results also cover plywood grades Underlayment Exterior (APA), C-D Interior (APA), and C-C Exterior (APA), all in Species Groups #1 and #3; nominal thicknesses used were 1/2", 5/8", and 3/4". Additionally, plywood grade 2.4.1 Sturd-I-Floor Interior (APA), manufactured only in Species Group #1, was used in 1-1/8" nominal thickness, both alone and in combination with some of the thinner plywood grades just mentioned (the results also cover 2.4.1 Sturd-I-Floor Exterior (APA) used in the same thickness). All plywood grades used in predesigns are the most plentiful and were assumed to be planned for use under dry conditions (equilibrium moisture content less than 16%).¹⁰

Each sheet of plywood should bear an APA (American Plywood Association) Grade-Trademark stamp on one of its faces. Typical markings are shown in the fourth column of the table on page 14 of Reference [12].⁹ The reader/user of this report is urged to look for and use such stamped markings, because lumberyards are prone to apply a local terminology, contrary to the formal terminology and that one stamped on the sheet of plywood; for example, a usage local to the author's home area is to advertise and describe a plywood grade as "CDX" (both orally and printed), even "CD Exterior", a plywood "grade" that is not listed in those of the APA. Instead, the plywood grade of these sheets is actually C-D Interior (APA) with exterior glue, a plywood grade that can be found in the listing of APA grades, meaning that geometric dimensions, allowable stresses, etc., can be obtained (see Reference [12]⁹).

It is recommended that the stress-graded lumber user consider obtaining a copy of Reference [11].⁹ Similarly but for plywood, Reference [12].⁹

A. Plywood Stressed-Skin Panels (Two-Sided)¹¹ as Closures

Appendix A1, Plywood Stress-Skin Panels (Two-Sided Only) as Closures - Design and Fabrication, includes a detailed treatment of the subject, aimed at the designer (engineer or architect); certain sections would be, however, of interest to the artisan reader, who might choose to gain an overview of Appendix A1 through use of its lists of Contents, Tables and Figures (pages A1-iii and -iv).

¹⁰ If dry conditions do not apply, all plywood must have "Exterior Glue" (so stamped); blast resistance shown in tables of Appendices A1, A2, and A3 would be reduced about 50% (conservatively; full redesigns are needed for a better estimate).


¹¹ Abbreviated as PSSPs herein.

Lumber ("2-by") sizes and grades considered for use in building PSSPs are discussed in the preceding section, as are plywood grades and nominal thicknesses. Figure 1 shows a cutaway perspective view of a 4-stringer PSSP, which also illustrates both continuous and non-continuous headers, as well as splice-plate installation. The latter may have little use herein, because closures are not expected to be needed in lengths longer than the 8-ft (sometimes 12-ft) plywood sheets that are available in plywood stocks of lumberyards. Another view (this one dimensioned) of a similar PSSP is shown by Figure A1-1A of Appendix A1. Both views show PSSPs with one outside stringer inset 1 in. and the other outside stringer projecting 3/4 in. so as to provide tongue-and-groove behavior among side-by-side panels; such detailing is perhaps impractical for the rapid construction of expedient option closures during a one- to three-day warning period, and such detailing is not recommended for other (mostly strength) reasons as well.

To obtain the strength benefits of stressed-skin structural behavior,¹⁰ PSSPs are built with the plywood face plies running parallel to the stringers, which must be joined to the plywood by either nailed-groove or pressure-glued construction (the latter is better so should be used if facilities are available therefor). See the Fabrication section, Appendix A1, for details.

Table A1-1 of Appendix A1 presents 248 designs in a form for direct reading: Columns 1-4 present nominal thickness and Face Ply Species Group for the top and bottom plywood skins of the PSSP designs; columns 5-6 give the nominal size (2x4 to 2x8) and number of stringers (per 48-in. wide PSSP), with the latter showing 4, 5, 7, and 9, but 6 or 8 may be used by taking values (in columns 7 and beyond) between 5-7 and 7-9, respectively; columns 7-8 show the PSSP required bearing length on each end support (in addition to the clear span dimension), in terms of bearing length on the plywood bottom skin and on the stringer bottom edge, respectively (the latter happens to be controlling in all designs); the remaining columns show, for each of the designs, the PSSP's estimated peak air blast overpressure resistance (psi) for clear spans from 2 to 12 ft by half-ft increments, but omitting any value below 5 psi. In a particular application, the clear span for the blast closure will be known, as will availability (sizes, grades, etc.) of plywood and stringers; from this point one might proceed as follows:

(1) Consider that the data presented covers four plywood grades in three nominal thicknesses and two face ply species grades, plus a fifth grade in one nominal thickness and one face ply species, and the plywood combinations are each used in predesigns with two stringer strengths (termed lower and higher in Table A1-1) - all as described in the preceding section, Wood Availability and Use.



Source: Reference 1 of Appendix A1

FIGURE 1 TYPICAL TWO-SIDED PLYWOOD STRESSED-SKIN PANEL

(2) Consider the data for, say, the 6th PSSP design (with 7 stringers), Table A1-1: Top and bottom skins nominal thickness are 3/4" and 1/2", respectively, both in Face Ply Species Group #3, and the 7 (lower strength) stringers are 2x4s (nominal dimensions).

(3) Required bearing length at each end of the PSSP, in addition to the clear span length, would be the larger value of Columns 7-8, or 3.5 in.

(4) For a clear span of 2.5 ft, the estimated peak air blast (side-on) overpressure resistance would be 9 psi (Column 10).

(5) Equivalent free-field air blast peak overpressure to the 9 psi just found, which is for overpressure when applied side-on, would be 4 psi free-field air blast peak overpressure if applied fully reflected (i.e., head-on); the peak blast pressure felt by the PSSP would be 9 psi in either case, if taxed to its estimated design resistance. The graph on page B1-26, Appendix B1, may be used to find such "side-on" versus "head-on" equivalent free-field air blast peak overpressures, in either English or SI (metric) units (it is sufficiently accurate for purposes herein to use $1 \text{ kg/cm}^2 = 100 \text{ kPa} = 100 \text{ kN/m}^2$ in reading the graph).

(6) For PSSP widths less than 48 inches: Convert the planned PSSP width and stringer spacing to a 48-in. wide equivalent PSSP; select the equivalent 48-in. PSSP number of stringers so that its stringer spacing is equal to or wider than that in the planned PSSP. Find the applicable overpressure value for the known clear span, as above; such value may be used without reduction for PSSP widths of 24 in. or more, but it is recommended that it be reduced linearly from 0% to 50% for PSSP widths of 24" to 8", respectively, with the latter being the narrowest width recommended for use (this recommendation is adapted from Reference [2] on page A1-29). NOTE: Panel width, as used throughout this section, is always measured perpendicular to the span direction of the PSSP.

(7) Selection of a particular PSSP design for planned use would probably be by trial-and-check repeated use of Steps 2 through 6 above.

An upgrading example using the above PSSP as a horizontal closure is shown on page A1-22 and illustrates the case of apportioning the PSSP's load capacity between peak air blast loading and soil (for nuclear radiation shielding) loading.

B. Plywood Stressed-Skin Panels (Two-Sided) as Columns & Beam-Columns

Appendix A2 deals with this subject and includes a continuation of the design procedure of Appendix A1, thus requiring frequent reference work between the two appendices. Aside from the continuation of the design procedure, the preceding section on PSSPs as closures, and its Figure 1, should be reviewed by the reader/user, as should be certain descriptive figures and general sections of Appendix A1, perhaps espe-

cially the section on fabrication of PSSPs. Table A2-1 of Appendix A2 is a listing of the computer program developed for the design procedures in both Appendices A1 and A2, thus the program will handle design/analysis of PSSPs, whether for use as beams, columns, or beam-columns. Table A2-2 provides data on PSSP designs similar to that provided by Table A1-1 of Appendix A1, but the former has the design data for columns and beam-columns, and includes only PSSPs that have the same plywood top and bottom skins. Table A2-2 shows, for column use, the total axial dynamic/impact load (in kips, or 1000s of pounds) that each PSSP may carry, the principal (and perhaps only real) use of the data. Also shown, for beam-column use, is data on the beam-column capacity of each PSSP in terms of an axial load equal to 20%, 40%, 60%, and 80% of the pure column use load, with each percentage related to the capacity remaining for lateral loads in terms of psi. All axial loads are related to a 48 in. wide PSSP.

Appendix A2 includes a sheet, PSSP Upgrading Example - Column, showing a sample calculation for a PSSP acting as a column, axially loaded (only) with both air blast and soil for fallout radiation shielding.

C. Plywood Panels as Closures

Appendix A3, Plywood Use for Closures - Design, covers the design of plywood panels as closures over apertures such as those found in basements. The design procedure applies to panels supported on two opposite sides of an aperture, or on all four sides.

The design procedure was used to develop the predesigns shown by Tables A3-1 and -2. An example of use is as follows: Referring to Table A3-1A, assume that 3/4 in. nominal thickness plywood is available in CD-PLUGGED INTERIOR (APA) grade in Face Ply Group 3 (so stamped on each sheet of plywood), and find from the table that one should refer to Table A3-1B, Block Numbers 8 and 16, for 1/2" and 3/4" plywood, respectively, meaning that Block No. 16 applies to this example; further, one should use the second line of that Block for Face Ply Group 3, in which line one finds values of (free field, side-on, long duration) peak air blast overpressure, in psi, for seven values of clear span, in inches, such as 20 psi for an 8-inch clear span. Attention should be given to the footnote of Table A3-1B. So far span conditions dealt with have been one-way simply-supported.

Two-way (supported on all four sides) span conditions are handled by further referring to Table A3-2 where one finds that, for Block Number 16 (of Tables A3-1B), the assumed plywood would have its 20 psi/ 8-inch span strength increased by 19% if supported on all four sides of a square opening/aperture 8"x8" (1:1 ratio of longer to shorter clear spans).

Appendix A3 contains further details if desired by the user. If available plywood is not one of the 10 grades entered in Table A3-1A (including 2 multi-grade entries), recourse to the design procedure starting on page A3-3 will be necessary.

D. Wood Beams and Columns

Appendix B1, Wood Beam and Column Design - Simply Supported, covers sizing (design/analysis) of wood beams - whether used solidly (side-by-side, on edge or flatwise) or spaced as in floor joists and roof rafters, and also whether used single-span or continuous over several spans, all simply supported - as well as wood columns. Further, different treatment is shown for wood beams used solidly, when covered with a thin sheet of plywood (repetitive-member use) or without a plywood cover (single-member use), because the allowable flexural stress f_b is different for these two uses.

Appendix B1 has two major sections, Wood Beams - Simply Supported and Wood Columns - Simple Supports. A design/analysis procedure is provided in each of these two major sections.

An illustrative example is presented in paragraph (5), page B1-13, of Appendix B1, for the use of wood beams solidly side-by-side, with a thin plywood covering. The next paragraph (6) deals with the same problem, but with the thin plywood covering omitted.

Sizing of wood beams used at spacings of 12, 16, and 24 in. is covered by an illustrative example in paragraph b., page B1-14, Appendix B1. Note: The results of this sizing differs from the example shown in Appendix B2, Home Basements Upgrading in Host Areas, because the latter results are based on interior blast limited to 5 psi or less on the floor above the basement, resulting in the use of a gradual rise time; in contrast, the treatment in Appendix B1 considers the blast loading rise time as zero. The results in Appendix B2 can be converted to match those of Appendix B1 by multiplying the former by a factor of 2/3.

For correcting the blast resistance found for a simply supported beam over a single-span to a simply supported beam extending continuously over two, three, four, or five equal spans of the same individual span length, a procedure and tabulation of correction factors is provided on page B1-14, Appendix B1.

For the sizing (design/analysis) of wood columns on simple supports, a design procedure is provided beginning on page B1-15, Appendix B1. A numerical example begins on page B1-22 and uses for its solution the table and graphs of Figure B1-2. A discussion of the adequacy of end bearing in columns follows.

Review, light or heavy, of Appendix B2, Home Basements Upgrading in Host Areas, is recommended for the reader/user concerned with use of

wood members in upgrading, both beams and columns; numerical examples and blast resistance values for lower and higher strength woods are included.

E. Peak Blast Resistance - Side-On versus Head-on

Finally, a conversion graph is given in Appendix B1 (page B1-26) for converting free field overpressures up to 50 psi when applied side-on, to an equal value of free field overpressure applied head-on, or fully reflected; "equal" in this sense means equal in peak blast pressure felt by the member (for example, the peak blast pressure felt by a structural member from 45 psi applied side-on is equal to 16 psi applied head-on (fully reflected)).

F. Steel Plates, Sheets, and Shapes

Appendix E1, Structural Steel Local Availability and Use for Blast Shelter Upgrading, is recommended for complete reading by the reader/user of this report.

Appendix D1, Blast-Resistant Design/Analysis of Steel Members, discusses steel design generally, structural steel material properties and strength/resistance expressions. Tables present the stresses used for sizing members (primarily plates and sheets), based on the ASTM designation for the steel, designations that are regularly used by steel suppliers. An applications section begins on page D1-9, which covers the sizing of steel plates as closures, acting either as one-way or two-way flat plates on simple supports; the section includes numerical examples carried along with the discussion. The example uses a table and graph, figure D1-1, for solving the one-way plate sizing problem, with correction factors for all steels, and correction factors for two-way plates from the one-way plate graphical solution results.

Use of steel plates and shapes may be considerably limited by weight-handling limitations where no equipment is available, other than hand labor. (Figure D1-1 solutions stop at around 500 pounds maximum weight of the steel member.) The use of steel shapes is not covered further in this report.

Chapter 7

SHELTER FOR KEY WORKERS

There is a need for shelters upgraded to the 30 to 50 psi air blast (peak free field overpressure) range. Such shelters will be in the "risk" areas briefly mentioned on page 2 herein; this shelter is needed at locations within 15-minutes travel time from each key worker's place of work. Such shelter has also been mentioned above in paragraph (3) on page 12 where it is stated that "Work to date has indicated a low probability of getting this protection level of shelter in existing buildings, unless a truly high level of manpower and material resources is spent and, even then, serious questions need to be first answered by tests concerning the blast resistance that can be expected from existing exterior basement walls."

Also discussed earlier (paragraph D, page 18), is the very serious problem of lack of knowledge/test results on the ultimate blast resistance capacity (through collapse) of existing exterior basement walls in buildings considered for shelter use.

Table 2 presents the results of existing structures evaluation (ESE) work done by James E. Beck [8] on 11 buildings across the United States; these NSS buildings are part of the 210-building "RTI statistical sample" often used for FEMA studies, both research and operational. Table 2, presenting some results of the ESE work, also has information added under this project, as shown along the right side of each sheet of the table. Attention is particularly invited to the data on "TYPICAL BASEMENT WALL" on the right side of the first sheet of the table; the data point up the discussion of the existing exterior basement wall problem mentioned earlier and cited above. Whether one considers the mean or 1% probability value (of the incipient collapse overpressures) shown in the data, as on the right of Table 1, the overall results show very little promise for upgrading existing basements to the 30 to 50 psi blast range; whether one looks at slabs (RCS), beams (RCB), girders (RCG), or joists (RCJ), of reinforced concrete, the prospects are bleak for their united floor strength exceeding a value considerably below the 30 to 50 psi range. Momentarily ignoring the basement wall problem, extensive upgrading would be required for all structural members (almost without exception) and for each closure's support frame, to reach the desired overpressure range. Cost effectiveness, in terms of expenditures of manpower and materials, could well dictate use of field type, expedient shelters, or other alternatives.

One alternative is the use of conventional large diameter pipe and culvert materials (8 ft i.d. for example); such use has been proven (by nuclear field tests) to provide high degrees of protection in a buried configuration. These include R/C pipe, corrugated steel culvert materials of round and "cattle pass" (Junior underpass) cross sections, and arch shaped (semi-circular) multi-plate corrugated steel (ammunition magazine) structures [4, p. 6-119 to -134].

TABLE 2. RESULTS FROM EXISTING STRUCTURES EVALUATION OF ELEVEN NSS BUILDINGS
11/26/79

| Case | Element Type | L (in.) | L (in.) | b (in.) | h (in.) | f _c (psi) | f _y (psi) | Support Case | Reinforcing Ratios at Cross Sections | | | | | | Tensile Membrane Steel Ratio | | Collapse Overpressure | | Incipient Collapse | |
|---|--------------|---------|---------|---------|---------|----------------------|----------------------|--------------|---|--------|--------|--------|--------|--------|------------------------------|--------|-----------------------|-----------------|--------------------|------------------|
| | | | | | | | | | 1 | 2 | 3 | 4 | 5 | 6 | Short | Long | Mean (psi) | Std. Dev. (psi) | Mean Std. (psi) | Prob. Dev. (psi) |
| Building 100, U.S. Post Office (RCF) | | | | | | | | | | | | | | | | | | | | |
| 1a | RCB-1 | 337 | 1,320 | 12 | 12 | 3,000 | 53,000 | 1 | 0.0172 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 5.49 | 0.53 | 4.00 | 6.49 |
| 1b | RCB-1 | 168 | 1,320 | 12 | 12 | 3,000 | 53,000 | 5 | 0.0172 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 23.00 | 2.76 | 19.24 | 25.76 |
| 1c | RCB-1 | 112 | 1,320 | 12 | 12 | 3,000 | 53,000 | 5 | 0.0172 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 0.0013 | 51.23 | 4.39 | 46.84 | 55.62 |
| 2a | RCB-2 | 223 | 2,320 | 18 | 18 | 3,000 | 53,000 | 5 | 0.0100 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 5.16 | 0.72 | 4.44 | 6.88 |
| 2b | RCB-2 | 111 | 2,320 | 18 | 18 | 3,000 | 53,000 | 5 | 0.0100 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 22.72 | 2.83 | 19.89 | 25.55 |
| 2c | RCB-2 | 74 | 2,320 | 18 | 18 | 3,000 | 53,000 | 5 | 0.0100 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 58.33 | 4.68 | 53.65 | 58.33 |
| 3a | RCB-3 | 197 | 1,900 | 12 | 12 | 3,000 | 53,000 | 5 | 0.0090 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 28.66 | 3.00 | 25.66 | 31.66 |
| 3b | RCB-3 | 98 | 1,900 | 12 | 12 | 3,000 | 53,000 | 5 | 0.0090 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 45.71 | 7.05 | 38.66 | 47.76 |
| 4a | RCB-4 | 104 | 1,900 | 12 | 12 | 3,000 | 53,000 | 5 | 0.0139 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 5.03 | 0.62 | 4.41 | 6.62 |
| 4b | RCB-4 | 50 | 1,900 | 12 | 12 | 3,000 | 53,000 | 5 | 0.0139 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 25.60 | 2.57 | 23.03 | 28.17 |
| 4c | RCB-4 | 25 | 1,900 | 12 | 12 | 3,000 | 53,000 | 5 | 0.0139 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 59.47 | 6.92 | 52.55 | 66.39 |
| 5a | RCB-5 | 17 | 360 | 3 | 3 | 3,000 | 53,000 | 6 | 0.0048 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 107.09 | 12.07 | 95.02 | 123.16 |
| 5b | RCB-5 | 17 | 360 | 3 | 3 | 3,000 | 53,000 | 6 | 0.0048 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 40.23 | 2.91 | 37.32 | 43.13 |
| 5c | RCB-5 | 17 | 360 | 3 | 3 | 3,000 | 53,000 | 6 | 0.0048 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 163.70 | 12.44 | 151.26 | 186.14 |
| 6a | RCB-6 | 100 | 6,231 | 17 | 17 | 3,000 | 53,000 | 51 | 0.0237 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 3.31 | 0.51 | 2.80 | 3.81 |
| 6b | RCB-6 | 100 | 6,231 | 17 | 17 | 3,000 | 53,000 | 51 | 0.0237 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 14.77 | 1.46 | 13.31 | 16.04 |
| 6c | RCB-6 | 100 | 6,231 | 17 | 17 | 3,000 | 53,000 | 51 | 0.0237 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 35.38 | 4.26 | 29.12 | 40.64 |
| 6d | RCB-6 | 100 | 6,231 | 17 | 17 | 3,000 | 53,000 | 51 | 0.0237 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 0.0003 | 62.62 | 7.29 | 55.33 | 71.96 |
| Building 110, Navy B. Lendis State Hospital (RCF) | | | | | | | | | | | | | | | | | | | | |
| 1a | RCB-1 | 169 | 1,552 | 7 | 7 | 3,300 | 53,000 | 7 | 0.0074 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 5.20 | 0.55 | 4.65 | 5.90 |
| 2a | RCB-1 | 204 | 1,552 | 7 | 7 | 3,300 | 53,000 | 6 | 0.0127 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 3.05 | 0.44 | 2.61 | 3.49 |
| 2b | RCB-1 | 102 | 1,552 | 7 | 7 | 3,300 | 53,000 | 6 | 0.0127 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.60 | 0.66 | 7.49 | 9.70 |
| 2c | RCB-1 | 60 | 1,552 | 7 | 7 | 3,300 | 53,000 | 7 | 0.0127 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 17.03 | 2.00 | 15.03 | 19.03 |
| 3a | RCB-2 | 164 | 254 | 14 | 14 | 3,300 | 53,000 | 7 | 0.0037 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 3.31 | 0.49 | 2.82 | 3.94 |
| 3b | RCB-2 | 164 | 254 | 14 | 14 | 3,300 | 53,000 | 7 | 0.0037 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 6.13 | 0.83 | 5.30 | 7.19 |
| 3c | RCB-2 | 81 | 254 | 14 | 14 | 3,300 | 53,000 | 5 | 0.0093 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 14.36 | 1.42 | 12.94 | 16.18 |
| 4a | RCB-3 | 254 | 254 | 12 | 12 | 3,300 | 53,000 | 6 | 0.0111 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 7.79 | 0.83 | 6.96 | 8.58 |
| 4b | RCB-3 | 128 | 254 | 12 | 12 | 3,300 | 53,000 | 6 | 0.0291 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 4.33 | 0.53 | 3.80 | 5.14 |
| 4c | RCB-3 | 65 | 254 | 12 | 12 | 3,300 | 53,000 | 5 | 0.0291 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 12.66 | 1.26 | 11.40 | 14.86 |
| 4d | RCB-3 | 128 | 254 | 12 | 12 | 3,300 | 53,000 | 5 | 0.0291 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 19.17 | 1.82 | 17.35 | 20.99 |
| 5a | RCB-5 | 154 | 20 | 20 | 20 | 3,300 | 53,000 | 7 | 0.0245 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 17.06 | 1.72 | 15.34 | 19.86 |
| 5b | RCB-5 | 154 | 20 | 20 | 20 | 3,300 | 53,000 | 6 | 0.0245 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 5.33 | 0.52 | 4.81 | 5.99 |
| 5c | RCB-5 | 154 | 20 | 20 | 20 | 3,300 | 53,000 | 6 | 0.0245 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 17.94 | 1.83 | 16.11 | 20.28 |
| Building 111, Grant Building (STF) | | | | | | | | | | | | | | | | | | | | |
| 1a | RCB-1 | 18,331 | -- | 2,512 | 2,512 | 44,000 | 44,000 | 6 | 0.0040 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 14.61 | 0.59 | 13.73 | 15.89 |
| 2a | RCB-1 | 216 | -- | 12,512 | 12,512 | 44,000 | 44,000 | 71 | 0.0040 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 67.59 | 6.87 | 58.72 | 76.48 |
| 2b | RCB-1 | 100 | -- | 5,21 | 5,21 | 44,000 | 44,000 | 51 | 0.0237 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 7.27 | 0.70 | 6.57 | 8.14 |
| 2c | RCB-1 | 72 | -- | 5,21 | 5,21 | 44,000 | 44,000 | 51 | 0.0237 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 15.13 | 1.44 | 13.69 | 16.98 |
| 3a | STB-1 | 218 | -- | 12,04 | 12,04 | 41,000 | 41,000 | 6 | 0.0237 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 34.28 | 3.43 | 29.85 | 38.67 |
| 3b | STB-1 | 199 | -- | 12,04 | 12,04 | 41,000 | 41,000 | 6 | 0.0237 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 10.97 | 1.60 | 9.37 | 13.62 |
| 3c | STB-1 | 177 | -- | 12,04 | 12,04 | 41,000 | 41,000 | 6 | 0.0237 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 39.25 | 4.37 | 33.88 | 44.85 |
| | | | | | | | | | (S=144.88 in ² , 16C163) (S=144.88 in ² , 16C163) (S=144.88 in ² , 16C163) | | | | | | | | 90.63 | 12.86 | 78.15 | 107.32 |

* Steel member, thus Mean and Standard Deviation values apply unchanged from regular ESE values (i.e., no problems with beam-action stress reversals, as there are with R/C)

** Based on added girder lines at midspan (.2B) or third-points (.2C), which would increase existing girders as if upgraded (.3B and .3C, respectively). However, added girder lines would require new columns and footings/caissons carried through from five to one basements (depending on which basement(s) are to be upgraded). Even so, basement walls are non-bearing, inadequate, and infeasible to upgrade; some of first basement wall is 100% abovegrade and penetrated by garage doors.

Incipient Collapse
Overpr (Tens. Membr.)
Mean Std. 1%
Dev. Prob.
(psi) (psi) (psi) (psi)

6.51 0.78 4.69
10.29 0.92 8.15
14.06 1.33 10.97

58.71 7.05 42.30

TYPICAL BASEMENT WALL
Lat/vert soil 1%
press. ratio Prob.
100% 6.2
50% 12
15% (unlikely), 40

14.68 1.46 11.28
24.64 1.83 20.38
22.14 2.23 16.95

21.40 4.14 16.66**
32.34 3.11 24.81**
29.08* 29.08*
60.90*

Table 2 (continued)

| Case | Element Type | L _o (in.) | L _b (in.) | L _h (in.) | b _b (in.) | h _b (in.) | f _c (psi) | Support Case | Reinforcing Ratios at Cross Sections | | | | | | | | Tensile Membrane Steel Ratio | | Incipient Collapse Overpressure | | | | Incipient Collapse Overpr (Tens. Membr.) Mean Std. 1% Dev. Prob. (psi) (psi) (psi) (psi) | |
|--|--------------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|--------------|--------------------------------------|--------|--------|--------|--------|--------|--------|--------|------------------------------|------|---------------------------------|-----------------------|--------------------|--------------------|---|--|
| | | | | | | | | | 1 | | 2 | | 3 | | 4 | | Short | Long | Mean (psi) | Std. Dev. (psi) | 10% Prob. (psi) | 90% Prob. (psi) | | |
| | | | | | | | | | p | p' | p | p' | p | p' | p | p' | | | | | | | | |
| Building 136, First Federal Savings & Loan Assn. (RCF) | | | | | | | | | | | | | | | | | | | | | | | | |
| .1a | RCB-1 | 16 | 62 | 2 | 3,000 | 56,000 | 6 | 6 | 0.0036 | 0.0 | 0.0036 | 0.0 | 0.0036 | 0.0 | 0.0036 | 0.0 | 12.40 | 1.20 | 10.06 | 13.93 | | | | |
| .1b | RCB-1 | 16 | 62 | 2 | 3,000 | 56,000 | n/a | n/a | 0.0036 | 0.0 | 0.0036 | 0.0 | 0.0036 | 0.0 | 0.0036 | 0.0 | 70.86 | 6.12 | 63.01 | 76.70 | | | | |
| .2A | RCB-1 | 160 | 42 | 6.10 | 14 | 3,000 | 53,000 | 7T | 0.0039 | 0.0039 | 0.0039 | 0.0 | 0.0040 | 0.0040 | 0.0040 | 0.0 | 3.53 | 0.49 | 2.90 | 4.16 | | | | |
| .2B | RCB-1 | 84 | 42 | 6.10 | 14 | 3,000 | 53,000 | 5T | 0.0039 | 0.0039 | 0.0039 | 0.0 | 0.0040 | 0.0040 | 0.0040 | 0.0 | 9.70 | 1.23 | 8.13 | 11.20 | | | | |
| .3A | RCB-1 | 220 | 42 | 6.10 | 14 | 3,000 | 53,000 | 6 | 0.0113 | 0.0113 | 0.0113 | 0.0 | 0.0113 | 0.0113 | 0.0113 | 0.0113 | 4.29 | 0.56 | 3.50 | 5.00 | | | | |
| .3B | RCB-1 | 116 | 42 | 6.10 | 14 | 3,000 | 53,000 | 7 | 0.0113 | 0.0113 | 0.0113 | 0.0 | 0.0113 | 0.0113 | 0.0113 | 0.0113 | 14.00 | 1.65 | 11.88 | 16.11 | | | | |
| .3C | RCB-1 | 76 | 42 | 6.10 | 14 | 3,000 | 53,000 | 5 | 0.0113 | 0.0113 | 0.0113 | 0.0 | 0.0113 | 0.0113 | 0.0113 | 0.0113 | 20.70 | 2.07 | 18.05 | 23.36 | | | | |
| .3D | RCB-1 | 220 | 42 | 6.10 | 14 | 3,000 | 53,000 | 6 | 0.0113 | 0.0113 | 0.0113 | 0.0 | 0.0113 | 0.0113 | 0.0113 | 0.0113 | 8.50 | 0.63 | 7.46 | 9.57 | | | | |
| Building 167, Lafayette Towers Building 2 (RCF) | | | | | | | | | | | | | | | | | | | | | | | | |
| .1a | RCFP-1 | 240 | 240 | 10 | 3,000 | 53,000 | 11 | 11 | 0.0030 | 0.0 | 0.0030 | 0.0 | 0.0030 | 0.0030 | 0.0030 | 0.0 | 6.31 | 0.76 | 5.33 | 7.29 | | | | |
| .1b | RCFP-1 | 240 | 240 | 10 | 3,000 | 53,000 | 11 | 11 | 0.0030 | 0.0 | 0.0030 | 0.0 | 0.0030 | 0.0030 | 0.0030 | 0.0 | 1.63 | 0.01 | 1.62 | 1.64 | | | | |
| .1c | RCFP-1 | 120 | 120 | 10 | 3,000 | 53,000 | 11 | 11 | 0.0030 | 0.0 | 0.0030 | 0.0 | 0.0030 | 0.0030 | 0.0030 | 0.0 | 30.03 | 3.96 | 25.75 | 35.91 | | | | |
| .1d | RCFP-1 | 120 | 120 | 10 | 3,000 | 53,000 | 11 | 11 | 0.0030 | 0.0 | 0.0030 | 0.0 | 0.0030 | 0.0030 | 0.0030 | 0.0 | 8.77 | 0.02 | 8.75 | 8.79 | | | | |
| .1e | RCFP-1 | 240 | 240 | 10 | 3,000 | 53,000 | 2 | 2 | 0.0030 | 0.0 | 0.0030 | 0.0 | 0.0030 | 0.0030 | 0.0030 | 0.0 | 9.13 | 0.98 | 7.87 | 10.39 | | | | |
| .1f | RCFP-1 | 120 | 120 | 10 | 3,000 | 53,000 | 1 | 1 | 0.0030 | 0.0 | 0.0030 | 0.0 | 0.0030 | 0.0030 | 0.0030 | 0.0 | 19.90 | 2.59 | 16.57 | 23.22 | | | | |
| Building 168, State Wildlife Conservation Building (RCF) | | | | | | | | | | | | | | | | | | | | | | | | |
| .1a | RCB-1 | 192 | -- | 6 | 3,000 | 44,000 | 6 | 6 | 0.0094 | 0.0 | 0.0094 | 0.0 | 0.0140 | 0.0025 | 0.0140 | 0.0025 | 9.95 | 1.07 | 8.52 | 11.32 | 20.81 | | | |
| .1b | RCB-1 | 192 | -- | 6 | 3,000 | 44,000 | 7 | 7 | 0.0094 | 0.0 | 0.0094 | 0.0 | 0.0140 | 0.0025 | 0.0140 | 0.0025 | 20.81 | 2.34 | 17.81 | 23.81 | 2.34 | | | |
| .2A | RCB-1 | 157.5 | 46 | 15.5 | 3,000 | 44,000 | 5 | 5 | 0.0086 | 0.0 | 0.0086 | 0.0 | 0.0126 | 0.0034 | 0.0126 | 0.0034 | 7.15 | 0.96 | 5.92 | 8.39 | 11.47 | | | |
| .2B | RCB-1 | 78.75 | 46 | 15.5 | 3,000 | 44,000 | 7 | 7 | 0.0086 | 0.0 | 0.0086 | 0.0 | 0.0126 | 0.0034 | 0.0126 | 0.0034 | 13.59 | 1.71 | 11.40 | 15.79 | 1.44 | | | |
| .3A | RCB-1 | 233.5 | 46 | 15.5 | 3,000 | 44,000 | 7 | 7 | 0.0131 | 0.0 | 0.0131 | 0.0 | 0.0126 | 0.0034 | 0.0126 | 0.0034 | 3.36 | 0.58 | 2.61 | 4.10 | 8.11 | | | |
| .3B | RCB-1 | 116.75 | 46 | 15.5 | 3,000 | 44,000 | 5 | 5 | 0.0131 | 0.0 | 0.0131 | 0.0 | 0.0126 | 0.0034 | 0.0126 | 0.0034 | 8.05 | 0.95 | 7.64 | 10.46 | 12.97 | | | |
| .3C | RCB-1 | 77.83 | 46 | 15.5 | 3,000 | 44,000 | 5 | 5 | 0.0131 | 0.0 | 0.0131 | 0.0 | 0.0126 | 0.0034 | 0.0126 | 0.0034 | 21.49 | 2.53 | 18.24 | 24.73 | 19.84 | | | |
| Building 206, Fitzsimmons General Hospital (RCF) | | | | | | | | | | | | | | | | | | | | | | | | |
| .1a | RCB-1 | 76 | 266 | 4 | 3,000 | 44,000 | 6 | 6 | 0.0073 | 0.0 | 0.0073 | 0.0 | 0.0073 | 0.0073 | 0.0073 | 0.0073 | 6.54 | 0.54 | 5.95 | 7.22 | | | | |
| .1b | RCB-1 | 76 | 133 | 4 | 3,000 | 44,000 | 6 | 6 | 0.0073 | 0.0 | 0.0073 | 0.0 | 0.0073 | 0.0073 | 0.0073 | 0.0073 | 4.79 | 0.83 | 7.71 | 9.84 | | | | |
| .2A | RCB-1 | 266 | 133 | 12 | 3,000 | 44,000 | 4 | 4 | 0.0138 | 0.0 | 0.0138 | 0.0 | 0.0160 | 0.0064 | 0.0160 | 0.0064 | 4.79 | 0.56 | 4.07 | 5.82 | 18.96 | | | |
| .2B | RCB-1 | 133 | 133 | 12 | 3,000 | 44,000 | 4 | 4 | 0.0138 | 0.0 | 0.0138 | 0.0 | 0.0160 | 0.0064 | 0.0160 | 0.0064 | 13.86 | 1.67 | 11.72 | 15.99 | 2.28 | | | |
| .3A | RCB-1 | 255 | 16 | 28 | 3,000 | 44,000 | 7 | 7 | 0.0101 | 0.0 | 0.0101 | 0.0 | 0.0074 | 0.0076 | 0.0074 | 0.0076 | 4.92 | 0.52 | 4.25 | 5.80 | 3.25 | | | |
| .3B | RCB-1 | 127.5 | 16 | 28 | 3,000 | 44,000 | 6 | 6 | 0.0101 | 0.0 | 0.0101 | 0.0 | 0.0074 | 0.0076 | 0.0074 | 0.0076 | 17.09 | 2.15 | 14.32 | 19.85 | 0.41 | | | |
| .3C | RCB-1 | 85 | 16 | 28 | 3,000 | 44,000 | 5 | 5 | 0.0101 | 0.0 | 0.0101 | 0.0 | 0.0074 | 0.0076 | 0.0074 | 0.0076 | 28.50 | 3.46 | 24.07 | 32.93 | 2.29 | | | |
| .3D | RCB-1 | 255 | 16 | 28 | 3,000 | 44,000 | 6 | 6 | 0.0101 | 0.0 | 0.0101 | 0.0 | 0.0074 | 0.0076 | 0.0074 | 0.0076 | 8.55 | 0.96 | 7.31 | 9.78 | 5.16 | | | |
| .4A | RCB-2 | 190 | 106 | 16 | 3,000 | 44,000 | 6 | 6 | 0.0073 | 0.0 | 0.0073 | 0.0 | 0.0073 | 0.0073 | 0.0073 | 0.0073 | 3.20 | 0.30 | 2.90 | 3.46 | 2.45 | | | |
| .4B | RCB-2 | 177 | 106 | 12 | 3,000 | 44,000 | 3 | 3 | 0.0060 | 0.0 | 0.0060 | 0.0 | 0.0073 | 0.0 | 0.0073 | 0.0073 | 6.06 | 0.73 | 5.13 | 6.99 | 0.63 | | | |
| .5A | RCB-2 | 88.5 | 12 | 16 | 3,000 | 44,000 | 6 | 6 | 0.0086 | 0.0 | 0.0086 | 0.0 | 0.0053 | 0.0085 | 0.0053 | 0.0085 | 3.94 | 0.62 | 3.15 | 4.73 | 1.81 | | | |
| .5B | RCB-2 | 88.5 | 12 | 16 | 3,000 | 44,000 | 7 | 7 | 0.0086 | 0.0 | 0.0086 | 0.0 | 0.0053 | 0.0085 | 0.0053 | 0.0085 | 11.99 | 1.16 | 10.50 | 13.47 | 4.54 | | | |
| .5C | RCB-2 | 88.5 | 12 | 16 | 3,000 | 44,000 | 7 | 7 | 0.0086 | 0.0 | 0.0086 | 0.0 | 0.0053 | 0.0085 | 0.0053 | 0.0085 | 18.45 | 2.23 | 15.80 | 21.81 | 1.41 | | | |
| .6A | RCB-2 | 105 | 12 | 20 | 3,000 | 44,000 | 6 | 6 | 0.0041 | 0.0029 | 0.0041 | 0.0029 | 0.0041 | 0.0041 | 0.0041 | 0.0041 | 12.17 | 0.74 | 11.22 | 13.12 | 2.60 | | | |

Table 2 (continued)

| Case | Element Type | L _s (in.) | L _b (in.) | L _c (in.) | h (in.) | f' c (psi) | f dy (psi) | Support Case | Reinforcing Ratios at Cross Sections | | | | | | | | Tensile Membrane Steel Ratio | | Incipient Collapse Overpressure | | | | Incipient Collapse Overpr (Tens. Membr.) | | | |
|--|--------------|-------------------------|-------------------------|-------------------------|------------|------------------|------------------|--------------|--------------------------------------|--------|--------|--------|--------|--------|--------|--------|------------------------------|--------|---------------------------------|-----------------------|-----------------------|-----------------------|--|-----------------------|----------------------|--------|
| | | | | | | | | | | | | | | | | | Short | Long | Mean (psi) | Std. Dev. (psi) | 10% Prob. (psi) | 90% Prob. (psi) | Mean (psi) | Std. Dev. (psi) | 1% Prob. (psi) | |
| | | | | | | | | | 1 | 2 | 3 | 4 | p | p' | p | p' | | | | | | | | | | |
| Building 220, Fidelity Federal Plaza Building (RCF) | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1a | RCS-1 | 95 | 306 | 153 | 4.5 | 3,000 | 53,000 | 6 | 0.0043 | 0.0 | 0.0043 | 0.0021 | 0.0043 | 0.0 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 |
| 1b | RCS-1 | 95 | 153 | 153 | 4.5 | 3,000 | 53,000 | 4 | 0.0043 | 0.0 | 0.0043 | 0.0021 | 0.0043 | 0.0 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 |
| 1c | RCS-1 | 95 | 102 | 102 | 4.5 | 3,000 | 53,000 | 4 | 0.0043 | 0.0 | 0.0043 | 0.0021 | 0.0043 | 0.0 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 | 0.0043 | 0.0021 |
| 2a | RCS-1 | 306 | 153 | 153 | 20 | 3,000 | 53,000 | 6 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 |
| 2b | RCS-1 | 153 | 153 | 153 | 20 | 3,000 | 53,000 | 7 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 |
| 2c | RCS-1 | 102 | 153 | 153 | 20 | 3,000 | 53,000 | 5 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 |
| 2d | RCS-1 | 76.5 | 153 | 153 | 20 | 3,000 | 53,000 | 5 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 | 0.0172 | 0.0103 | 0.0137 | 0.0006 |
| 3a | RCS-1 | 312 | 153 | 153 | 36 | 3,000 | 53,000 | 6 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 |
| 3b | RCS-1 | 156 | 153 | 153 | 36 | 3,000 | 53,000 | 7 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 |
| 3c | RCS-1 | 104 | 153 | 153 | 36 | 3,000 | 53,000 | 5 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 |
| 3d | RCS-1 | 78 | 153 | 153 | 36 | 3,000 | 53,000 | 5 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 |
| 3e | RCS-1 | 312 | 153 | 153 | 36 | 3,000 | 53,000 | 6 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 | 0.0063 |
| Building 225, Broadway Greenham Building (RCF) | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1a | RCFP-1 | 288 | 288 | 288 | 9 | 2,500 | 53,000 | 11 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0027 | 0.0027 | 0.0044 | 0.0027 | 0.0044 | 0.0027 | 0.0044 | 0.0027 | |
| 1b | RCFP-1 | 288 | 288 | 288 | 9 | 2,500 | 53,000 | 11 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0027 | 0.0027 | 0.0044 | 0.0027 | 0.0044 | 0.0027 | 0.0044 | 0.0027 | 0.0044 |
| 1c | RCFP-1 | 288 | 288 | 288 | 9 | 2,500 | 53,000 | 11 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0 | 0.0044 | 0.0027 | 0.0027 | 0.0044 | 0.0027 | 0.0044 | 0.0027 | 0.0044 | 0.0027 | 0.0044 |
| 2a | RCS-2 | 76 | 288 | 288 | 16 | 2,500 | 53,000 | 5 | 0.0111 | 0.0 | 0.0111 | 0.0 | 0.0111 | 0.0 | 0.0111 | 0.0 | 0.0111 | 0.0056 | 0.0056 | 0.0111 | 0.0056 | 0.0111 | 0.0056 | 0.0111 | 0.0056 | 0.0111 |
| 3a | RCS-2 | 266 | 288 | 288 | 25 | 2,500 | 53,000 | 7 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0062 | 0.0062 | 0.0123 | 0.0062 | 0.0123 | 0.0062 | 0.0123 | 0.0062 | 0.0123 |
| 3b | RCS-2 | 143 | 288 | 288 | 25 | 2,500 | 53,000 | 5 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0062 | 0.0062 | 0.0123 | 0.0062 | 0.0123 | 0.0062 | 0.0123 | 0.0062 | 0.0123 |
| 3c | RCS-2 | 95.3 | 288 | 288 | 25 | 2,500 | 53,000 | 5 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0 | 0.0123 | 0.0062 | 0.0062 | 0.0123 | 0.0062 | 0.0123 | 0.0062 | 0.0123 | 0.0062 | 0.0123 |
| 4a | RCS-2 | 253 | 288 | 288 | 26 | 2,500 | 53,000 | 7 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0081 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 |
| 4b | RCS-2 | 126.5 | 288 | 288 | 26 | 2,500 | 53,000 | 5 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0081 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 |
| 4c | RCS-2 | 84.3 | 288 | 288 | 26 | 2,500 | 53,000 | 5 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0081 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 |
| 4d | RCS-2 | 253 | 288 | 288 | 30 | 2,500 | 53,000 | 7 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0 | 0.0156 | 0.0081 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 | 0.0081 | 0.0156 |
| Building 227, May Company Eastland Shopping Center (RCF) | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1a | RCS-1 | 29 | 30 | 30 | 3 | 3,000 | 56,000 | 6 | 0.0032 | 0.0 | 0.0032 | 0.0 | 0.0032 | 0.0 | 0.0032 | 0.0 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 |
| 1b/r | RCS-1 | 29 | 30 | 30 | 3 | 3,000 | 56,000 | 6 | 0.0032 | 0.0 | 0.0032 | 0.0 | 0.0032 | 0.0 | 0.0032 | 0.0 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 | 0.0032 |
| 2a | RCS-1 | 270 | 30 | 30 | 7.5 | 3,000 | 53,000 | 77 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0053 | 0.0053 | 0.0107 | 0.0053 | 0.0107 | 0.0053 | 0.0107 | 0.0053 | 0.0107 |
| 2b | RCS-1 | 135 | 30 | 30 | 7.5 | 3,000 | 53,000 | 51 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0053 | 0.0053 | 0.0107 | 0.0053 | 0.0107 | 0.0053 | 0.0107 | 0.0053 | 0.0107 |
| 2c | RCS-1 | 90 | 30 | 30 | 7.5 | 3,000 | 53,000 | 51 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0 | 0.0107 | 0.0053 | 0.0053 | 0.0107 | 0.0053 | 0.0107 | 0.0053 | 0.0107 | 0.0053 | 0.0107 |
| 3a | RCS-1 | 282 | 30 | 30 | 30 | 3,000 | 53,000 | 6 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0079 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 |
| 3b | RCS-1 | 141 | 30 | 30 | 30 | 3,000 | 53,000 | 7 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0079 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 |
| 3c | RCS-1 | 94 | 30 | 30 | 30 | 3,000 | 53,000 | 5 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0079 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 |
| 3d | RCS-1 | 282 | 30 | 30 | 30 | 3,000 | 53,000 | 6 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0 | 0.0157 | 0.0079 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 | 0.0079 | 0.0157 |
| 4a | RCS-1 | 280 | 30 | 30 | 26 | 3,000 | 53,000 | 6 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0056 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 |
| 4b | RCS-1 | 140 | 30 | 30 | 26 | 3,000 | 53,000 | 7 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0056 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 |
| 4c | RCS-1 | 93.3 | 30 | 30 | 26 | 3,000 | 53,000 | 5 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0056 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 |
| 4d | RCS-1 | 280 | 30 | 30 | 26 | 3,000 | 53,000 | 6 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0 | 0.0118 | 0.0056 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 | 0.0056 | 0.0118 |

Table 2 (concluded)

| Case | Element Type | L _s (in.) | L _b (in.) | b _b (in.) | h _b (in.) | f' _c (psi) | f' _{dy} (psi) | Support Case | Reinforcing Ratios at Cross Sections | | | | | | | | Tensile Membrane Steel Ratio | | Incipient Collapse Overpressure | | | | Incipient Collapse Overpr (Tens. Membr.) | | | | | | | |
|-------------------------------------|--------------|-------------------------|-------------------------|-------------------------|-------------------------|--------------------------|---------------------------|--------------|--------------------------------------|--------|--------|-----|--------|--------|--------|-----|------------------------------|-------|---------------------------------|-----------------|-----------------|-----------------|--|-----------------|----------------|----|----|----|----|----|
| | | | | | | | | | 1 | | 2 | | 3 | | 4 | | Short | Long | Mean (psi) | Std. Dev. (psi) | 10% Prob. (psi) | 90% Prob. (psi) | Mean (psi) | Std. Dev. (psi) | 1% Prob. (psi) | | | | | |
| | | | | | | | | | p | p' | p | p' | p | p' | p | p' | | | | | | | | | | | | | | |
| Building 245, Portland Hilton Hotel | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1a | RC3-1 | 24 | 112 | 3 | 3 | 3,000 | 56,000 | 6 | 0.0029 | 0.0 | -- | -- | 0.0029 | 0.0 | -- | -- | 16.45 | 0.88 | 16.34 | 16.56 | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 1a/r | RC3-1 | 24 | 112 | 3 | 3 | 3,000 | 56,000 | n/a | 0.0029 | 0.0 | 0.0005 | 0.0 | 0.0029 | 0.0 | 0.0005 | 0.0 | 97.30 | 9.77 | 64.78 | 109.83 | 0.0029 | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 2a | RCJ-1 | 278 | | 5.5 | 5.5 | 15 | 3,000 | 53,000 | 47 | 0.0181 | 0.0103 | -- | -- | 0.0225 | 0.0106 | -- | -- | 8.49 | 0.66 | 7.38 | 9.59 | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 2b | RCJ-1 | 135 | | 5.5 | 5.5 | 15 | 3,000 | 53,000 | 77 | 0.0181 | 0.0103 | -- | -- | 0.0225 | 0.0106 | -- | -- | 25.79 | 3.78 | 21.71 | 29.86 | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 2c | RCJ-1 | 98 | | 5.5 | 5.5 | 15 | 3,000 | 53,000 | 57 | 0.0181 | 0.0103 | -- | -- | -- | -- | -- | -- | 32.78 | 4.12 | 27.50 | 38.05 | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| 3a | RCB-1 | 936 | | 30 | 30 | 76.8 | 3,000 | 53,000 | 6 | 0.0221 | 0.0110 | -- | -- | 0.0221 | 0.0106 | -- | -- | 11.26 | 1.56 | 9.26 | 13.27 | 0.0147 | -- | -- | -- | -- | -- | -- | -- | -- |
| 3b | RCB-1 | 448 | | 30 | 30 | 76.8 | 3,000 | 53,000 | 7 | 0.0221 | 0.0110 | -- | -- | -- | -- | -- | -- | 35.04 | 3.75 | 30.23 | 39.85 | 0.0147 | -- | -- | -- | -- | -- | -- | -- | -- |
| 3c | RCB-1 | 312 | | 30 | 30 | 76.8 | 3,000 | 53,000 | 5 | 0.0221 | 0.0110 | -- | -- | -- | -- | -- | -- | 53.65 | 6.50 | 45.31 | 61.98 | 0.0147 | -- | -- | -- | -- | -- | -- | -- | -- |
| 3d | RCB-1 | 234 | | 30 | 30 | 76.8 | 3,000 | 53,000 | 5 | 0.0221 | 0.0110 | -- | -- | -- | -- | -- | -- | 92.98 | 8.69 | 81.64 | 106.12 | 0.0147 | -- | -- | -- | -- | -- | -- | -- | -- |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

The question arises, however, as to how much of these materials could be mobilized and installed in a crisis build-up period of, say, one year.

REFERENCES

1. Murphy, H. L., C. K. Wiehle, and E. E. Pickering, Upgrading Basements for Combined Nuclear Weapons Effects: Expedient Options, Stanford Research Institute¹² Technical Report, for U. S. Defense Civil Preparedness Agency,¹³ May 1976. (AD-A030 762)¹⁴
2. Murphy, H. L., Upgrading Basements for Combined Nuclear Weapons Effects: Predesigned Expedient Options, Stanford Research Institute Technical Report, for U. S. Defense Civil Preparedness Agency, October 1977. (AD-A054 409)
3. Murphy, H. L., J. R. Rempel, and J. E. Beck, SLANTING IN NEW BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: A Consolidated Printing of Four Technical Reports, SRI International Technical Report, 3 vols., for U. S. Defense Civil Preparedness Agency, October 1977. (AD-A023 237)
4. Murphy, H. L., and J. E. Beck, Maximizing Protection in New EOCs from Nuclear Blast and Related Effects: Guidance Provided by Lecture and Consultation, Stanford Research Institute Technical Report, for U. S. Defense Civil Preparedness Agency, September 1976. (AD-A039 499)
5. Cristy, G. A., and C. H. Kearny, Expedient Shelter Handbook, Oak Ridge National Laboratory final report, ORNL-4941, for Defense Civil Preparedness Agency, August 1974.
6. Kearny, C. H., Expedient Shelter Construction and Occupancy Experiments, Oak Ridge National Laboratory report, ORNL-5039, March 1976.
- 7A. Wiehle, C. K., and J. L. Bockholt, Existing Structures Evaluation, Part I: Walls, Stanford Research Institute report for U. S. Office of Civil Defense, November 1968. (AD-687 293)
- 7B. Wiehle, C. K., and J. L. Bockholt, Dynamic Analysis of Reinforced Concrete Floor Systems, Stanford Research Institute report for U. S. Defense Civil Preparedness Agency, May 1973. (AD-768 206)
- 7C. Wiehle, C. K., Dynamic Analysis of a Building and Building Elements, Stanford Research Institute report for U. S. Defense Civil Preparedness Agency, April 1974. (AD-A001 387)

¹² Now SRI International.

¹³ Now Federal Emergency Management Agency (Washington, D.C.).

¹⁴ Publications with AD-numbers are available from NTIS, Springfield, Virginia 22151.

8. Beck, J. E., Summary of Dynamic Analyses of Selected NSS Buildings, SRI International report for U. S. Federal Emergency Management Agency, July 1980.
- 9A. Gabrielsen, B. L., G. Cuzner, and R. Lindskog, Blast Upgrading of Existing Structures, Scientific Service, Inc. final report for U. S. Defense Civil Preparedness Agency, January 1979.
- 9B. Wilton, C., B. L. Gabrielsen, and R. S. Tansley, Shelter Upgrading Manual: Host Area Shelter, Scientific Service, Inc. final report for U. S. Federal Emergency Management Agency, March 1980.
- 9C. Gabrielsen, B. L., R. S. Tansley, and G. Cuzner, Upgrading of Existing Structures, Phase II, Scientific Service, Inc. final report for U. S. Federal Emergency Management Agency, June 1980.
10. Private communication of November 17, 1980 with Mr. Mark K. McVay of the U. S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.
11. Design Values for Wood Construction, A Supplement to the 1977 Edition of National Design Specification for Wood Construction, National Forest Products Association, 1619 Massachusetts Avenue, Washington, D.C. 20036, April 1980.
12. Plywood Design Specification, American Plywood Association, 1119 A Street, Tacoma, Washington, Revised April 1978.

Appendix A

BLAST-RESISTANT DESIGN/ANALYSIS GENERAL APPROACH

CONTENTS

| | |
|--|------|
| Introduction | A-1 |
| Loading | A-2 |
| Structural Yield Resistance | A-2 |
| Structural Properties of Materials | A-6 |
| Design Versus Weapons Analyst Overpressure | A-6 |
| Factor of Safety | A-6 |
| NOTATION | A-9 |
| REFERENCES | A-11 |

FIGURES

| | | |
|-----|----------------------------|-----|
| A-1 | BLAST LOADING | A-3 |
| A-2 | BLAST RESISTANCE | A-5 |

Appendix A

BLAST-RESISTANT DESIGN/ANALYSIS GENERAL APPROACH

Introduction

The purpose of this appendix is to discuss several matters that are common to all blast-resistant design/analysis approaches, whatever the construction material. This and the following engineering appendices are aimed at architects and engineers, but generally those weak in, say, indeterminate structures and dynamic structural analysis.

For collateral reading, there are many references: the overall source-book on nuclear weapons effects [1, using its Contents and Index to locate items of interest],¹ an early paper, tightly written, that is now a classic [2] (an errata was later published: delete the denominator "6" in Eq. 2, p. 49; delete the fraction bar in text line below Eq. 7a, p. 56; and, change the "q" subscript to "e" in line 7, p. 58); the first professional society manual on the subject, still current [3]; two bulky manuals [4,5]; a textbook [6]; and, two publications used in the preparation of this and other appendices herein [7,8].

In this and following appendices, design and analysis may be used with little difference in meaning. In most cases dealt with in upgrading, design is accomplished by seeing what materials one has to work with, then determining each potential member's blast resistance (analysis) when used under a particular set of conditions. Most often a design/analysis procedure will be presented followed by a simplifying graph or table, which is used by entering either with the member parameters to find its blast resistance, or with its desired blast resistance to find the needed member parameters (size, useful stresses, span, etc.).

Newmark has clearly stated a simplified approach to blast-resistant design/analysis [8(Ch.7)] from which the following material is quoted (parenthetic connective words or insertions are by this writer):

"The various factors governing structural design for blast resistance . . . include loading, structural resistance, design considerations as affected by the material used, and the structural properties of these materials. . . . Resistance expressions for different materials and support conditions (are presented in following appendices).

¹ Brackets are used herein to indicate sources in the References list at the end of this appendix.

Loading

The simplified loading (Figure A-1) of the various structural elements . . . are . . . assumed (to be) . . . long duration step pulses² with pressures p_m , which are a function of the location of the elements and their orientation with respect to the blast wave. (In Figure A-1:

t = time, measured from arrival of the blast front (sec).)

Structural Yield Resistance

"For the long duration step pulse loading shown in Figure A-1 the relationship (among) the design parameters is:

$$p_m/q_y = 1 - 1/(2\mu) \quad (1)$$

where:

p_m = peak pressure (psi)

p_y = the (idealized) yield resistance of the structural element (psi)

μ = the ductility factor defining the maximum acceptable response of the structure, i.e., the ratio of the maximum deflection to the yield deflection

"Two important design parameters do not appear in the above equation. These parameters are:


t_d = the duration of the (positive phase of the blast) loading (sec)

T = the (effective natural) period (of vibration) of the structural element (sec)

These parameters do not appear (in Eq. 1) because the ratio t_d/T is considered to be infinite, or effectively greater than about 3. Reference [2 or 3] may be consulted to obtain the relationships replacing the above equation when the ratio t_d/T is small.

"The structural yield resistance q_y and the limit of acceptable structural response μ are determined by considering the resistance-deflection curve for the structural element. The resistance q (is) considered as a static loading distributed spatially in the same manner as the air blast loading;

² A loading whose application is instantaneous (i.e., rise time equals zero) and duration is long.



Source: Reference 8, page 169

Figure A-1 BLAST LOADING

q = structural resistance (psi)

is plotted in Figure A-2, where

q_y = the structural yield resistance (psi)

The deflection is also plotted in Figure A-2, where

x_e = the yield deflection.

The ductility factor

$$\mu = (x_m/x_e)$$

where


x_m = the maximum acceptable deflection.

In the selection of x_m , both structural integrity and structural function should be considered. The value of x_m should not be greater than the deflection at which the resistance of the structure begins to drop off or fracture occurs. Operational requirements, e.g., avoidance of jamming of a door or its operating mechanism, may set a lower limit on x_m .

"Figure A-2 is a typical resistance-deflection curve with its idealized bi-linear representation as used in design. The idealized resistance function is constructed so that the area under both the real and ideal curves are equal (from zero to yield (x_e) and (from yield to maximum response (x_m)).

"The design involves establishing the required yield resistance for the structural element and then providing this resistance in the structural element (or analysis involves knowing the latter and finding q_y). The peak pressure p_m is evaluated (by considering expected peak overpressure, peak expected pressure and reflection factor, peak room filling pressure [7(p.8-112)], etc., and) the orientation of the structural element with respect to the blast wave. If allowable maximum deflection is set by structural considerations, the ductility factor μ is a function of the type of structural element and materials used. If operational requirements govern, the ductility factor μ will be selected to limit the maximum deflection of the structure to the permissible magnitude.

"In the (following appendices), expressions are presented for yield resistance q_y , yield deflection x_e , and the period T for (structural) elements of various materials and structural types. The maximum recommended value of the ductility factor based on consideration of structural integrity is presented for each material and each structural type considered. These μ values must then be checked to insure that the resulting deformations are operationally acceptable.



Source: Adapted from Reference 8, page 170

Figure A-2 BLAST RESISTANCE
(Typical Real and Idealized Load-Deflection Curves)

Structural Properties of Materials

The following appendices are presented the strength properties of materials considered suitable for (basement protective) structures. In many instances the variety of commercially available materials is too great for complete description of pertinent properties herein. Therefore, expressions for design stresses for protective design (may be) given in lieu of extensive strength tabulations.

Protective structures are designed on the basis of a predicted failure load, failure being defined either by the limit of acceptable deformation or by the (incipient) collapse of the structural element. Normally a ductile, large deformation, failure mode is desired in design since large amounts of energy are absorbed in inelastic deformation.

"The design stresses given herein correspond generally to the probable yield stress of the material under the blast loading conditions. These design stresses represent probable yield stresses for the material, not guaranteed minimum values, since it is desired to estimate the actual yield load for the structural element rather than a lower limit to the yield load."

Design versus Weapons Analyst Overpressure

One must emphasize that the peak blast design overpressure p_m is not a weapon analyst overpressure. The former is a value that should give, say, a 99% probability of not reaching incipient collapse or some other failure definition, whereas the latter should be a median (50% probability) value [Ref. 6-2].

Factor of Safety

Blast resistance design analysis (for, say, 99% probability of not reaching incipient collapse or some other failure definition) is based on a peak blast pressure value that has all factors of safety wrung out of it. In structural design to resist dynamic loads, various structural elements are likely to have different dynamic response characteristics (e.g., effective natural period of elastic vibration T). Thus, if all structural elements are to be designed to the same dynamic strength level, the loading must be in terms of a dynamic load(s). Therefore, if a factor of safety common to all structural elements is to be set, it must be in terms of the dynamic loading, that is, in this case air blast peak pressure. Because protective structures against nuclear air blast are very expensive, the dynamic factor of safety is usually taken as

1) $F = 1.5$ the peak air blast pressure (1) considered most likely to occur, or
2) the one assumed for design use as the pressure that one can afford to protect against. If the latter is to be subject to a further factor of safety, for example two, then this factor is simply used

as a multiplier on the peak pressure arrived at by either of the two methods just described.

NOTATION

- p_m = peak pressure (psi)
- p_y = the (idealized) yield resistance of the structural element (psi)
- q = structural resistance (psi)
- q_y = the structural yield resistance (psi)
- T = the (effective natural) period (of vibration) of the structural element (sec)
- t = time, measured from arrival of the blast front (sec)
- t_d = the duration of the (positive phase of the blast) loading (sec)
- x_e = the yield deflection
- x_m = the maximum acceptable deflection
- μ = (x_m/x_e)
- μ = the ductility factor defining the maximum acceptable response of the structure, i.e., the ratio of the maximum deflection to the yield deflection

REFERENCES

1. Glasstone, S., editor, The Effects of Nuclear Weapons, U. S. Department of Defense and Atomic Energy Commission, February 1964 reprint (with changes) of 1962 edition, Superintendent of Documents, Washington, D.C.; a 1977 edition is now available.
2. N. M. Newmark, "An Engineering Approach to Blast-Resistant Design," Transactions, Volume 121, p. 45-64, American Society of Civil Engineers, 1956.
3. Anderson, F. E., Jr., R. J. Hansen, H. L. Murphy, N. M. Newmark, and M. P. White, Design of Structures to Resist Nuclear Weapons Effects, ASCE Manual of Engineering Practice No. 42, 1961, and Supplement 1963 (combined into a "1964 edition").
4. Newmark, N. M., and J. D. Hiltiwanger, Principles and Practices for Design of Hardened Structures, Air Force Design Manual, published by Air Force Special Weapons Center, Kirtland AFB, New Mexico, Report No. SWC-TDR 62-138, December 1962. (AD-295 408)³
5. Manuals-Corps of Engineers, U. S. Army, Engineering and Design, Design of Structures to Resist the Effects of Atomic Weapons, EM 1110-345-413 (July 1959), -414 to -416 (March 1957), -417 (January 1958), and -418 to -421 (January 1960), U. S. Government Printing Office, Washington, D.C. (AD-419 for -416).⁴
6. Biggs, J. M., Introduction to Structural Dynamics, 1964 (McGraw-Hill).
7. Murphy, H. L., J. R. Rempel, and J. E. Beck, SLANTING IN NEW BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: A Consolidated Printing of Four Technical Reports, Stanford Research Institute⁵ Technical Reports, 3 volumes, for U. S. Defense Civil Preparedness Agency,⁶ October 1975. (AD-A023 237) Omitted, of course, was any material in a later report that replaced material published in an earlier report.

³ Those references for which "AD-" numbers are shown are understood to be available for purchase from NTIS, Springfield, Virginia, 22151.

⁴ Reprinted, without change, and redesignated; e.g., EM 1110-345-413 through EM 1110-345-421 became Headquarters, Department of the Army, TM 5-856-1 through TM 5-856-9.

⁵ Now SRI International

⁶ Now Federal Emergency Management Agency

8. Newmark, N. M., Design of Openings for Buried Shelters, Report 2-67, U. S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi, July 1963; Chapter 7.

Appendix A1

PLYWOOD STRESSED-SKIN PANELS (TWO-SIDED ONLY) AS CLOSURES -
DESIGN AND FABRICATION

Extracts (with minor revisions) from the main text and Appendix A1 of

Murphy, H. L., Upgrading Basements for Combined Nuclear Weapons Effects:
Predesigned Expedient Options, Stanford Research Institute* Technical
Report, for U.S. Defense Civil Preparedness Agency, # October 1977.
(AD-A054 409)

* Now SRI International

Now Federal Emergency Management Agency

CONTENTS

| | |
|---|-------|
| DESIGN | A1-1 |
| Design Procedure | A1-1 |
| Design Stresses - Blast Protection Use vs. Normal Use . . . | A1-12 |
| Typical Designs of PSSPs | A1-15 |
| PSSP UPGRADING EXAMPLE - CLOSURE | A1-22 |
| FABRICATION | A1-23 |
| FURTHER WORK | A1-24 |
| NOTATION | A1-25 |
| REFERENCES | A1-29 |

TABLE

| | | |
|-------|--|-------|
| Al-1. | PSSP Designs for Lower and Higher Strength Stringers ($F_v = 280$ and 380 psi) (Beams). | Al-16 |
|-------|--|-------|

FIGURES

| | | |
|-------|---|------|
| Al-1. | Plywood Stressed-Skin Panel (Example Trial Section) and Table on Stringer Spacing | Al-2 |
| Al-2. | Neutral Axis for Deflection and (EI_g) (Calculations Examples) | Al-4 |
| Al-3. | Neutral Axis for Bending Moment and (EI_n) (Calculations Examples) | Al-6 |
| Al-4. | Rolling Shear Critical Plane and Q_s | Al-8 |

Design

A design procedure for plywood stressed-skin panels was developed because plywood and suitable wood members for the necessary stringers are in abundant supply in local lumberyards, and because efficient use of such materials can assist greatly in meeting the existing basement upgrading need for many closures against air blast entry into the basement.

Existing design procedures were studied, used as a basis for developing the procedure that follows, but had to be carefully reviewed/modified/rederived to make them both dimensionally consistent (and thus more readily convertible to metric units, a contract requirement) and usable for panel widths other than 48 in. (a limitation built into the present procedure).^{1,2*}

The developed design procedure is limited to plywood stressed-skin panels with both top and bottom skins, both of which are used with the grain of the outer plies parallel to the stringers. Adequate shear transfer between plywood (flanges) and stringers (webs) is assumed, based on using pressure-glued or nail-glued joining techniques. The normal-use allowable stresses in the procedure are intended for application to panels at least 2 ft wide (measured perpendicular to stringers); narrower panels are subject to reductions in allowable stresses.^{2(p.19)}

Design Procedure. The design procedure (steps) follows:

1. Assume a trial section and clear span (in direction of stringers), and that panel is fully and uniformly loaded. See Figure 1A.
2. Get values for b ("b distance"), both for top b_t and bottom b_b skins (Figure 1B). If clear distance between stringers, Figure 1A, exceeds $2b$ for both skins, this design procedure is inapplicable.^{1(p.5)}
3. Calculate N.A. (neutral axis location) for deflection. Use bottom of panel as reference line for moment arms y applied to areas A_i/E ,

* Superscript numbers are related to the references list at the end of this appendix. Reference 2 must be held by the user, particularly for its Tables, pp. 9, 14-17 and 26; holding Reference 1 is unnecessary but may be desirable. (Reference of this report's main text is later reference and not significantly changed from Reference 2 herein.)

Top Skin - 5/8" UNDERLAYMENT Group 1 INT-APA
(For this thickness and stringer spacing, a 5 ply 5-layer panel should be used for resistance to concentrated floor loads.)

$$A_{||} = 2.728 \text{ in.}^2/\text{ft}$$


$$I_{||} = 0.141 \text{ in.}^4/\text{ft}$$

$$I_{\perp} = 0.023 \text{ in.}^4/\text{ft}$$

2 x 6 Douglas fir-
Larch No 1
stringers

$$A^* = 8.06 \text{ in.}^2$$

$$I^* = 19.4 \text{ in.}^4$$



Bottom Skin - 5/16"
C-D 20/0 INT-APA

$$A_{||} = 1.914 \text{ in.}^2/\text{ft}$$

$$I_{||} = 0.025 \text{ in.}^4/\text{ft}$$

$$\text{Clear distance between stringers} = \frac{48 - 3 \times 1.5 - 1 - 0.75}{3} = 13.9''$$

$$\text{Total splice plate width} = 3(13.9 - 0.5) = 40.2''$$

*Includes a 1/8" reduction in depth to allow for resurfacing.

A.

Basic Spacing, b , For Various Plywood Thicknesses

(Face grain parallel to stringers*)

| Plywood | Basic Spacing b (inches) | | | | |
|-----------------------------------|----------------------------|-----------|-----------|-----------|-----------|
| | 3 | 4 | 5 | 8 | 7 |
| | | (3 layer) | (5 layer) | (5 layer) | (7 layer) |
| 1/4" Sanded | 10 | | | | |
| 5/16" Unsanded | 12 | | | | |
| 3/8" Unsanded | 16 | | | | |
| 3/8" Sanded | 19 | | | | |
| 1/2" Unsanded sanded touch sanded | 22 | 22 | 23 | | |
| 5/8" Unsanded sanded | 27 | 35 | 33 | | |
| 5/8" 19/32" Touch sanded | | 27 | 32 | | |
| 3/4" Unsanded sanded touch sanded | | 36 | 38 | 38 | |
| 23/32" Touch sanded | | 35 | 34 | 37 | |
| 7/8" Unsanded | | | 48 | | 39 |
| 7/8" Sanded | | | | | 51 |
| 1" Unsanded sanded | | | | | 53 |
| 2 1/4" | | | | | 56 |

*Where plywood face grain is across stringers, write APA for appropriate "b" distances.

B.

FIGURE A1-1 PLYWOOD STRESSED-SKIN PANEL (Example Trial Section)^{1(p.4)}
AND TABLE ON STRINGER SPACING^{1(p.5)}

counting only plies parallel to stringers (for $A_{//}$) and increasing E values (to correct from effective E to true E in bending), by 10% for skins^{2(p.17),1(p.7)} and 3% for stringers.^{3,1(p.7)} $A_{//}$ values are available from tables^{2(p.16: note units, col. 4: in.²/ft)}. A calculation example is shown in Figure 2A.

4. Calculate panel (EI_g) using N.A. of Step 3. This stiffness factor is for moment deflection only (i.e., excludes shear deflection). Obtain I_o values for skins.^{2(p.16,col.5)} Calculate I_o values for (combined) stringers ($bd^3/12$), including a portion of any stringer that is partially outside the plywood skins, as one stringer is in the calculation example shown in Figure 2B. Same E values and percentage increases are used as in Step 3.

5. Calculate allowable load (TL) - deflection:^{*†}

$$p_d = 1 / [C \ell' (\frac{5}{384} \frac{\ell^2}{EI_g} + \frac{0.15}{AG})] + DL$$

where: p_d = allowable TL - panel deflection (psi)

C = factor for max. allowable deflection*
(often 360 floors, 240 roofs, LL only)

(EI_g) from Step 4 (lb-in.²)

A = (actual) total X-sec. area of all stringers (in.²)

G = modulus of rigidity of stringers (psi)
(taken as 0.06 E plus 3%)


ℓ = clear span of panel (in direction of stringers)(in.)

ℓ' = width of panel (skins only)(perpendicular to ℓ)(in.)

6. Calculate allowable load (TL) - top skin deflection (cross-panel). Usually only the top skin deflection need be checked, but unusual assumed sections may require top skin moment and shear investigations.^{1(p.9)}
Check strip 1 in. wide for allowable total load (TL) and deflection

* If C is based on TL, then p_d will be directly in TL units (psi), without adding the DL term in the equation.^{1(p.9)}

† While (EI_g) excludes shear deflection, the formula for p_d includes it.




Values of A_{II} of plywood from PDS Table 1.

| Item | E | A_{II} | $A_{II}E$ | y | $A_{II}E y$ |
|-------------|-------------------------------------|-------------------------|------------|-------|-------------|
| Top Skin | $1,800,000 \times 1.1 = 1,980,000$ | $4 \times 2.778 = 10.9$ | 21,600,000 | 6.000 | 129,600,000 |
| Stringers | $1,800,000 \times 1.03 = 1,850,000$ | $4 \times 8.06 = 32.2$ | 59,600,000 | 3.000 | 178,800,000 |
| Bottom Skin | $1,800,000 \times 1.1 = 1,980,000$ | $4 \times 1.914 = 7.66$ | 15,200,000 | 0.156 | 2,370,000 |
| Total | | 50.8 | 96,400,000 | | 310,770,000 |

$$\bar{y} = \frac{\sum A_{II} E y}{\sum A_{II} E} = \frac{310,770,000}{96,400,000} = 3.22''$$

A.



Values of I_o of plywood from PDS Table 1.

| Item | E | I_o | A_{II} | d | d^2 | $A_{II} d^2$ | $I_o + A_{II} d^2$ | $E(I_o + A_{II} d^2)$ |
|-------------|-----------|-------|----------|------|-------|---------------|--------------------|-----------------------|
| Top Skin | 1,980,000 | 0.564 | 10.9 | 2.78 | 7.73 | 84.3 | 84.9 | 168,000,000 |
| Stringers | 1,850,000 | 77.6 | 32.2 | 0.22 | 0.48 | 1.55 | 79.2 | 147,000,000 |
| Bottom Skin | 1,980,000 | .100 | 7.66 | 3.06 | 9.36 | 71.7 | 71.8 | 142,000,000 |
| Total | | | | | | $I_o = 235.9$ | | 457,000,000 |

$$EI_g = 457,000,000 \text{ lb-in.}^2 \text{ per 4-ft width}$$

B.

FIGURE A1-2 NEUTRAL AXIS FOR DEFLECTION AND (EI_g)
(Calculations Examples)^{1(p.8)}

(FF or fixed ends beam assumption), based on cross-panel top skin deflection behavior, as follows:

$$p_t = 384 EI / [C(l'')^3] + DL$$

where: p_t = allowable TL - top skin deflection (psi)

C = factor for max. allowable deflection*
(often 360 floors, 240 roofs, LL only)

E is for top skin^{2(p.17, no 10% added)} (psi)

I is for stress applied perpendicular to stringers and face grain^{2(p.16, col.9)}; table's in.⁴/ft values must be changed to in.⁴/in.

l'' = clear distance between stringers (Step 2 and Fig 1A) (should be uniform; if not, use longest value)(in.)


Mid-span cross-panel deflection, of course, then equals l''/C .

7. Calculate N.A. for bending. Effective width of skins (as "flanges" to each stringer) is $b/2$ on each side of stringer, plus the width of the stringer. Get b from Step 2. Make sketch showing effective widths with each stringer, of both top and bottom skins. Calculate N.A. location, using bottom of panel as reference line for moment arms y ; see example, Figure 3A; E values are used plus percentages, as in Step 3. Recall that $A_{//}$ tabular values are in in.²/ft width and must be corrected for effective width of skins (versus total width used in Step 3), as must I_o skin values; moment arms for skins and stringers are the same as in Step 3. NOTE: Non-Stress-Graded stringers are omitted in the calculations of this Step (i.e., valued at zero), even though in Steps 3 and 4 they would be included.

8. Calculate (EI_n) for bending. Use all data from Step 7, plus using I_o for each skin as flanges (from Step 4, but correcting I_o values from full panel width to "effective widths" of Step 7), again correcting for tabular units of in.⁴/ft width, as necessary; use I_o values for stringers, as in Step 4 (omit Non-Stress-Graded stringers, though, as in Step 7). See example calculations, Figure 3B.

* If C is based on TL, then p_t will be directly in TL units (psi) without adding the DL term in the equation.^{1(p.9)}


Effective width of top skin = 48"
 Effective width of bottom skin = $48'' - 3(13.9 - 12) = 42.3''$



| Item | E | A | A E | y | A Ey |
|-------------|-----------|---------------------------------------|-------------------|-------|--------------------|
| Top Skin | 1,980,000 | 10.9 | 21,600,000 | 6.00 | 129,600,000 |
| Stringers | 1,850,000 | 32.2 | 59,600,000 | 3.00 | 178,800,000 |
| Bottom Skin | 1,980,000 | $\frac{42.3}{12} \times 1.914 = 6.75$ | 13,400,000 | 0.156 | 2,090,000 |
| | | | 94,600,000 | | 310,490,000 |

$$\bar{y} = \frac{\sum A_{||} E y}{\sum A_{||} E} = \frac{310,490,000}{94,600,000} = 3.28''$$

A.



| Item | E | I _o | A | d | d ² | A d ² | I _o + A d ² | E(I _o + A d ²) |
|-------------|-----------|----------------|-----------------|------|----------------|--------------------------------|---|---|
| Top Skin | 1,980,000 | 0.564 | 10.9 | 2.72 | 7.40 | 80.7 | 81.3 | 161,000,000 |
| Stringers | 1,850,000 | 77.6 | 32.2 | 0.28 | 0.078 | 2.51 | 80.1 | 148,000,000 |
| Bottom Skin | 1,980,000 | 0.088 | 6.75 | 3.12 | 9.73 | 65.7 | 65.8 | 130,000,000 |
| | | | | | | | I _n = 227.2 | 439,000,000 |

$$EI_n = 439,000,000 \text{ lb-in.}^2 \text{ per 4-ft width}$$

B.

FIGURE A1-3 NEUTRAL AXIS FOR BENDING MOMENT AND (EI_n)
 (Calculations Examples)¹(p.10,11)

9. Determine top skin allowable compressive stress. Obtain F_c .^{2(p.17)} correct F_c in same manner as for F_t using ratio of joint distance between stringers ℓ'' (Step 6) to ℓ . Step 5, as follows: for ratio ≤ 0.5 , use 100%; for ratio > 1.0 up to 1.5 (see parenthetical comment in Step 2), use 67%; and for ratios between 0.5 and 1.5, vary percentage correction linearly between 100% and 66.7% (p.11)*

10. Determine bottom skin allowable tensile stress. Obtain F_t .^{2(p.17)} correct F_t in same manner as Step 9 (for F_c), using b_1 from Step 2.^{1(p.11)}

11. Calculate allowable load (H) - bending:

$$p_b = (8 F_c - (c(\ell'\ell'')))(EI_n / E)$$

where: p_b = allowable load (H) - bending (psi)

F = F_c or F_t from Steps 9 and 10, as appropriate (psi)

(EI_n) from Step 8 (lb-in.²)

E for skin under check, top or bottom (as in Step 3, including percentage increase)(psi)

c = distance from N.A. for bending (Step 7) to extreme fibre (of skin under check, top or bottom)(in.)

ℓ and ℓ' are same as in Step 5 (in.)


Check p_b for both top (p_{bt}) and bottom (p_{bb}) skins, then use smaller value as the applicable p_b .

12. Calculate allowable load (TL) - rolling shear:

It is generally sufficient to check rolling shear only in the thicker skin (it usually has the larger Q_s of the two skins, which leads to a smaller allowable load).^{1(p.13)} The skin's critical plane for checking (in panels with face plies parallel to stringers, a fundamental limitation in the overall procedure herein) is along the glued plane on the inner side of the inside face ply of the panel; see Figure 4A.

Find area A (in.²) for parallel-grain plies outside the critical plane (note that tabular values are for 48-in. wide panels, so must be corrected proportionately for other panel widths ℓ'), Figure 4B, 2nd or

* Reference 1, p.11, figure erroneously shows 67.5% instead of correct value of 66.7% (as shown in text example and in other sources).



A and y' for Computing Q_s *

| Plywood Thickness (in.) | STRUCTURAL I Grades, or any Group 4 Panel | | | | All Other Panels | | | |
|----------------------------|---|------------|-------------------------|------------|-------------------------|------------|-------------------------|------------|
| | Face Grain to Stringers | | Face Grain to Stringers | | Face Grain to Stringers | | Face Grain to Stringers | |
| | Area (in ²) | y' (in.) | Area (in ²) | y' (in.) | Area (in ²) | y' (in.) | Area (in ²) | y' (in.) |
| Unsanded Panels | | | | | | | | |
| 5/16 | 4.75 | 0.0495 | 4.75 | 0.149 | 3.83 | 0.0479 | 2.64 | 0.149 |
| 3/8 | 4.45 | 0.0464 | 5.75 | 0.180 | 3.13 | 0.0461 | 3.19 | 0.180 |
| 1/2 | 5.81 | 0.0606 | 7.75 | 0.242 | 6.25 | 0.131 | 4.31 | 0.242 |
| 5/8 | 9.24 | 0.176 | 9.75 | 0.305 | 7.18 | 0.140 | 5.42 | 0.305 |
| 3/4 | 7.34 | 0.0765 | 11.8 | 0.367 | 8.16 | 0.208 | 6.53 | 0.367 |
| Sanded Panels | | | | | | | | |
| 1/4 | 3.36 | 0.0350 | 4.91 | 0.121 | 3.36 | 0.0350 | 2.73 | 0.121 |
| 3/8 | 3.36 | 0.0350 | 8.51 | 0.184 | 3.36 | 0.0350 | 4.73 | 0.184 |
| 1/2 | 3.89 | 0.0406 | 9.23 | 0.246 | 3.89 | 0.0406 | 5.13 | 0.246 |
| 5/8 | 4.56 | 0.0475 | 11.7 | 0.309 | 4.56 | 0.0475 | 6.51 | 0.309 |
| 3/4 | 12.0 | 0.277 | 15.1 | 0.371 | 8.18 | 0.233 | 8.42 | 0.371 |
| Touch Sanded Panels | | | | | | | | |
| 1/2 | 4.56 | 0.0475 | 8.35 | 0.224 | 4.56 | 0.0475 | 4.64 | 0.224 |
| 19/32 | 7.93 | 0.174 | 11.6 | 0.276 | 5.90 | 0.139 | 6.44 | 0.276 |
| 5/8 | 8.21 | 0.185 | 12.3 | 0.288 | 6.06 | 0.148 | 6.86 | 0.288 |
| 23/32 | 6.06 | 0.0632 | 14.5 | 0.344 | 8.14 | 0.213 | 8.06 | 0.344 |
| 3/4 | 6.06 | 0.0632 | 15.3 | 0.356 | 8.37 | 0.225 | 8.50 | 0.356 |
| 2 1/4 | | | | | 12.7 | 0.359 | 16.5 | 0.547 |

* Area based on 48" wide panel. For other widths, use a proportionate area.

B.

FIGURE A1-4 ROLLING SHEAR CRITICAL PLANE AND Q_s ^{1(p.14)}

6th column. Calculate distance d_s (in.) from N.A. (for deflection, Step 3) to centroid of A, using moment arm $d_s = c - y'$ (all in. units), where c is distance from N.A. to extreme fibre and y' can be taken from table, Figure 4B. Then calculate the statical moment Q_s (in.³):

$$Q_s = A d_s$$

Calculate $\sum F_s t$ (psi-in., or lb/in.), the sum of the glueline widths over each stringer, each multiplied by its applicable allowable rolling shear stress F_s (Reference 2, page 17) but with a 50% reduction applied to outer stringer(s) whose clear distance to a panel edge is less than half the clear distance between stringers.^{1(p.15)}

Calculate allowable load (TL) - rolling shear (p_s , psi):

$$p_s = (2(\sum F_s t) / (\ell \ell' Q_s)) ((EI_g) / E)$$

where: $(\sum F_s t)$ (lb./in.), ℓ and ℓ' (in.), and Q_s (in.³) are defined above

(EI_g) from Step 4 (lb-in.²)

E for skin under check, usually thicker one (tabular value plus 10% if taken from Ref. 2, p. 17)

13. Calculate allowable load (TL) - horizontal shear:

Calculate statical moment Q_v of all parallel-grain plies and stringers in full panel width ℓ' , working either above or below* the N.A. for deflection (Step 3 and Figure 2 can provide numerical data for these $Q_v = A d$ calculations, as an example of course):

$$Q_v = Q_{\text{stringers}} + Q_{\text{skin}} [E_{\text{skin}} / E_{\text{stringers}}]$$

where: Q_v is defined above (in.³)

$Q_{\text{stringers}}$ = x-sec. area of all stringer portions either above or below N.A. (depending on chosen approach)* times its centroidal distance from deflection N.A. (as moment arm) (in.³)

Q_{skin} = $A_{//}$ for chosen skin \times moment arm (in.³)^{2(p.16, col. 4 for $A_{//}$)}
 E 's as before (Step 3, including percentage increases)(psi)

* Calculations "below" are easier, if deflection N.A. calculations (Step 3) were made as stated, i.e., using bottom surface of panel as reference plane.

Calculate:

$$p_v = (2 F_v t / (\ell \ell' Q_v)) ((EI_g) / E_{st})$$

where: p_v = allowable load (TL) - horizontal shear (psi)

F_v = allowable stress in stringer horizontal shear (psi)³(Table 1)

t = sum of stringer widths (including side projecting portions, Figures 1A and 2)(in.)

(EI_g) from Step 4 (lb-in.²)

E_{st} for stringers, as in Step 3 including percentage increase (psi)

ℓ , ℓ' , and Q_v as above (in., in., and in.³)

14. Calculate required end bearing length:

The preceding steps that have led to allowable load (TL) under various criteria have used ℓ = clear span (in.)(Steps 5,6,11,12 and 13), but for end bearing, the full length of the panel will be greater than ℓ , sufficiently to provide for the allowable load (TL) in end bearing. Further, properly installed headers will have to be capable of spreading the end bearing load across the full panel width of the (thin) bottom skin; thus continuous headers crossing (nail-glued or pressure-glued) the stringer ends, and within the cover of both top and bottom skins, are recommended (see Reference 1, page facing page 1, top sketch, far end, for example).

The following approach to calculating ℓ_e (required plywood end bearing length at each end) considers adoption of the continuous-headers recommendation just above, but may be also used, perhaps with less confidence in ultimate strength behavior, for blocking-type headers (see same Reference 1 sketch, near end, for an example).

Let: ℓ_e = required plywood end bearing length at each end of panel (in.)

ℓ = clear span of panel, as before (in.)

ℓ' = full panel width (skins only)(note: entire panel area, including end bearing lengths, are assumed to be under a uniform loading)(in.)

p_m = smallest of the calculated allowable loads (TL), from Steps 5, 6, 11, 12 and 13 (psi)

$F_{c\perp}$ = allowable bearing stress on plywood face, for load perpendicular to plane of outer ply actually in bearing (psi)²(p.17)

Then: applied load must be less than or equal to resisting capacity:

$$p_m l_e \leq 2 l_e F_{c\perp}$$

or l_e (min. at each end of panel) = $p_m l_e / (2 F_{c\perp})$

It is recommended that l_e be at least 1.5 in. (38 mm).

The bearing length of each stringer end (at least 1.5 or 2 inches) (38 or 51 mm) should be sufficient to handle the unit blast load on the plywood panel multiplied by the maximum c-c spacing of stringers and divided by the stringer width, all in accordance with Appendix B (especially Figure 6-12, which may be extended as needed based on last "bullet" paragraphs on page 6-111). See also Figures 9 later herein.

15. Glued plywood end joints (across face grain):^{2(p.25,Sec.5.6)}

15A. Scarf joints: Sketches of end-of-grain joints are available.^{4(p.9-11)} Scarf joints are made by bevelling across the plywood end edges (i.e., perpendicular to stringers and face plies of top and bottom skins), then joining the bevelled ends with an appropriate adhesive.

For the tension skin: 1 in 8 or flatter bevels transmit 100% of full allowable stress; 1 in 5 transmit 75%; use linear proportioning between these two bevels; and steeper than 1 in 5 are not to be used.^{2(p.25)}

For compression skin: 1 in 5 or flatter bevels transmit 100% of allowable stress; steeper than 1 in 5 are not to be used.^{2(p.26)}

(Note: Finger joints are too complicated to form and otherwise unsuitable for further consideration herein.)

15B. Splice-plate design (butt joints): While scarf joints are the recommended technique, this design section is presented for use if needed.^{1(p.12,Sec.2.5.6)}

For a splice-plate illustration, see Figure 1^(2,p.4) or top sketch of page facing page 1 of reference 1.

Splice-plates are to: be 1/4 in. clear of stringers at both plate ends; have skin face grain perpendicular to splice; be of grade and species group equal to the plywood spliced; and be no thinner than the skin being spliced. Tension skins with splice-plates are capable of transmitting 100% of maximum allowable stress.^{2(p.26,table)} If the splice-plate is shorter than required for use of an allowable stress in the referenced table, the allowable stress is to be reduced proportionately.

Calculate splice plate allowable load (TL) - tension:

$$p_p = (8 F / (c \ell' \ell^2)) ((EI_g) / E)$$

where: p_p = allowable load (TL) on tension splice at point of max. moment (psi)

F = allowable splice-plate stress \times proportion of panel width actually spliced^{2(p.26,table)}

c = distance from deflection neutral axis to extreme bottom (tension) fibre (in.)

c and (EI_g) are as in Figure 2A (\bar{y}) and Step 4, respectively (in.⁸ and lb-in.²)

E is for tension skin, as used in Step 3 (with the percentage increase)(psi)

ℓ and ℓ' are as before (in.)

Splice plate allowable load (TL) - compression: These plates can be approved by inspection, for 100% transmittal of allowable stress, subject to cited references.^{2(Sec.5.6.1.2 and 5.6.2.2)}

Design Stresses - Blast Protection Use versus Normal Use. The design procedure detailed above is that for normal, day-to-day uses, for which allowable stresses are prescribed.^{2(p.17),3} Such allowable stresses are totally inappropriate for one-time blast loadings, with their extremely short (essentially zero) rise-times and short durations (1 or 2 seconds in our range of interest, even for megaton weapons), inappropriate in that they result in seriously underestimating the ultimate strength of structural members under blast loadings. The reader is referred to Appendix B1 herein, especially the introductory section and the "Design Procedure" section; within the latter, specific attention is

invited to its introductory section and design steps 1 through 4. Such referenced reading covers the very basic structural dynamics, bilinear blast resistance, ductility ratio μ , etc., as well as the increased stresses used in blast-resistant design: for wood beams, the increases are four times for F_b and F_v (extreme fibre stress in bending and horizontal shear stress, respectively) and no increase in $F_{c\perp}$ (compression stress perpendicular to grain, or bearing stress). Authorities are cited.

An examination of literature helpfully furnished by the U.S. Forest Products Laboratory, Madison, Wisconsin, indicated the following: Tests on plywood stressed-skin panels (PSSPs) to destruction were few in the literature furnished, being restricted to tests on PSSPs with narrow, plywood stringers where all (predictably) failed along the stringer glue-lines; the allowable stress increase of 100% for impact loads^{2(Sec.3.3.1.1)} seems to be well supported by a test report⁵ in terms of both short duration loads and fast rate of loading, for both wood and wood-based materials (including plywood).

If one considers that "allowable" stresses in most cases (and materials types) are based on a factor of safety of about two, we can then arrive at a factor of four (including the 100% for impact) for ultimate strength under short, rapidly applied loads - a factor of four for certain stresses, at least. These stresses might include, for PSSPs:^{2(p.17)} F_b , F_t , F_c , F_v and F_s , but not $F_{c\perp}$.

Pending receipt of better information based on sorely needed tests, these dynamic stress increases were tentatively adopted for use herein; test data found were for static loadings, or for loads within severe limits on deflection, or for loadings far short of failure/collapse (as used in typical air blast loadings and design technology).^{5,6}

For a value of the ductility ratio μ , however (see App. B1, Design Step 3), a value of two was similarly and tentatively adopted for PSSPs, with a value of three tentatively continued for wood beams,* again hoping to obtain appropriate test information in the early future. For a

* See Appendix B1 following.

dynamic load simplified to a step pulse (zero rise-time to a constant loading of infinite duration), the relationship is

$$P_{dm} = P_m (1 - 1/(2\mu)) = P_m (3/4), \text{ for } \mu = 2$$

Typical Designs of PSSPs. In order to handle the many sets of design computations required in producing a reasonably adequate catalog of pre-designs, a computer program was prepared (in Dartmouth BASIC), following the above 15-step design procedure (Step 15 on design of plywood end joints was not included in the design output, although it is included in the computer program). A listing of the computer program is used, but as revised for use there, is shown in Appendix A2.

The pre-designs* covered clear span ranges from 24" to 96" for lighter panels and from 24" to 144" for heavier. Stringers included 2x4s, 2x6s and 2x8s of both relatively low and high strengths, thereby covering a considerable range of lumber species among those readily available in local lumberyards. Several plywood types/species/grades were examined, with complete pre-designs using two types/grades throughout; this was coupled with use of face ply species groups #1 and #3, except that #3 was not used for the 1-1/8" plywood because of unavailability.

The pre-designs of Table 1 are limited to two plywoods: Underlayment Interior (APA) in face ply group species #1 and #3, for 1/2", 5/8", and 3/4" thicknesses; and 2.4.1 Sturd-I-Floor Interior (APA), which is only made in #1, for the 1-1/8" thickness. These plywoods have high availability in local lumberyards in the indicated thicknesses.

Also having similar availability are three other plywood grades: Underlayment Exterior (APA), C-D Interior (APA) and C-C Exterior (APA). Pre-designs were prepared using these three plywoods in sufficient number to show that Table 1 may also be used for them with insignificant errors (all on the conservative side).

* All included panel dead load (DL), which was less than 0.1 psi in all cases, thus P_{dm} values are appropriate for laterally loaded panels used horizontally or vertically.

Table A1-1A PSSP DESIGNS FOR LOWER STRENGTH STRINGERS ($F_v = 280$ psi)*
(Beams)

Panel Width: 48 in.

| TOP SKIN | | BOT. SKIN | | STRNGRS | | REQ'D. BEAR. EACH END | | (FREE FIELD, SIDE-ON, LONG DURATION) PEAK AIR BLAST OVERPRESSURE psi VS. CLEAR SPAN | | | | | | | | | | | | | | | | | | | | |
|--------------|--------------|--------------|--------------|-------------------|--------------|-----------------------|--------------|---|----|----|----|---|----|---|----|---|----|---|----|---|----|---|----|----|-----|----|-----|----|
| Nom. Th. in. | Face Ply Grp | Nom. Th. in. | Face Ply Grp | Nom. Ply Size in. | Face Ply Grp | Ply. Skin in. | Str- ngs in. | Clear Span, ft | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | 2 | 2½ | 3 | 3½ | 4 | 4½ | 5 | 5½ | 6 | 6½ | 7 | 7½ | 8 | 8½ | 9 | 9½ | 10 | 10½ | 11 | 11½ | 12 |
| 1/2 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 4.5 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.0 | 9 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.5 | 11 | 9 | 8 | 6 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.5 | 14 | 11 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | | |
| 1/2 | #3 | 1/2 | #3 | 2X4 | 4 | 1.5 | 4.5 | 7 | 5 | | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.0 | 8 | 6 | 5 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.5 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.0 | 12 | 10 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | | | |
| 5/8 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 5.0 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.5 | 9 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 4.0 | 12 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.5 | 14 | 11 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | | |
| 5/8 | #3 | 1/2 | #3 | 2X4 | 4 | 1.5 | 4.5 | 7 | 5 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.0 | 8 | 6 | 5 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.5 | 11 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.0 | 13 | 10 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | | | |
| 3/4 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 5.0 | 8 | 6 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.5 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 4.0 | 12 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.5 | 15 | 12 | 10 | 8 | 7 | 7 | 6 | 5 | 5 | 5 | | | | | | | | | | | |
| 3/4 | #3 | 1/2 | #3 | 2X4 | 4 | 1.5 | 4.5 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.0 | 8 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.5 | 11 | 9 | 7 | 6 | 6 | 5 | | | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.5 | 13 | 11 | 9 | 8 | 7 | 7 | 6 | 5 | 5 | | | | | | | | | | | | |
| 3/4 | #1 | 3/4 | #1 | 2X4 | 4 | 1.5 | 5.0 | 8 | 6 | 5 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.5 | 10 | 8 | 6 | 5 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 4.0 | 13 | 10 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 4.0 | 15 | 12 | 10 | 9 | 8 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | |
| 3/4 | #3 | 3/4 | #3 | 2X4 | 4 | 1.5 | 5.0 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.5 | 9 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 4.0 | 12 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.5 | 14 | 11 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | |
| 1-1/8 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 5.0 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.5 | 9 | 8 | 6 | 5 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 4.5 | 13 | 11 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 4.0 | 16 | 13 | 11 | 9 | 8 | 8 | 7 | 7 | 6 | 5 | 5 | 5 | | | | | | | | | |
| 1-1/8 | #1 | 1/2 | #3 | 2X4 | 4 | 1.5 | 4.5 | 7 | 6 | 5 | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 4.5 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 4.5 | 13 | 11 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 4.0 | 16 | 13 | 11 | 9 | 8 | 8 | 7 | 7 | 6 | 5 | 5 | 5 | | | | | | | | | |

Table A1-1A

[illegible]

Table A1-1a PSSP DESIGNS FOR LOWER STRENGTH STRINGERS ($F_v = 280 \text{ psi}$)* (concluded)

Panel Width: 48 in.

| TOP SKIN | | BOT. SKIN | | STRNGRS | | REQD. BEAR. EACH END | | (FREE FIELD, SIDE-ON, LONG DURATION) PEAK AIR BLAST OVERPRESSURE psi VS. CLEAR SPAN | | | | | | | | | | | | | | | | | | | | | | |
|------------------|--------------|------------------|--------------|-------------------|-----|----------------------|------------|---|----|----|----|----|----|----|----|----|----|---|----|---|----|---|----|----|-----|----|-----|----|---|---|
| Nom. Ply Th. in. | Face Ply Grp | Nom. Ply Th. in. | Face Ply Grp | Nom. Ply Size in. | No. | Ply. Bot. Skin in. | Strngs in. | Clear Span, ft | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | 2 | 2½ | 3 | 3½ | 4 | 4½ | 5 | 5½ | 6 | 6½ | 7 | 7½ | 8 | 8½ | 9 | 9½ | 10 | 10½ | 11 | 11½ | 12 | | |
| 1-1/8 #1 | | 1/2 | #1 | 2X6 | 4 | 1.5 | 7.5 | 12 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 7.0 | 15 | 12 | 10 | 8 | 7 | 7 | 6 | 5 | 5 | 5 | 5 | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 7.0 | 21 | 17 | 14 | 12 | 11 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 1/2 | #3 | 2X6 | 4 | 1.5 | 7.0 | 11 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 7.0 | 15 | 12 | 10 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 2.0 | 7.0 | 22 | 17 | 15 | 12 | 11 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 3/4 | #1 | 2X6 | 4 | 1.5 | 8.0 | 12 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 7.5 | 15 | 12 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 1.5 | 7.0 | 22 | 17 | 14 | 12 | 11 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 3/4 | #3 | 2X6 | 4 | 1.5 | 6.5 | 27 | 22 | 18 | 15 | 13 | 12 | 11 | 10 | 9 | 8 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | | |
| | | | | | 5 | 1.5 | 7.5 | 11 | 9 | 8 | 7 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 2.0 | 7.0 | 22 | 18 | 15 | 13 | 11 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 1-1/8 | #1 | 2X6 | 4 | 1.5 | 8.5 | 13 | 11 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 8.0 | 16 | 13 | 11 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 1.5 | 7.0 | 22 | 18 | 15 | 13 | 11 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 1/2 | #1 | 2X8 | 4 | 1.5 | 6.5 | 27 | 22 | 18 | 16 | 14 | 12 | 11 | 10 | 9 | 8 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | | |
| | | | | | 5 | 1.5 | 10.0 | 16 | 12 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 1.5 | 9.5 | 30 | 24 | 20 | 17 | 15 | 13 | 12 | 11 | 10 | 9 | 8 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 1/2 | #3 | 2X8 | 4 | 1.5 | 9.5 | 15 | 12 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 10.0 | 20 | 16 | 13 | 12 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 2.5 | 10.0 | 31 | 25 | 21 | 18 | 16 | 14 | 13 | 11 | 10 | 10 | 9 | 8 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 3/4 | #1 | 2X8 | 4 | 1.5 | 10.5 | 16 | 13 | 11 | 9 | 8 | 7 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 10.0 | 21 | 17 | 14 | 12 | 10 | 9 | 8 | 8 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 1.5 | 9.5 | 30 | 24 | 20 | 17 | 15 | 13 | 12 | 11 | 10 | 9 | 9 | 8 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 3/4 | #3 | 2X8 | 4 | 1.5 | 10.0 | 15 | 12 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 10.0 | 21 | 16 | 14 | 12 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 2.5 | 10.0 | 31 | 25 | 21 | 18 | 15 | 14 | 12 | 11 | 10 | 10 | 9 | 8 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 |
| 1-1/8 #1 | | 1-1/8 | #1 | 2X8 | 4 | 1.5 | 11.0 | 17 | 14 | 12 | 10 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 10.5 | 21 | 17 | 14 | 12 | 11 | 9 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| | | | | | 7 | 1.5 | 9.5 | 29 | 23 | 20 | 17 | 15 | 13 | 12 | 11 | 10 | 9 | 8 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |

Table A1-1B PSSP DESIGNS FOR HIGHER STRENGTH STRINGERS ($F_v = 380$ psi)*
Panel Width: 48 in.

| TOP SKIN | | BOT. SKIN | | STRNGS | | REQD. BEAR. EACH END | | (FREE FIELD, SIDE-ON, LONG DURATION) PEAK AIR BLAST OVERPRESSURE psi VS. CLEAR SPAN | | | | | | | | | | | | | | | | | | |
|--------------|--------------|--------------|--------------|-------------------|---------------------|----------------------|-----|---|----|----|----|----|----|---|----|---|----|---|----|---|----|---|----|----|-----|----|
| Nom. Th. in. | Face Ply Grp | Nom. Th. in. | Face Ply Grp | Nom. Ply Size in. | Ply. Bot. Skins in. | Str-ngs in. | | Clear span, ft. | | | | | | | | | | | | | | | | | | |
| | | | | | | | | 2 | 2½ | 3 | 3½ | 4 | 4½ | 5 | 5½ | 6 | 6½ | 7 | 7½ | 8 | 8½ | 9 | 9½ | 10 | 10½ | 11 |
| 1/2 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 3.5 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.5 | 11 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 14 | 11 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | |
| | | | | | 9 | 1.5 | 2.5 | 17 | 14 | 11 | 10 | 8 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | |
| 1/2 | #3 | 1/2 | #3 | 2X4 | 4 | 1.5 | 3.5 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.0 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 2.5 | 13 | 10 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 2.5 | 15 | 12 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | |
| 5/8 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 3.5 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.5 | 11 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 14 | 11 | 10 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | |
| | | | | | 9 | 1.5 | 2.5 | 17 | 14 | 11 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | |
| 5/8 | #3 | 1/2 | #3 | 2X4 | 4 | 1.5 | 3.5 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.0 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 2.5 | 13 | 10 | 9 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 2.5 | 15 | 12 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | |
| 3/4 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 3.0 | 8 | 6 | 5 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.0 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 15 | 12 | 10 | 9 | 8 | 7 | 6 | 5 | 5 | 5 | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.0 | 18 | 14 | 12 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | | | | | | | |
| 3/4 | #3 | 1/2 | #3 | 2X4 | 4 | 1.5 | 3.5 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.0 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 13 | 11 | 9 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | |
| | | | | | 9 | 1.5 | 2.5 | 16 | 13 | 11 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | 5 | | | | | | | | |
| 3/4 | #1 | 3/4 | #1 | 2X4 | 4 | 1.5 | 3.5 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.5 | 11 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 16 | 13 | 11 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | 5 | | | | | | | | |
| | | | | | 9 | 1.5 | 3.0 | 19 | 15 | 13 | 11 | 10 | 8 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | |
| 3/4 | #3 | 3/4 | #3 | 2X4 | 4 | 1.5 | 3.5 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.5 | 11 | 9 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 14 | 11 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | | |
| | | | | | 9 | 1.5 | 2.5 | 17 | 14 | 11 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | |
| 1-1/8 | #1 | 1/2 | #1 | 2X4 | 4 | 1.5 | 3.0 | 7 | 6 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.0 | 10 | 8 | 7 | 6 | 5 | 5 | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 16 | 12 | 10 | 9 | 8 | 7 | 6 | 6 | 5 | 5 | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.0 | 20 | 16 | 14 | 12 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | | | | | |
| 1-1/8 | #3 | 1/2 | #3 | 2X4 | 4 | 1.5 | 3.0 | 7 | 6 | 5 | | | | | | | | | | | | | | | | |
| | | | | | 5 | 1.5 | 3.0 | 10 | 8 | 6 | 5 | 5 | | | | | | | | | | | | | | |
| | | | | | 7 | 1.5 | 3.0 | 15 | 12 | 10 | 8 | 7 | 7 | 6 | 5 | 5 | 5 | | | | | | | | | |
| | | | | | 9 | 1.5 | 3.0 | 20 | 16 | 13 | 11 | 10 | 9 | 8 | 7 | 7 | 6 | 6 | 5 | 5 | 5 | | | | | |

Table A1-1B PSSP DESIGNS FOR HIGHER STRENGTH STRINGERS ($F_v = 380$ psi)* (continued)
Panel Width: 48 in.

| TOP SKIN | | | | BOT. SKIN | | STRNGRS | | REQD. BEAR. EACH END | | (FREE FIELD, SIDE-ON, LONG DURATION) PEAK AIR BLAST OVERPRESSURE psi VS. CLEAR SPAN | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|-------------------------|-------------------------|---|----|---|----|---|----|---|----|---|----|---|----|---|----|---|----|----|-----|----|-----|----|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|----|
| Nom. Th. in. | Face Ply Grp | Nom. Th. in. | Face Ply Grp | Nom. Th. in. | Face Ply Grp | Nom. Th. in. | Face Ply Grp | Ply. in. | Bot. Str- ngs in. | Clear Span, ft | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | 2 | 2½ | 3 | 3½ | 4 | 4½ | 5 | 5½ | 6 | 6½ | 7 | 7½ | 8 | 8½ | 9 | 9½ | 10 | 10½ | 11 | 11½ | 12 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1-1/8 | #1 | 3/4 | #1 | 2X4 | 4 | 1.5 | 3.0 | 8 | 6 | 5 | 5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | </ |

Table A1-1B (concluded)

[illegible]

* For dynamic loads (blast) use herein, F_v values were four times the normal use values, as published in Reference 3's Supplement.

PSSP Upgrading Example - Closure

Try one of the PSSP designs as a horiz. closure over an aperture (such as a stairwell), in the floor over a candidate basement shelter.

Assume use of the last PSSP design on page A1-20: $3/4"$ #1 both skins, 9 - 2×6 stringers (higher strength). Assume clear span of 4 ft.

From Table A1-1B: peak blast overpr. = 16 psi

Factors included in the blast design are: 2.0 for impact duration of loading; 2.0 for factor of safety; and 0.75 for $\mu = 2$. See page A1-12.

Basic (static) load strength of PSSP =

$$\frac{16 \text{ psi}}{2.0 \times 2.0 \times 0.75} = 5.33 \text{ psi}$$

Fallout shielding soil:

Assume 18" th. layer of 95 pcf soil.

Allow 15% added stress for load duration less than 2 mos.

$$\text{Static load strength used up for fallout soil} = \frac{1.5 \times 95}{144} \times \frac{1}{1.15} = 0.86 \text{ psi}$$

Static load strength remaining = 4.47 psi

Blast:

Use static load strength remaining (4.47), increased by the 3 factors taken out above:

\therefore Peak blast overpressure strength:

$$4.47 \times 2.0 \times 2.0 \times 0.75 = \underline{13.41 \text{ psi}}$$

Fabrication

Fabrication of plywood stressed-skin panels (PSSPs) is concisely yet thoroughly described in a publication available upon request.⁷ The publication emphasizes the need for adequate gluing in order to develop the composite action of plywood stressed-skins and the stringers. Results from mechanical-pressure gluing have been found to be generally superior to nail-gluing (latter, properly performed, is the basis for the design section herein, however); supplies needed for nailing may have to be estimated in advance, for which the following extract will be useful:^{7(p.6)}

"Nails shall be at least . . . 6d for 1/2" to 7/8" plywood, 8d for 1" to 1-1/8" plywood, . . . spaced not to exceed . . . 4" (along the framing members) for plywood 1/2" and thicker, using one line for lumber 2" thick or less, and two lines for lumber more than 2" and up to 4" thick (wide)."

Glue, recommended for use in accordance with the manufacturers' recommendations, should be one of the two following types: Interior, for use when the equilibrium moisture content of the materials used does not exceed 18%, may be casein type with a mold inhibitor, conforming with ASTM Specification D3024; Exterior, for higher moisture contents, conforming to ASTM Specification D2559.

Nailing without gluing simply does not exploit the strength of PSSPs and the capabilities of their materials - the nails can too easily yield along the grain of the stringers so that they are inadequate as a shear transfer mechanism. The sparse test data found clearly show concern with deflection, not flexural, behavior as the controlling criterion, thus ultimate strength is not considered.

In the absence of some kind of ultimate strength behavior tests, the author has no basis for a recommendation, even heavily qualified, on the relative strength of nailed-only to nail- or pressure-glued PSSPs.

Further Work

As mentioned in the section on "Design Stresses . . ." above, tests for ultimate strength (i.e., through to failure/collapse, recording full load-deflection history including time) under dynamic loadings, or even under static loadings if well into the plastic range, are badly needed as a better basis for design of PSSPs as blast closures. With such information, one might be, for example, justified in design procedure use of numerical integration of the equation of motion, instead of the less rigorous approach of using a step-pulse loading of infinite duration, as has been done in preparing the design procedure above. Further, the wood design stresses would be better known, of course, as would the composite behavior including the primary cause of each test PSSP's failure mode. Some tests have been completed at the Ballistics Research Laboratory, U. S. Army, Aberdeen Proving Grounds, Maryland 21005, and more are planned.

NOTATION

| | |
|----------------|--|
| A | total x-section area of all stringers |
| A | x-section area of parallel-grain plies outside the critical plane for rolling shear |
| A | total x-section area of all stringers and skins $A_{//}$ (beam-columns) |
| $A_{//}$ | x-section area (finished) of plies // stringers, in each skin |
| A_{\perp} | x-section area (finished) of plies \perp stringers, in each skin |
| b, b_b, b_t | basic stringer spacing; subscripts are for bottom and top skins, respectively |
| C | factor for maximum allowable deflection (usually based on LL only) |
| c | distance from neutral axis (for deflection or bending, as locally defined) to extreme fibre (of skin under check) (see \bar{y}) |
| d | moment arms for various x-sectional areas (subscripted A's), used in I_g and I_n calculations |
| $d_s = c - y'$ | |
| E | modulus of elasticity |
| E_{st} | E of stringers |
| (EI_g) | panel parameter, calculated using neutral axis for deflection |
| (EI_n) | panel parameter, calculated using neutral axis for bending moment |
| F | allowable stress, general |
| F | allowable splice-plate stress multiplied by proportion of panel width actually spliced |
| F_c | allowable stress, compression in plane of plies // stringers |
| F_c | allowable stress, compression // grain in stringers |
| $F_{c\perp}$ | allowable stress, bearing on plywood face |
| F_s | allowable stress, rolling shear |
| F_t | allowable stress, tension in plane of plies // stringers |
| F_t | allowable stress, tension // grain in stringers |
| F_v | allowable stress, horizontal shear, in stringers |
| G | modulus of rigidity in stringers |
| I | moment of inertia, total x-sectional area (finished) of all stringers |
| I | moment of inertia, in direction \perp stringers, of top skin A_{\perp} |
| I_g | gross I of total panel x-section about deflection N.A. |

NOTATION (concluded)

| | |
|---------------------|---|
| I_n | gross I of total panel x-section about bending N.A. |
| I_o | gross moment of inertia of x-section portion about own centroidal axis |
| $I_{//}, I_{\perp}$ | moment of inertia for plies, corresponding to $A_{//}$ and A_{\perp} areas |
| ℓ | clear span of panel, in direction of stringers |
| ℓ_e | plywood end bearing length required at <u>each</u> end of panel |
| ℓ' | panel width (skins only), perpendicular to ℓ |
| ℓ'' | clear distance between stringers |
| p | design LL or TL (use load related to assumed C factor) |
| p_a | allowable axial load (TL) in beam-column |
| p_b | allowable load (TL) - bending moment |
| p_d | allowable load (TL) - panel deflection |
| p_{dm} | same as p_m but specifically for dynamic loads/loadings |
| p_m | smallest of calculated allowable transverse loads (TL) (in PSSPs for: deflection, bending moment, rolling shear and horizontal shear) |
| p_p | allowable load (TL) - tension splice-plate |
| p_s | allowable load (TL) - rolling shear |
| p_t | allowable load (TL) - top skin deflection |
| p_v | allowable load (TL) - horizontal shear |
| Q_s | statical moment, about neutral axis for deflection, of parallel plies outside critical plane for rolling shear (see A above) |
| Q_v | statical moment, about neutral axis for deflection, of stringers and $A_{//}$ plies x-sectional areas, taken <u>either</u> above <u>or</u> below that axis (used in horizontal shear allowable load calculations) |
| t | glueline width of each stringer (used in $\Sigma F_s t$) |
| t | sum of stringer widths, including side projecting portions |
| t_h | thickness of header (solid across all panel stringers) |
| y | moment arms used in neutral axes calculations |
| y' | half-thickness of parallel plies outside critical plane for rolling shear (see Q_s and A above) |
| \bar{y} | distance from neutral axis to bottom extreme fibre (calculated in both deflection and bending moment calculations for neutral axis) |
| μ | ductility ratio (maximum to elastic deflection, of a selected point, usual at mid-span or mid-height) |

REFERENCES

1. "Design of Plywood Stressed-Skin Panels," Supplement 3 to Plywood Design Specification (PDS), American Plywood Association, 1119 A Street, Tacoma, Washington 98401, revised December 1976.
2. Plywood Design Specification (PDS), American Plywood Association, revised December 1976.
3. National Design Specification for Stress-Grade Lumber and Its Fastenings, National Forest Products Association, 1619 Massachusetts Avenue, N.W., Washington, D.C. 20036, 1973 edition, with Table 1 Supplement (allowable unit stresses, published separately), April 1973, revised November 1974.
4. Wood Handbook: Wood as an Engineering Material, Forest Products Laboratory, Forest Service, U.S. Department of Agriculture, Agriculture Handbook No. 72 (Government Printing Office, Washington, D.C.), revised August 1974.
5. Gerhards, C. C., Effect of Duration and Rate of Loading on Strength of Wood and Wood-Based Materials, USDA Forest Service Research Paper FPL 283, 1977, U.S. Forest Products Laboratory, Madison, Wisconsin 53705.
6. Drawsky, R. H., and J. M. Carney (editor), Stressed Skin Panel Tests, Laboratory Report No. 82, Douglas Fir Plywood Association, Tacoma, Washington, April 1960.
7. Fabrication of Plywood Stressed-Skin Panels, Plywood Fabrication Specification SS-8, American Plywood Association, Tacoma, Washington 98401, 1974.

Appendix A2

PLYWOOD STRESSED-SKIN PANELS (TWO-SIDED) AS BEAM-COLUMNS

CONTENTS

| | |
|--|-------|
| Design | A2-1 |
| A. Design Procedures | A2-5 |
| B. Design Stresses (Blast versus Normal Loads) and Ductility . . | A2-7 |
| Applications | A2-8 |
| NOTATION | A2-23 |
| REFERENCES | A2-27 |

TABLES

| | |
|--|-------|
| A2-1 PSSP Design: Computer Program (HLMPSp) Listing | A2-9 |
| A2-2 PSSP Designs for Lower and Higher Strength Stringers ($F_v = 280$ and 380 psi) (Columns and Beam-Columns) | A2-18 |

(BLANK)

A2-iv

Appendix A2

PLYWOOD STRESSED-SKIN PANELS (TWO-SIDED) AS BEAM-COLUMNS

Design

In the preceding Appendix A1, a design procedure, useful stresses, and typical designs were developed for plywood stressed-skin panels (PSSPs) and their estimated ultimate/collapse strength capacity for lateral/transverse (blast) loads. Such panels are of considerable interest to the overall purposes of the project work because abundant supplies of wood for stringers and plywood for skins are available in local lumberyards. Thus their potential is high for use in expedient upgrading of existing basements for shelter against the combined effects of a nuclear weapon detonation. These panels are treated in Appendix A1 in terms of their usefulness as closures, that is to resist transverse blast loads. The purpose of this appendix is to develop procedures for use of such panels as beam-columns, that is to resist axial (blast) loads, without or combined with transverse/lateral (blast) loads.

The basic references of Appendix A1 also contain information pertinent to beam-column design, or simple column design alone [1(sec.3),2].¹ The formula provided for the latter is

$$P_a = 3.619 (EI_g) / \ell^2 \quad (1)$$

or

$$P_a = F_c A \quad (2)$$

whichever value is less, where²

P_a = allowable axial load (lbs), if axial load only exists

(EI_g) = stiffness factor for moment deflection [1(Sec.2.4.3)]
(lbs-in.² for full panel)(from Step 4, Appendix A1)

ℓ = clear span of member (simply-supported/pin-ended)(in.)

¹ Brackets are used herein to indicate sources in the References list at the end of this appendix.

² Variables are defined herein at point of first use and in Notation at end of appendix.

F_c = allowable compressive stress (parallel to grain) for plywood skins (psi) [2(p.17)], corrected for buckling [1(Sec.2.5.4)]

A = total x-sectional area of longitudinal grain material in both plywood skins and stringers (in.²)

The interaction formula provided for beam-columns is

$$P/P_a + (M/S) / F_c \leq 1 \quad (3)$$

where

P = allowable axial load (lbs), under combined loading

M = allowable bending moment (in.-lb), under combined loading

S = I_n / c

in which

S = section modulus of full panel (in.³)

I_n = bending moment of inertia of full panel (in.⁴)

c = distance from N.A. (bending) to extreme fiber in compression (in.)

Calculations of I_n and c (or \bar{y}) are shown in Appendix A1, Figure 3, and Steps 7 and 8.

Assuming that the authors of References [1 and 2] used theory including a solid, rectangular cross-section column, then $I = bd^3/12$. Using this for I_g and solving Equations 1 and 2 for F_c (also recalling that $r^2 = I/A$) leads to

$$F_c = (0.3016 E) / (\ell/d)^2 = (\pi^2 E) / (2.727(\ell/r)^2)$$

where

I_g = gross moment of inertia of cross section (in.⁴)

b = least dimension of solid rectangular cross section (in.)

d = greater dimension of solid rectangular cross section (in.)

r = radius of gyration (in.)

E = modulus of elasticity (psi)

The equation's left form is found in Reference [3(p.15 and 65)], under simple solid-column design, indicating that the assumption above is cor-

rect. The equation's right form is Euler's equation [4(Eq.3 and 14)] in one of its many forms. Euler's equation is suitable for simply-supported/pin-ended long columns at ultimate (not allowable) load; it is non-conservative [4] when applied to columns with ℓ/r less than about 150,³ a value much too high for the uses contemplated herein; and the above constant, 2.727, is a factor of safety.

The serious concern with using the foregoing for blast loads is that various approximations have been introduced that can be collectively tolerated because of the allowable/working stress approach for normal uses. Where one is dealing with collapse strength of a column or beam-column, the design approach must take dynamic buckling directly into account and must consider deflection, usually at mid-height, caused by all loads, plus initial eccentricity if it is known or can be estimated. Thus it was concluded that a beam-column design approach should include iteration toward an estimated total deflection from all sources, i.e., initial eccentricity if any, as well as deflection from moments due to transverse and axial loads.⁴ The following design approach includes such iteration; it comes from Reference [4(p.5-42, Eq.18)], and is converted to PSSP Notation (Appendix A1 and herein). Henceforth

$$F_c = P/A + (M + P_y)(c/I_n) \quad (4)$$

where

M_{max} = maximum moment caused by transverse loads only (in.-lb)

y = deflection of column at M (in.)

The referenced source suggests iteration toward a final value for y , using for a first trial value that from M alone⁵ in the right-side second term of Equation 4. An approach to performing the suggested iteration follows, using the simply-supported/pin-ended member assumption stated earlier.

From Reference [6], for transverse loads⁵ (and modified to Notation herein):

$$M_{mid-ht} = p_m \ell' \ell^2 / 8 \quad (5)$$

$$\bar{y}_{mid-ht} = 5 p_m \ell' \ell^4 / (384(EI_n)) \quad (6)$$

³ Meaning, for a rectangular column cross-section, ℓ/d less than about 43 (but it's about 24 per Ref.[3],p.65).

⁴ An iterative numerical method for analyzing a beam-column is available [5(App.A,p.6-160)].

⁵ That is, with $P = 0$.

where

$\bar{y}_{\text{mid-ht}}$ = deflection of column at M_{max} (transverse loads only)(in.)

Thus, for combined transverse and axial loads:

$$y_{\text{mid-ht}} = 5 \ell^2 (M_{\text{mid-ht}} + P_a y) / (48(EI_n)) \quad (7)$$

where

p_m = smallest of calculated allowable transverse (only) loads
(in PSSPs, calculated loads for: deflection, bending moment,
rolling shear and horizontal shear) (psi) (from Appendix A1
design of PSSPs)

$y_{\text{mid-ht}}$ = deflection of column at M (in.)

ℓ' = width of PSSP skins (perpendicular to stringers) (in.)

(EI_n) = stiffness factor for bending moment [1(Sec.2.5.3)] (lb-in.²
for full panel) (from Step 8, Appendix A1)

y = trial y at mid-height

For examining locations other than at mid-height of the (prismatic)
beam-column, similar equations to Equations 5 to 7 would then be [6]:

$$M_x = p_m \ell' x (\ell - x) / 2 \quad (8)$$

$$\bar{y}_x = p_m \ell' x (\ell^3 - 2\ell x^2 + x^3) / (24(EI_n)) \quad (9)$$

$$y_x = (M_x + P_a y) (\ell^2 + \ell x - x^2) / (12(EI_n)) \quad (10)$$

where

x = location being examined (length along member) (in.)

The overall design approach just described should be applied with
due regard to variation in units: some of the parameters are for full
panel width, some would usually be applied to design of a one-inch wide
strip of panel. All units, therefore, should be checked for values
appropriate to one width or the other. All formulas herein are dimen-
sionally consistent; there are no dimensions hidden in constants.

A. Design Procedures

Steps in the design procedure follow.

1. Assume a trial section and clear span/height (in direction of stringers); see Figure 1A, Appendix A1. Use only stress-graded stringers, with face grain of both plywood skins parallel to the stringers. Plan connections to PSSP such that loads are only axial, on pinned ends, with or without uniformly distributed transverse/lateral loads.

2. Same as Step 2, Appendix A1.

3. Calculate A as in Step 3 and Figure 2A, Appendix A1.

4-6. Same as Steps 7 through 9, respectively, of Appendix A1. The c value needed later comes from Step 4 (either \bar{y} in Figure 3A, Appendix A1, or the actual PSSP thickness minus \bar{y} , probably the latter but certainly whichever value is for the compression side).

At this point, values for the following variables used in this appendix are known: A (from Step 3), c (4), (EI_N) (5), F_c (6), I_N (5), ℓ (1), and ℓ' (1).

7. Set $M = 0$ and Equation 4 becomes:

$$F_c = P_a/A + P_a(cy/I_N) \quad \text{or} \quad P_a = F_c / (1/A + cy/I_N) \quad (11)$$

From Equation 2:

$$F_c = P_a / A \quad (12)$$

Whether $y \geq 0$ (with trial design F_c held constant), the P_a of Equation 12 will be \geq the P_a of Equation 11, thus Equation 11 is used below. This P_a is the maximum allowable axial load, applied when $M = 0$ (i.e., transverse/lateral load is zero).

8. Set $M = 0$, then iterate on trial y , using as a minimum value/eccentricity (in.)

$$y = 0.01 \ell / d'$$

where

$$d' = \text{depth of PSSP stringers (in.)}$$

then solving Equation 11 for P_a and Equation 7 with trial y value on right; repeat until y values on right and left sides of Equation 7 are equal or acceptably close (say 1% to 5%).

9. For combined transverse and axial loads, the PSSP must first be investigated, using Steps 1-14, Appendix A1, to find p_m , the peak tran-

verse load capability with $P_a = 0$; if a dynamic loading p_{dm} value was found, it must be corrected to an equivalent static load p_m :

If the PSSP is one of those pre-designed and shown in Appendix A1, its p_{dm} value may be read from Figures 5-7 there, as the air blast peak overpressure (psi). However, such p_{dm} is based on the Design Stresses-Blast . . . section⁶ of the appendix, which includes use of $\mu = 2$ and a step pulse, meaning that the static equivalent p_m is $4/3$ the chart value p_{dm} (still with design stresses greatly increased over those for normal, not blast-resistant, use). A value for μ and blast design stresses in beam-columns, in contrast to normal-use design stresses, are discussed in the next section.

Subscripts for mid-height will be dropped from here on, for convenience; the PSSP should be prismatic and with negligible initial eccentricity,⁷ therefore all M and y values will be for mid-height (mid-length) for a vertical (horizontal) beam-column.

10. Solve Equations 5 and 6 for M and related y , when $P = 0$.

From Step 8, values of P_a and related y , when $M = 0$, are known. Thus the two extreme values of transverse or axial load capacity, with their related mid-height/mid-length deflections, are known at this point. These unique values will be identified as M_{max} (or its related p_m of Step 9) and P_a in the steps below.

11. Assume: a value for P between P_a and zero, and a first trial value⁷ for y proportional to those found in Steps 8 and 10 (for P_a and for $P = 0$, respectively).

12. Solve Equation 4 for M :

$$M = (I_n / c) (F_c - P / A) - Py, \quad \text{but } \leq (M_{max} - Py) \quad (13)$$

13. Solve Equation 7 using the trial y on the right side. Compare the left-side y , found from solving Equation 7, with the trial y used. If the two y values are not in acceptable agreement (say, 1% to 5%), use the left-side value as the new trial value⁷ of y and repeat Steps 12 and 13; otherwise, proceed with the next design step.

14. Find allowable p'_m related to the final M of Step 12:

$$p'_m = (M_{(step\ 12)} / M_{max}) p_{m(step\ 9)} \quad (14)$$

⁶ Includes, at the end of that section, a definition of step pulse and the basic relationship $p_{dm} = p_m (1 - 1/(2\mu))$. It follows that $P_{da} = P_a (1 - 1/(2\mu))$, but μ will usually be different in the two uses: (1) lateral loads only; or (2) axial loads only, or axial and lateral loads.

⁷ But using not less than the minimum eccentricity value of Step 8.

(This allowable p'_m could also be found using Equation 5 with the final M of Step 12, or Equation 6 with the final left-side y of Step 13.)

15. With allowable P (Step 11) and p'_m (Step 14) known, one pair of pertinent values for the assumed trial section PSSP has been found, besides the two pairs of extreme values (Step 10). Other pairs of values are found by repeating Steps 11-14. To complete the design, a new trial section(s) may have to be assumed, repeating Steps 1-14.

B. Design Stresses (Blast versus Normal Loads) and Ductility

The user of this appendix is referred to a section with the same title, appearing in Appendix A1; the information there is applicable to this appendix except for the last paragraph, which deals with a value for the ductility ratio μ .

For a value of the ductility ratio μ for beam-columns, $\mu = 1$ is recommended for use because of buckling considerations. Increases of normal-use stresses are those already recommended for adoption.⁸ If a step pulse (defined in the Appendix A1 section) is appropriate, then the footnote to design Step 9 applies, thus $P_{da} = P_a/2$ ($P_d = P/2$) and $P_{dm} = p_m/2$ ($p'_{dm} = p'_m/2$); p_{dm} or p'_{dm} is the allowable load from peak exterior blast incident overpressure on the PSSP, and p_m or p'_m is the pseudostatic uniform load capacity, respectively.

It is possible that a significant rise time should be applied to the axial blast load but probably not. However, the transverse blast load occurring inside a basement shelter is very likely to have a significant rise time as well as a significant reduction in peak value from the blast peak exterior incident overpressure, due to room filling.⁹ If a rough approximation must be suggested it would be that $p_{dm} = p_m$ ($p'_{dm} = p'_m$) where only human-size doorways and typical basement windows constitute the apertures; large openings would indicate use of $p_{dm} = p_m$ times 3/4, even approaching 1/2. This suggested approach attempts to consider both lengthened rise time and reduced peak value of overpressure in terms of that incident on the basement's exterior.

⁸ See Appendix A1 section with same title as this one: multiply normal-use F_b , F_v , and F_c values by four, but not F_{c1} or E values.

⁹ See published guidance on design of combined nuclear weapons effects shelter in planned (new) basements, References [5 and 7], especially the latter's Appendix E appearing in Volume 3; the same Appendix E, written by J. R. Rempel, a colleague, was published in an earlier report, Reference [8]. The Appendix E technique was used to produce a short section and two design graphs [7 and 8 (p.8-112 to 8-114)] giving maximum interior pressure and time to reach such pressure, both in terms of V/A (room volume/total aperture area).

Applications

The computer program used (for PSSP design of "beam/slab" type members) in the earlier publication of Appendix A1, was updated to add beam-column and column PSSP design. Table A2-1 shows a listing of the program, as well as a sample problem. The program listed does not automatically increase normal-use design stresses⁸ (they must be entered with multiples, if any, already included by the user), and it does not include the dynamic factors for blast loads (section B above, second paragraph).

AD-A097 915

SRI INTERNATIONAL MENLO PARK CA

F/G 13/13

UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: PREDE--ETC(U)

JUL 80 H L MURPHY

DCPA01-77-C-0227

NL

UNCLASSIFIED

EX-9
2-11-80




Table A2-1 (continued)

```

1330 PRINT "STEP 5:"
1340 INPUT L1
1350 PRINT
1360 PRINT
1370 GOTO 1430
1380 IF L1=INT(L1) THEN 1410
1390 LET L1=INT(L1)+1
1400 GOTO 1420
1410 LET L1=INT(L1)
1420 GOTO 1530
1430 PRINT "ENTER C FACTOR IN MAX ALLOWABLE DEF. L/C"
1440 PRINT " (HLMSP1, STEP 6: PDS3, P. 9)"
1450 INPUT C1
1460 PRINT
1470 PRINT "IS C FACTOR IN TERMS OF LL OR TL?"
1480 INPUT AS
1490 IF AS="TL" THEN 1570
1500 IF AS="LL" THEN 1570
1510 GOTO 1470
1520 LET P1=1/C1+1.2+5*1.2/2/384/E4+.15/A2/1.06+E3*1.03
1530 IF AS="TL" THEN 1620
1540 LET N1=P1
1550 GOTO 1610
1560 PRINT "ENTER DESIGN DL (PSI)"
1570 INPUT P9
1580 PRINT
1590 PRINT
1600 RETURN
1610 LET P1=P1+P9
1620 PRINT
1630 PRINT "STEP 5:"
1640 PRINT "P-SUB D = "P1" PSI"
1650 IF AS="TL" THEN 1670
1660 PRINT "MADE UP OF LL = "N1" AND DL = "P9" PSI"
1670 PRINT "PANEL DEF. (MID-SPAN, SS) = "L1/C1" IN."
1680 REM *****
1690 REM * STEP 6 (HLMSP1) *
1700 REM *****
1710 GOTO 1780
1720 PRINT "STEP 6:"
1730 PRINT "ENTER 1 FOR TOP SKIN (STRESS PERPENDICULAR TO STRINGERS)"
1740 PRINT " (PDS+P. 16, CDL. 9) (IN. 4/ET)"
1750 INPUT I8
1760 PRINT
1770 RETURN
1780 IF AS="TL" THEN 1810
1790 LET P7=384*E1*18/12/C1/L4*3+P9
1800 GOTO 1820
1810 LET P7=384*E1*18/12/C1/L4*3
1820 PRINT
1830 PRINT "STEP 6:"
1840 PRINT "P-SUB I = "P7" PSI"
1850 PRINT " TOP SKIN DEF. BETW. STRINGERS = "L4/C1" IN."
1860 PRINT
1870 REM *****
1880 REM * STEP 7 (HLMSP1) *
1890 REM *****
1900 GOTO 1970
1910 PRINT "STEP 7:"
1920 PRINT "ENTER EFFECTIVE WIDTHS (AS FLANGES) OF TOP, BOT. SKINS"
1930 PRINT " (HLMSP1, FIG. 3A: PDS3, P. 10, PT. FIG.)"
1940 INPUT W1, W2
1950 PRINT
1960 RETURN
1970 LET N15J=A1/12+M1+A2/12+M2+A3
1980 LET N16J=A1/12+M1+E1*1.1+A2/12+M2+E2*1.1+A3+E3*1.03
1990
2000 LET N17J=A1/12+M1+E1*1.1+Y1+A2/12+M2+E2*1.1+Y2+M2+E3*1.03+Y3
2010 PRINT "STEP 7:"
2020 PRINT "BENDING N15J = "Y18" IN."
2030 PRINT "HLMSP1 FIG. 3A: TOTAL C (PLUS TOTAL OF AREAS)"
2040 PRINT " (N15J+N16J+N17J)"
2050 PRINT
2060 REM *****
2070 REM * STEP 8 (HLMSP1) *
2080 REM *****
2090 LET J4=Y1-Y2
2100 LET J4=Y4-Y2
2110 LET D6=ABS(Y4-Y3)
2120 LET N1=1/12+M1+A1/12+M1+D4*2
2130 LET N2=1/12+M2+A2/12+M2+D5*2
2140 LET N3=1/12+M3+A3/12+M3*2
2150 LET J9=N1+A2+N3
2160 LET N4=E1*1.1+N1
2170 LET N5=E2*1.1+N2
2180 LET N6=E3*1.03+N3
2190 LET J5=N4+N5+N6
2200 PRINT "STEP 8:"
2210 PRINT "E1-SUB N1 = "J5" LB-IN. 2"
2220 PRINT "HLMSP1 FIG. 3B: TOTAL C: "J9+E5
2230 REM *****
2240 REM * STEP 9 (HLMSP1) *
2250 REM *****
2260 GOTO 2330
2270 PRINT "STEPS 9 & 10:"
2280 PRINT "ENTER TOP SKIN F-SUB C & BOT. SKIN F-SUB T (PSI)"
2290 PRINT " (PDS+P. 17)"
2300 INPUT F1, F2
2310 PRINT
2320 RETURN
2330 IF L4/B1 < .5 THEN 2450
2340 IF L4/B1 < 2 THEN 2360
2350 PRINT "WARNING: STRINGER SPACING SHOULD BE <= 2 B (SUB T OR C)"
2360 PRINT " (B VALUES FROM STEP 2)"
2370 PRINT
2380 IF L4/B1 < 1 THEN 2410
2390 LET F1=F1*1-.333*(L4/B1-.5)
2400 GOTO 2450
2410 LET F1=F1*.667
2420 REM *****
2430 REM * STEP 10 (HLMSP1) *
2440 REM *****
2450 IF L4/B2 < .5 THEN 2570
2460 IF L4/B2 < 2 THEN 2500
2470 PRINT "WARNING: STRINGER SPACING SHOULD BE <= 2 B (SUB T OR C)"
2480 PRINT " (B VALUES FROM STEP 2)"
2490 PRINT
2500 IF L4/B2 < 1 THEN 2530
2510 LET F2=F2*1-.333*(L4/B2-.5)
2520 GOTO 2570
2530 LET F2=F2*.667
2540 REM *****
2550 REM * STEP 11 (HLMSP1) *
2560 REM *****
2570 PRINT "STEPS 9 & 10:"
2580 PRINT "F-SUB C AND T-RESP Y = "F1" AND "F2" PSI"
2590 GOTO 2660
2600 PRINT "STEP 11:"
2610 PRINT "ENTER OVERALL PANEL THICKNESS (IN.)"
2620 INPUT T1
2630 PRINT
2640 RETURN
2650

```


Table A2-1 (continued)

```

2600 LET N1=8-YA/L2-L1/2+E5 (E101.1)
2610 LET N2=8-YA/L2-L1/2+E5 (E201.1)
2620 LET N3=F101
2630 LET N101=F201
2640 IF N101=0 THEN 2730
2650 LET N101=N101
2660 LET N101=N101
2670 LET N101=N101
2680 LET N101=N101
2690 LET N101=N101
2700 LET N101=N101
2710 LET N101=N101
2720 LET N101=N101
2730 LET N101=N101
2740 LET N101=N101
2750 LET N101=N101
2760 LET N101=N101
2770 LET N101=N101
2780 LET N101=N101
2790 LET N101=N101
2800 LET N101=N101
2810 LET N101=N101
2820 LET N101=N101
2830 LET N101=N101
2840 LET N101=N101
2850 LET N101=N101
2860 LET N101=N101
2870 LET N101=N101
2880 LET N101=N101
2890 LET N101=N101
2900 LET N101=N101
2910 LET N101=N101
2920 LET N101=N101
2930 LET N101=N101
2940 LET N101=N101
2950 LET N101=N101
2960 LET N101=N101
2970 LET N101=N101
2980 LET N101=N101
2990 LET N101=N101
3000 LET N101=N101
3010 LET N101=N101
3020 LET N101=N101
3030 LET N101=N101
3040 LET N101=N101
3050 LET N101=N101
3060 LET N101=N101
3070 LET N101=N101
3080 LET N101=N101
3090 LET N101=N101
3100 LET N101=N101
3110 LET N101=N101
3120 LET N101=N101
3130 LET N101=N101
3140 LET N101=N101
3150 LET N101=N101
3160 LET N101=N101
3170 LET N101=N101
3180 LET N101=N101
3190 LET N101=N101
3200 LET N101=N101
3210 LET N101=N101
3220 LET N101=N101
3230 LET N101=N101
3240 LET N101=N101
3250 LET N101=N101
3260 LET N101=N101
3270 LET N101=N101
3280 LET N101=N101
3290 LET N101=N101
3300 LET N101=N101
3310 LET N101=N101

```

Table A2-1 (continued)

```

4060 INPUT L5
4070 PRINT
4080 RETURN
4090 IF L5<L2 THEN 4130
4100 PRINT "SPICE-PLATE LENGTH MUST BE SHORTER THAN PANEL WIDTH"
4110 PRINT
4120 GOSUB 4040
4130 LET P=80*(L5/L2)*Y2/L2*(L1+L2)*E4/(E2*L1)
4140 PRINT "P-SUB P = "P68" PSI"
4150 PRINT "IF P-SUB P < P-SUB M ("TP5") OR DESIGN TL, WHICHEVER"
4160 PRINT "CRITERION IS USED, SPICE-PLATE SHOULD BE REDESIGNED"
4170 PRINT "OR REDUCED (P-SUB P CALC'D ON MID-SPAN LOCATION)"
4180 GOSUB 5000
4190 PRINT "RUN A BEAM-COLUMN DESIGN (YES OR NO)"
4200 INPUT B5
4210 IF B5="NO" THEN 4190
4220 IF B5="NO" THEN 4190
4230 INPUT B5
4240 PRINT "AFF TRANSVERSE (LATERAL) LOADS ZERO (YES OR NO)"
4250 INPUT C5
4260 GOSUB 5000
4270 PRINT "TOP B"
4280 PRINT "CL-DIST. RETW. STRNGR'S"
4290 PRINT "1"
4300 PRINT "2"
4310 PRINT "3"
4320 PRINT "4"
4330 PRINT "5"
4340 PRINT "6"
4350 PRINT "7"
4360 PRINT "8"
4370 PRINT "9"
4380 PRINT "10"
4390 PRINT "11"
4400 PRINT "12"
4410 PRINT "13"
4420 PRINT "14"
4430 PRINT "15"
4440 PRINT "16"
4450 PRINT "17"
4460 PRINT "18"
4470 PRINT "19"
4480 PRINT "20"
4490 PRINT "21"
4500 PRINT "22"
4510 PRINT "23"
4520 PRINT "24"
4530 PRINT "25"
4540 PRINT "26"
4550 PRINT "27"
4560 PRINT "28"
4570 PRINT "29"
4580 PRINT "30"
4590 PRINT "31"
4600 PRINT "32"
4610 PRINT "33"
4620 PRINT "34"
4630 PRINT "35"
4640 PRINT "36"
4650 PRINT "37"
4660 PRINT "38"
4670 PRINT "39"
4680 PRINT "40"
4690 PRINT "41"
4700 PRINT "42"
4710 PRINT "43"
4720 PRINT "44"
4730 PRINT "45"
4740 PRINT "46"
4750 PRINT "47"
4760 PRINT "48"
4770 PRINT "49"
4780 PRINT "50"
4790 PRINT "51"
4800 PRINT "52"
4810 PRINT "53"
4820 PRINT "54"
4830 PRINT "55"
4840 PRINT "56"
4850 PRINT "57"
4860 PRINT "58"
4870 PRINT "59"
4880 PRINT "60"
4890 PRINT "61"
4900 PRINT "62"
4910 PRINT "63"
4920 PRINT "64"
4930 PRINT "65"
4940 PRINT "66"
4950 PRINT "67"
4960 PRINT "68"
4970 PRINT "69"
4980 PRINT "70"
4990 PRINT "71"
5000 PRINT "72"
5010 PRINT "73"
5020 PRINT "74"
5030 PRINT "75"
5040 PRINT "76"
5050 PRINT "77"
5060 PRINT "78"
5070 PRINT "79"
5080 PRINT "80"
5090 PRINT "81"
5100 PRINT "82"
5110 PRINT "83"
5120 PRINT "84"
5130 PRINT "85"
5140 PRINT "86"
5150 PRINT "87"
5160 PRINT "88"
5170 PRINT "89"
5180 PRINT "90"
5190 PRINT "91"
5200 PRINT "92"
5210 PRINT "93"
5220 PRINT "94"
5230 PRINT "95"
5240 PRINT "96"
5250 PRINT "97"
5260 PRINT "98"
5270 PRINT "99"
5280 PRINT "100"
5290 PRINT "101"
5300 PRINT "102"
5310 PRINT "103"
5320 PRINT "104"
5330 PRINT "105"
5340 PRINT "106"
5350 PRINT "107"
5360 PRINT "108"
5370 PRINT "109"
5380 PRINT "110"
5390 PRINT "111"
5400 PRINT "112"
5410 PRINT "113"
5420 PRINT "114"
5430 PRINT "115"
5440 PRINT "116"
5450 PRINT "117"
5460 PRINT "118"
5470 PRINT "119"
5480 PRINT "120"
5490 PRINT "121"
5500 PRINT "122"
5510 PRINT "123"
5520 PRINT "124"
5530 PRINT "125"
5540 PRINT "126"
5550 PRINT "127"
5560 PRINT "128"
5570 PRINT "129"
5580 PRINT "130"
5590 PRINT "131"
5600 PRINT "132"
5610 PRINT "133"
5620 PRINT "134"
5630 PRINT "135"
5640 PRINT "136"
5650 PRINT "137"
5660 PRINT "138"
5670 PRINT "139"
5680 PRINT "140"
5690 PRINT "141"
5700 PRINT "142"
5710 PRINT "143"
5720 PRINT "144"
5730 PRINT "145"
5740 PRINT "146"
5750 PRINT "147"
5760 PRINT "148"
5770 PRINT "149"
5780 PRINT "150"
5790 PRINT "151"
5800 PRINT "152"
5810 PRINT "153"
5820 PRINT "154"
5830 PRINT "155"
5840 PRINT "156"
5850 PRINT "157"
5860 PRINT "158"
5870 PRINT "159"
5880 PRINT "160"
5890 PRINT "161"
5900 PRINT "162"
5910 PRINT "163"
5920 PRINT "164"
5930 PRINT "165"
5940 PRINT "166"
5950 PRINT "167"
5960 PRINT "168"
5970 PRINT "169"
5980 PRINT "170"
5990 PRINT "171"
6000 PRINT "172"
6010 PRINT "173"
6020 PRINT "174"
6030 PRINT "175"
6040 PRINT "176"
6050 PRINT "177"
6060 PRINT "178"
6070 PRINT "179"
6080 PRINT "180"
6090 PRINT "181"
6100 PRINT "182"
6110 PRINT "183"
6120 PRINT "184"
6130 PRINT "185"
6140 PRINT "186"
6150 PRINT "187"
6160 PRINT "188"
6170 PRINT "189"
6180 PRINT "190"
6190 PRINT "191"
6200 PRINT "192"
6210 PRINT "193"
6220 PRINT "194"
6230 PRINT "195"
6240 PRINT "196"
6250 PRINT "197"
6260 PRINT "198"
6270 PRINT "199"
6280 PRINT "200"
6290 PRINT "201"
6300 PRINT "202"
6310 PRINT "203"
6320 PRINT "204"
6330 PRINT "205"
6340 PRINT "206"
6350 PRINT "207"
6360 PRINT "208"
6370 PRINT "209"
6380 PRINT "210"
6390 PRINT "211"
6400 PRINT "212"
6410 PRINT "213"
6420 PRINT "214"
6430 PRINT "215"
6440 PRINT "216"
6450 PRINT "217"
6460 PRINT "218"
6470 PRINT "219"
6480 PRINT "220"
6490 PRINT "221"
6500 PRINT "222"
6510 PRINT "223"
6520 PRINT "224"
6530 PRINT "225"
6540 PRINT "226"
6550 PRINT "227"
6560 PRINT "228"
6570 PRINT "229"
6580 PRINT "230"
6590 PRINT "231"
6600 PRINT "232"
6610 PRINT "233"
6620 PRINT "234"
6630 PRINT "235"
6640 PRINT "236"
6650 PRINT "237"
6660 PRINT "238"
6670 PRINT "239"
6680 PRINT "240"
6690 PRINT "241"
6700 PRINT "242"
6710 PRINT "243"
6720 PRINT "244"
6730 PRINT "245"
6740 PRINT "246"
6750 PRINT "247"
6760 PRINT "248"
6770 PRINT "249"
6780 PRINT "250"
6790 PRINT "251"
6800 PRINT "252"
6810 PRINT "253"
6820 PRINT "254"
6830 PRINT "255"
6840 PRINT "256"
6850 PRINT "257"
6860 PRINT "258"
6870 PRINT "259"
6880 PRINT "260"
6890 PRINT "261"
6900 PRINT "262"
6910 PRINT "263"
6920 PRINT "264"
6930 PRINT "265"
6940 PRINT "266"
6950 PRINT "267"
6960 PRINT "268"
6970 PRINT "269"
6980 PRINT "270"
6990 PRINT "271"
7000 PRINT "272"
7010 PRINT "273"
7020 PRINT "274"
7030 PRINT "275"
7040 PRINT "276"
7050 PRINT "277"
7060 PRINT "278"
7070 PRINT "279"
7080 PRINT "280"
7090 PRINT "281"
7100 PRINT "282"
7110 PRINT "283"
7120 PRINT "284"
7130 PRINT "285"
7140 PRINT "286"
7150 PRINT "287"
7160 PRINT "288"
7170 PRINT "289"
7180 PRINT "290"
7190 PRINT "291"
7200 PRINT "292"
7210 PRINT "293"
7220 PRINT "294"
7230 PRINT "295"
7240 PRINT "296"
7250 PRINT "297"
7260 PRINT "298"
7270 PRINT "299"
7280 PRINT "300"
7290 PRINT "301"
7300 PRINT "302"
7310 PRINT "303"
7320 PRINT "304"
7330 PRINT "305"
7340 PRINT "306"
7350 PRINT "307"
7360 PRINT "308"
7370 PRINT "309"
7380 PRINT "310"
7390 PRINT "311"
7400 PRINT "312"
7410 PRINT "313"
7420 PRINT "314"
7430 PRINT "315"
7440 PRINT "316"
7450 PRINT "317"
7460 PRINT "318"
7470 PRINT "319"
7480 PRINT "320"
7490 PRINT "321"
7500 PRINT "322"
7510 PRINT "323"
7520 PRINT "324"
7530 PRINT "325"
7540 PRINT "326"
7550 PRINT "327"
7560 PRINT "328"
7570 PRINT "329"
7580 PRINT "330"
7590 PRINT "331"
7600 PRINT "332"
7610 PRINT "333"
7620 PRINT "334"
7630 PRINT "335"
7640 PRINT "336"
7650 PRINT "337"
7660 PRINT "338"
7670 PRINT "339"
7680 PRINT "340"
7690 PRINT "341"
7700 PRINT "342"
7710 PRINT "343"
7720 PRINT "344"
7730 PRINT "345"
7740 PRINT "346"
7750 PRINT "347"
7760 PRINT "348"
7770 PRINT "349"
7780 PRINT "350"
7790 PRINT "351"
7800 PRINT "352"
7810 PRINT "353"
7820 PRINT "354"
7830 PRINT "355"
7840 PRINT "356"
7850 PRINT "357"
7860 PRINT "358"
7870 PRINT "359"
7880 PRINT "360"
7890 PRINT "361"
7900 PRINT "362"
7910 PRINT "363"
7920 PRINT "364"
7930 PRINT "365"
7940 PRINT "366"
7950 PRINT "367"
7960 PRINT "368"
7970 PRINT "369"
7980 PRINT "370"
7990 PRINT "371"
8000 PRINT "372"
8010 PRINT "373"
8020 PRINT "374"
8030 PRINT "375"
8040 PRINT "376"
8050 PRINT "377"
8060 PRINT "378"
8070 PRINT "379"
8080 PRINT "380"
8090 PRINT "381"
8100 PRINT "382"
8110 PRINT "383"
8120 PRINT "384"
8130 PRINT "385"
8140 PRINT "386"
8150 PRINT "387"
8160 PRINT "388"
8170 PRINT "389"
8180 PRINT "390"
8190 PRINT "391"
8200 PRINT "392"
8210 PRINT "393"
8220 PRINT "394"
8230 PRINT "395"
8240 PRINT "396"
8250 PRINT "397"
8260 PRINT "398"
8270 PRINT "399"
8280 PRINT "400"
8290 PRINT "401"
8300 PRINT "402"
8310 PRINT "403"
8320 PRINT "404"
8330 PRINT "405"
8340 PRINT "406"
8350 PRINT "407"
8360 PRINT "408"
8370 PRINT "409"
8380 PRINT "410"
8390 PRINT "411"
8400 PRINT "412"
8410 PRINT "413"
8420 PRINT "414"
8430 PRINT "415"
8440 PRINT "416"
8450 PRINT "417"
8460 PRINT "418"
8470 PRINT "419"
8480 PRINT "420"
8490 PRINT "421"
8500 PRINT "422"
8510 PRINT "423"
8520 PRINT "424"
8530 PRINT "425"
8540 PRINT "426"
8550 PRINT "427"
8560 PRINT "428"
8570 PRINT "429"
8580 PRINT "430"
8590 PRINT "431"
8600 PRINT "432"
8610 PRINT "433"
8620 PRINT "434"
8630 PRINT "435"
8640 PRINT "436"
8650 PRINT "437"
8660 PRINT "438"
8670 PRINT "439"
8680 PRINT "440"
8690 PRINT "441"
8700 PRINT "442"
8710 PRINT "443"
8720 PRINT "444"
8730 PRINT "445"
8740 PRINT "446"
8750 PRINT "447"
8760 PRINT "448"
8770 PRINT "449"
8780 PRINT "450"
8790 PRINT "451"
8800 PRINT "452"
8810 PRINT "453"
8820 PRINT "454"
8830 PRINT "455"
8840 PRINT "456"
8850 PRINT "457"
8860 PRINT "458"
8870 PRINT "459"
8880 PRINT "460"
8890 PRINT "461"
8900 PRINT "462"
8910 PRINT "463"
8920 PRINT "464"
8930 PRINT "465"
8940 PRINT "466"
8950 PRINT "467"
8960 PRINT "468"
8970 PRINT "469"
8980 PRINT "470"
8990 PRINT "471"
9000 PRINT "472"
9010 PRINT "473"
9020 PRINT "474"
9030 PRINT "475"
9040 PRINT "476"
9050 PRINT "477"
9060 PRINT "478"
9070 PRINT "479"
9080 PRINT "480"
9090 PRINT "481"
9100 PRINT "482"
9110 PRINT "483"
9120 PRINT "484"
9130 PRINT "485"
9140 PRINT "486"
9150 PRINT "487"
9160 PRINT "488"
9170 PRINT "489"
9180 PRINT "490"
9190 PRINT "491"
9200 PRINT "492"
9210 PRINT "493"
9220 PRINT "494"
9230 PRINT "495"
9240 PRINT "496"
9250 PRINT "497"
9260 PRINT "498"
9270 PRINT "499"
9280 PRINT "500"
9290 PRINT "501"
9300 PRINT "502"
9310 PRINT "503"
9320 PRINT "504"
9330 PRINT "505"
9340 PRINT "506"
9350 PRINT "507"
9360 PRINT "508"
9370 PRINT "509"
9380 PRINT "510"
9390 PRINT "511"
9400 PRINT "512"
9410 PRINT "513"
9420 PRINT "514"
9430 PRINT "515"
9440 PRINT "516"
9450 PRINT "517"
9460 PRINT "518"
9470 PRINT "519"
9480 PRINT "520"
9490 PRINT "521"
9500 PRINT "522"
9510 PRINT "523"
9520 PRINT "524"
9530 PRINT "525"
9540 PRINT "526"
9550 PRINT "527"
9560 PRINT "528"
9570 PRINT "529"
9580 PRINT "530"
9590 PRINT "531"
9600 PRINT "532"
9610 PRINT "533"
9620 PRINT "534"
9630 PRINT "535"
9640 PRINT "536"
9650 PRINT "537"
9660 PRINT "538"
9670 PRINT "539"
9680 PRINT "540"
9690 PRINT "541"
9700 PRINT "542"
9710 PRINT "543"
9720 PRINT "544"
9730 PRINT "545"
9740 PRINT "546"
9750 PRINT "547"
9760 PRINT "548"
9770 PRINT "549"
9780 PRINT "550"
9790 PRINT "551"
9800 PRINT "552"
9810 PRINT "553"
9820 PRINT "554"
9830 PRINT "555"
9840 PRINT "556"
9850 PRINT "557"
9860 PRINT "558"
9870 PRINT "559"
9880 PRINT "560"
9890 PRINT "561"
9900 PRINT "562"
9910 PRINT "563"
9920 PRINT "564"
9930 PRINT "565"
9940 PRINT "566"
9950 PRINT "567"
9960 PRINT "568"
9970 PRINT "569"
9980 PRINT "570"
9990 PRINT "571"

```

PRINT "STRAP WIDTHS"
 PRINT "1" "2" "3" "4"
 PRINT "5" "6" "7" "8" "9" "10" "11" "12" "13" "14" "15" "16" "17" "18" "19" "20" "21" "22" "23" "24" "25" "26" "27" "28" "29" "30" "31" "32" "33" "34" "35" "36" "37" "38" "39" "40" "41" "42" "43" "44" "45" "46" "47" "48" "49" "50" "51" "52" "53" "54" "55" "56" "57" "58" "59" "60" "61" "62" "63" "64" "65" "66" "67" "68" "69" "70" "71" "72" "73" "74" "75" "76" "77" "78" "79" "80" "81" "82" "83" "84" "85" "86" "87" "88" "89" "90" "91" "92" "93" "94" "95" "96" "97" "98" "99" "100" "101" "102" "103" "104" "105" "106" "107" "108" "109" "110" "111" "112" "113" "114" "115" "116" "117" "118" "119" "120" "121" "122" "123" "124" "125" "126" "127" "128" "129" "130" "131" "132" "133" "134" "135" "136" "137" "138" "139" "140" "141" "142" "143" "144" "145" "146" "147" "148" "149" "150" "151" "152" "153" "154" "155" "156" "157" "158" "159" "160" "161" "162" "163" "164" "165" "166" "167" "168" "169" "170" "171" "172" "173" "174" "175" "176" "177" "178" "179" "180" "181" "182" "183" "184" "185" "186" "187" "188" "189" "190" "191" "192" "193" "194" "195" "196" "197" "198" "199" "200" "201" "202" "203" "204" "205" "206" "207" "208" "209" "210" "211" "212" "213" "214" "215" "216" "217" "218" "219" "220" "221" "222" "223" "224" "225" "226" "227" "228" "229" "230" "231" "232" "233" "234" "235" "236" "237" "238" "239" "240" "241" "242" "243" "244" "245" "246" "247" "248" "249" "250" "251" "252" "253" "254" "255" "256" "257" "258" "259" "260" "261" "262" "263" "264" "265" "266" "267" "268" "269" "270" "271" "272" "273" "274" "275" "276" "277" "278" "279" "280" "281" "282" "283" "284" "285" "286" "287" "288" "289" "290" "291" "292" "293" "294" "295" "296" "297" "298" "299" "300" "301" "302" "303" "304" "305" "306" "307" "308" "309" "310" "311" "312" "313" "314" "315" "316" "317" "318" "319" "320" "321" "322" "323" "324" "325" "326" "327" "328" "329" "330" "331" "332" "333" "334" "335" "336" "337" "338" "339" "340" "341" "342" "343" "344" "345" "346" "347" "348" "349" "350" "351" "352" "353" "354" "355" "356" "357" "358" "359" "360" "361" "362" "363" "364" "365" "366" "367" "368" "369" "370" "371" "372" "373" "374" "375" "376" "377" "378" "379" "380" "381" "382" "383" "384" "385" "386" "387" "388" "389" "390" "391" "392" "393" "394" "395" "396" "397" "398" "399" "400" "401" "402" "403" "404" "405" "406" "407" "408" "409" "410" "411" "412" "413" "414" "415" "416" "417" "418" "419" "420" "421" "422" "423" "424" "425" "426" "427" "428" "429" "430" "431" "432" "433" "434" "435" "436" "437" "438" "439" "440" "441" "442" "443" "444" "445" "446" "447" "448" "449" "450" "451" "452" "453" "454" "455" "456" "457" "458" "459" "460" "461" "462" "463" "464" "465" "466" "467" "468" "469" "470" "471" "472" "473" "474" "475" "476" "477" "478" "479" "480" "481" "482" "483" "484" "485" "486" "487" "488" "489" "490" "491" "492" "493" "494" "495" "496" "497" "498" "499" "500" "501" "502" "503" "504" "505" "506" "507" "508" "509" "510" "511" "512" "513" "514" "515" "516" "517" "518" "519" "520" "521" "522" "523" "524" "525" "526" "527" "528" "529" "530" "531" "532" "533" "534" "535" "536" "537" "538" "539" "540" "541" "542" "543" "544" "545" "546" "547" "548" "549" "550" "551" "552" "553" "554" "555" "556" "557" "558" "559" "560" "561" "562" "563" "564" "565" "566" "567" "568" "569" "570" "571" "572" "573" "574" "575" "576" "577" "578" "579" "580" "581" "582" "583" "584" "585" "586" "587" "588" "589" "590" "591" "592" "593" "594" "595" "596" "597" "598" "599" "600" "601" "602" "603" "604" "605" "606" "607" "608" "609" "610" "611" "612" "613" "614" "615" "616" "617" "618" "619" "620" "621" "622" "623" "624" "625" "626" "627" "628" "629" "630" "631" "632" "633" "634" "635" "636" "637" "638" "639" "640" "641" "642" "643" "644" "645" "646" "647" "648" "649" "650" "651" "652" "653" "654" "655" "656" "657" "658" "659" "660" "661" "662" "663" "664" "665" "666" "667" "668" "669" "670" "671" "672" "673" "674" "675" "676" "677" "678" "679" "680" "681" "682" "683" "684" "685" "686" "687" "688" "689" "690" "691" "692" "693" "694" "695" "696" "697" "698" "699" "700" "701" "702" "703" "704" "705" "706" "707" "708" "709" "710" "711" "712" "713" "714" "715" "716" "717" "718" "719" "720" "721" "722" "723" "724" "725" "726" "727" "728" "729" "730" "731" "732" "733" "734" "735" "736" "737" "738" "739" "740" "741" "742" "743" "744" "745" "746" "747" "748" "749" "750" "751" "752" "753" "754" "755" "756" "757" "758" "759" "760" "761" "762" "763" "764" "765" "766" "767" "768" "769" "770" "771" "772" "773" "774" "775" "776" "777" "778" "779" "780" "781" "782" "783" "784" "785" "786" "787" "788" "789" "790" "791" "792" "793" "794" "795" "796" "797" "798" "799" "800" "801" "802" "803" "804" "805" "806" "807" "808" "809" "810" "811" "812" "813" "814" "815" "816" "817" "818" "819" "820" "821" "822" "823" "824" "825" "826" "827" "828" "829" "830" "831" "832" "833" "834" "835" "836" "837" "838" "839" "840" "841" "842" "843" "844" "845" "846" "847" "848" "849" "850" "851" "852" "853" "854" "855" "856" "857" "858" "859" "860" "861" "862" "863" "864" "865" "866" "867" "868" "869" "870" "871" "872" "873" "874" "875" "876" "877" "878" "879" "880" "881" "882" "883" "884" "885" "886" "887" "888" "889" "890" "891" "892" "893" "894" "895" "896" "897" "898" "899" "900" "901" "902" "903" "904" "905" "906" "907" "908" "909" "910" "911" "912" "913" "914" "915" "916" "917" "918" "919" "920" "921" "922" "923" "924" "925" "926" "927" "928" "929" "930" "931" "932" "933" "934" "935" "936" "937" "938" "939" "940" "941" "942" "943" "944" "945" "946" "947" "948" "949" "950" "951" "952" "953" "954" "955" "956" "957" "958" "959" "960" "961" "962" "963" "964" "965" "966" "967" "968" "969" "970" "971" "972" "973" "974" "975" "976" "977" "978" "979" "980" "981" "982" "983" "984" "985" "986" "987" "988" "989" "990" "991" "992" "993" "994" "995" "996" "997" "998" "999" "1000"

SUBROUTINE TO ADD BEAM-COLUMN (BC) DESIGN CAPABILITY
 SEE HLMSP1 REPORT OF 10/77 PP. A2-4 TO -6 FOR BC DESIGN STEPS.
 BC DESIGN STEPS 1-6 ARE COVERED BY HLMSP DESIGN STEPS 1-9.
 BC STEP 6 CLOSED, REQUIRING VALUES FOR 7 VARIABLES FIRST 2
 ARE PROVIDED BY STATEMENTS FOLLOWING THESE REM'S, AND OTHER 5
 ARE L2 (L-PRIME), ALL FROM PRECEDING HLMSP STEPS.
 L2 (L-PRIME), ALL FROM PRECEDING HLMSP STEPS.
 PANEL DEFLECTION AND DEFLECTION BETWEEN STRINGERS HAVE BEEN
 EXCLUDED AS TRANSVERSE LOAD CAPACITY CRITERIA, BY LINE 3640-3720
 OF THIS MODIFICATION! DELETE THEM IF SUCH CRITERIA EXCLUSION IS
 UNDESIRABLE.

WHERE P-SUB DM = P-SUB M * (1 - 1/(2*U2))
 BUT, DEPENDING ON INTERIOR RISE-TIME, PERHAPS REDUCED PEARL BLAST
 PRESSURE ETC. U2 = 1.1000 AS SUCH THINGS REDUCE THE BLAST
 LOADING TOWARDS A STATIC LOAD, I.E., WITH UNITY DYNAMIC
 MAGNIFICATION FACTOR.
 SEE REPORT TEXT (REVISED APP. A2 IN NEW REPORT).
 REM * STEP 10 BC (HLMSP1) *

Table A2-1 (continued)

```

4460 REM *****
4480 LET M(9)=P54.2*1.2/8
4490 LET Y(9)=5*P54.2*1.4/384/E5
4500 LET Q(9)=P5
4510 LET M(11)=Q(11)*P(9)=0
4520 REM *****
4530 REM * STEPS 11-15 BC (HMSRI) *
4540 REM *****
4550 FOR I=8 TO 2 STEP -1
4560 LET P(11)=P(11)*(9-I)/8
4570 LET M(11)=Y(9)*(9-I)/8
4580 FOR J=1 TO 50
4590 LET M(11)=9/2*(F1-P(11)/M)-P(11)*M(11)
4600 IF M(11) < M(9)-P(11)*M(11) THEN 6620
4610 LET M(11)=M(9)-P(11)*M(11)
4620 LET M(11)=54.1/2*(M(11)+P(11)*M(11))/48/E5
4630 IF ABS(M(11)-M(11)) < .01 THEN 6680
4640 LET M(11)=M(11)
4650 IF J=50 THEN 6670
4660 PRINT "J=50 IN STEP 13 THIS TRIAL/ERROR SOLUTION EQ. A2-7 UNSATISFACTORY"
4670 NEXT J
4680 LET Y(11)=M(11)
4690 LET Q(11)=M(11)/M(9)+Q(9)
4700 NEXT I
4710 REM *****
4720 REM * OUTPUT PORTION *
4730 PRINT "STEPS 7-8 BC:"
4740 PRINT "MAX. AXIAL LOAD (W/ ZERO LATERAL LOAD), P-SUB A= "
4750 IF CS="YES" THEN 4189
4760 PRINT "RELATED MID-LENGTH DEF., Y="1/INT(Y(11)*10000*1/2)/10000" IN."
4770 PRINT
4780 PRINT "STEPS 9-10 BC:"
4790 PRINT "MAX. MID-LENGTH MOMENT FROM LATERAL LOADS (WITH ZERO AXIAL LOAD)"
4800 PRINT "1/INT(M(9)/100*1/2)/101
4810 PRINT "IN-KIPS (KIP-KILO-POUND=1,000 LBS)"
4820 PRINT "RELATED DEFLECTION,"1/INT(Y(9)*100*1/2)/1001" IN., MID-LENGTH"
4830 PRINT "RELATED LATERAL LOADING, P-SUB A= "1/INT(Q(9)*1000*1/2)/1000
4840 PRINT "PSI"
4850 PRINT "STEPS 11-15 BC:"
4860 PRINT "AXIAL LOAD LATERAL LOAD/MOMENT P-DELTA MOM. DEFLECTION"
4870 PRINT " (LBS.) (PSI) (IN.-KIPS) (IN.-KIPS) (IN.)"
4880 PRINT
4890 FOR I=1 TO 9
4900 PRINT USING "8.7D"1/INT(P(11)+1/2)
4910 PRINT USING "8.2X7D.D"1/INT(Q(11)*10*1/2)/10
4920 PRINT USING "8.2X7D.D"1/INT(M(11)/100*1/2)/10
4930 PRINT USING "8.2X9D.D"1/INT(P(11)*Y(11)/100*1/2)/10
4940 PRINT USING "2X7D.DD"1/INT(Y(11)*100*1/2)/100
4950 NEXT I
4960 GOSUB 5000
4970 LET T=.0027*1.2*(144*P9*2/E5)^.5
4980 PRINT "SIMPLY SUPPORTED, EFFECTIVE NATURAL PERIOD OF (LATERAL) "
4990 PRINT "VIBRATION."
7000 PRINT "T="1/INT(T*1000000.*1/2)/100000.1" SEC."
7010 PRINT
7020 RETURN
9999 END

```

A2-13

SAMPLE PROBLEM (as used in Ref. 1)

STEP 21
ENTER 'B' DISTANCES FOR TOP & BOT. SKINS, RESP Y (IN.)
(HMSRI, F16.1B1 ALSO PDS3, P.5 (TABLE))
?38.12

ENTER CLEAR DISTANCE BETWEEN STRINGERS (F16.1B, HMSRI) (IN.)
(SHOULD BE UNIFORM IF NOT, USE LARGEST VALUE)
?13.9

STEP 31
ENTER E VALUES (PSI) FOR TOP, BOT. SKINS & STRINGERS, RESP Y
(PDS, P.17 & NDS)
?1800000, 1800000, 1800000

ENTER A// VALUES FOR TOP, BOT. SKINS (SQ IN/FT WIDTH)
(PDS, P.16, COL. 4)
?2.728, 1.914

ENTER TOTAL X-SECT. AREA OF ALL STRINGERS (SQ IN)
?32.2

ENTER MOMENT ARMS FOR TOP, BOT. SKINS & STRINGERS, RESP Y (IN.)
(FROM BOTTOM SURFACE OF PANEL)
?6.156, 3

ENTER WIDTH (PLYWOOD) OF PANEL (IN.) ?48

STEP 41
ENTER I OF TOP, BOT. SKINS ABOUT OWN AXES (IN. 4/FT WIDTH)
(PDS, P.16, COL. 5)
?141.025

ENTER TOTAL WIDTH OF STRINGERS (IN.) ?6

STEP 51
ENTER CLEAR SPAN L OF PANEL (IN.) ?168

ENTER C FACTOR, IN MAX. ALLOWABLE DEF., L/C
(HMSRI, STEP 61 PDS3, P.9)
?360

IS C FACTOR IN TERMS OF LL OR TL ?LL

ENTER DESIGN DL (PSI) ?0.694444

STEP 61
ENTER I FOR TOP SKIN (STRESS PERPENDICULAR TO STRINGERS)
(PDS, P.16, COL. 9) (IN. 4/FT)
?0.23

STEP 71
ENTER EFFECTIVE WIDTHS (AS FLANGES) OF TOP, BOT. SKINS
(HMSRI, F16.3B1 PDS3, P.10, RT. F16.)
?48.42, 3

STEPS 9 & 101
ENTER TOP SKIN F-SUB C & BOT. SKIN F-SUB T (PSI)
(PDS, P.17)
?1540, 1650

STEP 111
ENTER OVERALL PANEL THICKNESS (IN.) ?6.312

Table A2-1 (continued)

```

STEP 121
ENTER AREA // PLIES OUTSIDE CRITICAL PLACES, TOP & BOT.
SKINS, RESP'Y (IN, 2 / 48 IN.)
(ENH 6.7TH COLS. MLMSPI FIG. 4 AND PDS3 TABLE P. 14)
26.06/3.83

ENTER Y-Axis RELATED VALUES (SAME SOURCE, 3RD & 7TH COLS. IN.)
2.148., 0475

ENTER 3 STRINGER WIDTH TOTALS (IN.) IN FOLLOWING ORDER:
UNGLUED (PHOTODUROS) STRINGER(S) WIDTH (TOTAL IN.)
GLUELINE (TOTAL IN.) WIDTH OF EXTERIOR STRINGERS
WHOSE CLEAR DIST. TO PANEL EDGE IS LESS THAN HALF
CLEAR DIST. BETW. STRINGERS.
GLUELINE (TOTAL IN.) WIDTH OF ALL OTHER STRINGERS.
2.75, 2.25/3

ENTER F-SUB S FOR TOP & BOT. SKINS, RESP'Y (PSI)
248.48

STEP 131
ENTER ALLOWABLE HORIZ. SHEAR STRESS IN STRINGERS (PSI)
795

STEP 141
ENTER ALLOWABLE STRESS IN BEARINGS ON PLYWOOD BOT. FACE (PSI)
2340

STEP 151
ENTER ALLOWABLE SPLICE-PLATE MAX. STRESS (PSI)
21200

ENTER TOTAL LENGTH OF SPLICE-PLATE ACROSS PANEL (IN.)
240.2

ANY CHANGES DESIRED (YES OR NO)
NO

WANT TABULATION OF INPUT VALUES (YES OR NO)
YES

```

| STEP | TOP B | CL. DIST. BETW. STRINGERS | CL. DIST. BETW. STRINGERS |
|------|---|---|---|
| 2 | 32 | 12 | 13.9 |
| 3 | E TOP SKIN 1.80000E+06 A// BOT. SKIN 1.80000E+06 1.914 MON. ARM STR'S 3 | E BOT. SKIN 1.80000E+06 AREA STRANGERS 32.2 PANEL WIDTH (PLYWOOD) 48 | E STRANGERS 1.80000E+06 TP. SK. MON. ARM 6 BOT. DITTO .156 |
| 4 | I TOP SK. .141 | I BOT. SK. .025 | TOTAL WIDTH STRINGERS 6 |
| 5 | PANEL CL. SP. 168 | C FACTOR 360 | C IN LL OR TL? LL |
| 6 | DESIGN DL 6.94444E-02 | I TOP SK. (STRESS PERPEND. TO STR'S) .023 | |
| 7 | TOP SKIN 48 | E BOT. SKIN 42.3 | EFFECTIVE WIDTHS |
| 9.10 | TOP SK. F-SUB C BOT. SK. F-SUB Y 1540 | | |
| 11 | OVERALL PANEL THICKNESS 6.312 | | |
| 12 | TOP SK. A// 6.06 RELATED Y-PRIME VALUES .148 UNGLUED .75 TOP SK. F-SUB S BOT. SK. F-SUB S 48 | E BOT. SK. A// 3.82 RELATED Y-PRIME VALUES .0479 E EXT. GLUED 2.63 BOT. SK. F-SUB S 48 | BOTH OUTSIDE CRITICAL PL. B INT. GLUED 3 STRING WIDTHS |
| 13 | ALLOW. HORIZ. SHEAR STRESS, STRINGERS 95 | | |
| 14 | PLYM. BOT. FACE ALLOW. BEAR. STRESS 340 | | |
| 15 | ALLOW. SPL-PL. MAX. STRESS 1200 | TOTAL X-PANEL SPL-PL. LENGTH 40.2 | |

ANY CHANGES DESIRED (YES OR NO)

WANT TABULATION OF INPUT VALUES (YES OR NO)?

Table A2-1 (concluded)

| | | | |
|---|--------------------------|-------------|---|
| STEP 31 Y-BAR DEFLECTION (N.A.) = 3.22501 WLMSP1 FIG. 2A TOTALS: 50.768 IN. | 9.64634E+07 | 3.11096E+08 | STEPS 7-8 BC1 MAX. AXIAL LOAD (W/ ZERO LATERAL LOAD), P-SUB A= 49172. LBS. RELATED MID-LENGTH DEFL. Y= .313 IN. |
| STEP 41 (E1-SUB 6) = 4.56779E+08 WLMSP1 FIG. 2B TOTALS: 235.716 LB-IN.2 | 4.56779E+08 | | STEPS 9-10 BC1 MAX. MID-LENGTH MOMENT FROM LATERAL LOADS (WITH ZERO AXIAL LOAD) RELATED DEFLECTION= .5 IN. MID-LENGTH RELATED LATERAL LOADING, P-SUB M= .439 PSI |
| STEP 51 P-SUB D = .476408 PSI MADE UP OF LL = .406964 PANEL DEFL. (MID-SPAN, SS) = .466667 IN. | AND DL = 6.94444E-02 PSI | | STEPS 11-15 BC1 AXIAL LOAD LATERAL LOAD/MOMENT P-DEL (A NOM. DEFLECTION (LBS.) (IN.-KIPS) (IN.-KIPS) (IN.) |
| STEP 61 P-SUB T = 1.43971 PSI TOP-SKIN DEFL. BETW. STRINGERS = 3.86111E-02 IN. | | | 49172 0.0 0.0 15.4 0.31 43025 0.1 19.9 8.0 0.19 36879 0.2 30.4 10.0 0.27 30732 0.2 42.0 10.9 0.35 24586 0.3 54.7 10.8 0.44 19439 0.4 65.2 9.2 0.50 12293 0.4 68.3 6.1 0.50 6146 0.4 71.3 3.1 0.50 0 0.4 74.4 0.0 0.50 |
| STEP 71 Y-BAR (BENDING N.A.) = 3.28337 IN. WLMSP1 FIG. 3A TOTALS: (PLUS TOTAL OF AREAS) 49.8588 9.46633E+07 3.10819E+08 | | | |
| STEP 81 (E1-SUB M) = 4.39474E+08 WLMSP1 FIG. 3B TOTALS: 227.039 LB-IN.2 | 4.39474E+08 | | |
| STEPS 9 & 101 P-SUB C AND T, RESP. Y = 1540 AND 1100.55 PSI | | | |
| STEP 111 P-SUB B = .439327 PSI TOP-SKIN = .666459 & BOT. SKIN = .439327 PSI | | | |
| STEP 121 TOP SKIN CONTROL: P-SUB S = .63600 PSI (BOT. SKIN P-SUB S = .931003 PSI) | | | |
| STEP 131 P-SUB V = .678801 PSI Q-SUB V = 51.3103 IN.3 | | | |
| STEP 141 P-SUB M = .439327 PSI I-SUB E = 1.5 IN. | | | |
| STEP 151 RESERVE PRESCRIBED MIN. LENGTHS FOR TENSION SPLICE- PLATES (PDS) P. 26 TABLE & OTHER LIMITATIONS (WLMSP1) P-SUB P = .424524 PSI IF P-SUB P < P-SUB M (.439327) OR DESIGN TL, WHICHEVER CRITERION IS USED, SPLICE-PLATE SHOULD BE REDESIGNED OR RELOCATED (P-SUB P CALC'D ON MID-SPAN LOCATION) | | | |

A2-15

STAMP Y SUPPORTED, EFFECTIVE NATURAL PERIOD OF (LATERAL) VIBRATION:
T = .07964 SEC.

RUN ANOTHER PROBLEM (YES OR NO)

?NO

DONE

BYE

RUN A BEAM-COLUMN DESIGN (YES OR NO)

?YES

ARE TRANSVERSE (LATERAL) LOADS ZERO (YES OR NO)

?NO

The PSSP designs in Table A2-2* show the results of using the computer program (Table A2-1) for columns and beam-columns. These results include use of the recommended increases in normal-use design stresses⁸ and use of the recommended dynamic factors for blast loads (section B above, second paragraph).

An illustrative example is shown on the page following Table A2-2.

* Prepared by J. E. Beck of James E. Beck and Associates (subcontractor).

Table A2-2A PSSP DESIGNS FOR LOWER STRENGTH STRINGERS ($F_v = 280$ psi)
(Columns and Beam-Columns)

Panel Width: 48 in.

| Top & Bottom Skins | | Stringers | | Req'd* Bearing Length Ea. End | Panel Height = 7 ft | | | | Panel Height = 8 ft | | | | Panel Height = 9 ft | | | | | | |
|-----------------------|----|-----------|-----|--|---------------------------|--|-----|-----|---------------------------|--|-----|-----|---------------------------|--|-------|-----|-----|-----|-----|
| | | | | | P _{da} (kips) | P _{dm} (psi) for P _d /P _{da} = | | | P _{da} (kips) | P _{dm} (psi) for P _d /P _{da} = | | | P _{da} (kips) | P _{dm} (psi) for P _d /P _{da} = | | | | | |
| | | | | | | 0.8 | 0.6 | 0.4 | | 0.2 | 0.8 | 0.6 | | 0.4 | 0.2 | 0.8 | 0.6 | 0.4 | 0.2 |
| 1/2 | #1 | 4 | 2x4 | 4.5 | 130.7 | 0.6 | 0.9 | 1.0 | 1.2 | 128.5 | 0.4 | 0.7 | 0.9 | 1.0 | 126.5 | 0.2 | 0.5 | 0.7 | 0.8 |
| | | 5 | | 4.0 | 169.5 | 0.6 | 1.0 | 1.2 | 1.4 | 166.4 | 0.4 | 0.7 | 0.9 | 1.1 | 163.4 | 0.2 | 0.5 | 0.7 | 1.0 |
| | | 7 | | 3.5 | 219.5 | 0.6 | 1.1 | 1.4 | 1.7 | 214.8 | 0.3 | 0.7 | 1.1 | 1.4 | 191.1 | 0.2 | 0.5 | 0.9 | 1.2 |
| | | 9 | | 3.5 | 268.0 | 0.5 | 1.1 | 1.6 | 2.0 | 261.5 | 0.2 | 0.7 | 1.2 | 1.7 | 203.1 | 0.3 | 0.7 | 1.1 | 1.5 |
| 1/2 | #3 | 4 | 2x4 | 4.5 | 84.0 | 0.4 | 0.7 | 1.0 | 1.1 | 82.6 | 0.3 | 0.5 | 0.8 | 0.9 | 81.3 | 0.2 | 0.4 | 0.6 | 0.8 |
| | | 5 | | 4.0 | 109.0 | 0.4 | 0.8 | 1.1 | 1.3 | 107.0 | 0.3 | 0.5 | 0.9 | 1.1 | 105.0 | 0.1 | 0.3 | 0.6 | 0.9 |
| | | 7 | | 3.5 | 141.1 | 0.4 | 0.8 | 1.3 | 1.6 | 138.1 | 0.2 | 0.5 | 0.9 | 1.4 | 135.1 | 0.1 | 0.3 | 0.6 | 1.0 |
| | | 9 | | 3.0 | 172.3 | 0.4 | 0.8 | 1.3 | 1.9 | 168.1 | 0.2 | 0.5 | 0.9 | 1.5 | 148.5 | 0.1 | 0.4 | 0.7 | 1.2 |
| 3/4 | #1 | 4 | 2x4 | 5.0 | 152.3 | 0.6 | 1.1 | 1.2 | 1.3 | 150.0 | 0.5 | 0.9 | 1.0 | 1.1 | 147.9 | 0.4 | 0.7 | 0.8 | 1.0 |
| | | 5 | | 4.5 | 176.5 | 0.6 | 1.2 | 1.4 | 1.6 | 175.5 | 0.5 | 1.0 | 1.1 | 1.3 | 172.7 | 0.3 | 0.7 | 0.9 | 1.1 |
| | | 7 | | 4.0 | 229.3 | 0.8 | 1.5 | 1.7 | 2.0 | 224.8 | 0.5 | 1.0 | 1.4 | 1.7 | 220.5 | 0.3 | 0.6 | 1.1 | 1.4 |
| | | 9 | | 4.0 | 276.5 | 0.8 | 1.5 | 2.0 | 2.3 | 272.2 | 0.4 | 0.9 | 1.6 | 2.0 | 268.2 | 0.2 | 0.6 | 1.2 | 1.7 |
| 3/4 | #3 | 4 | 2x4 | 5.0 | 97.9 | 0.5 | 0.9 | 1.2 | 1.3 | 96.4 | 0.4 | 0.7 | 1.0 | 1.1 | 95.1 | 0.2 | 0.5 | 0.8 | 0.9 |
| | | 5 | | 4.5 | 114.7 | 0.5 | 1.0 | 1.3 | 1.5 | 112.9 | 0.4 | 0.7 | 1.1 | 1.3 | 111.0 | 0.2 | 0.5 | 0.8 | 1.1 |
| | | 7 | | 4.0 | 147.4 | 0.5 | 1.0 | 1.5 | 1.9 | 144.5 | 0.3 | 0.7 | 1.1 | 1.6 | 141.7 | 0.2 | 0.5 | 0.8 | 1.2 |
| | | 9 | | 3.5 | 179.0 | 0.5 | 1.0 | 1.6 | 2.2 | 175.0 | 0.3 | 0.7 | 1.1 | 1.7 | 171.2 | 0.2 | 0.4 | 0.8 | 1.3 |
| 1-1/8 | #1 | 4 | 2x4 | 5.5 | 170.1 | 1.2 | 1.4 | 1.5 | 1.6 | 168.0 | 0.8 | 1.1 | 1.2 | 1.4 | 166.0 | 0.6 | 0.9 | 1.1 | 1.2 |
| | | 5 | | 5.0 | 197.2 | 1.2 | 1.6 | 1.7 | 1.9 | 194.5 | 0.8 | 1.3 | 1.5 | 1.6 | 191.9 | 0.6 | 1.1 | 1.2 | 1.4 |
| | | 7 | | 5.0 | 249.8 | 1.2 | 2.0 | 2.2 | 2.4 | 245.7 | 0.8 | 1.5 | 1.8 | 2.1 | 241.8 | 0.6 | 1.1 | 1.5 | 1.8 |
| | | 9 | | 4.5 | 300.8 | 1.2 | 2.2 | 2.6 | 2.9 | 295.1 | 0.8 | 1.5 | 2.1 | 2.5 | 289.6 | 0.5 | 1.1 | 1.8 | 2.1 |

* For full lateral load and zero axial load; use 20% axial load (i.e., $P_d = 0.2P_{da}$). Reduce required bearing length (each end) with larger axial loads, varying in accordance with change in p_{dm} values; use minimum of 2 in. each end, however. For example, using data for 1/2 in. #3, 2x4s, 4-stringer, 7-ft long PSSP, and axial load = $0.6P_{da}$: required bearing length each end is $4.5(0.7/1.1) = 2.9$ in. each end. The bearing length values were obtained from Table A1-1A.

P_{da} is the maximum axial load, that is, when lateral load, $p_{dm} = 0$.

Table A2-2A (Concluded)

Panel Width: 48 in.

| Top & Bottom Skins | | | Stringers | Req'd* Bearing Length Ea. End | Panel Height = 7 ft | | | | Panel Height = 8 ft | | | | Panel Height = 9 ft | | | | | | |
|--------------------|-------------|--------------|-----------|--|-----------------------------|-----|--|-----|-----------------------------|-------|--|-----|-----------------------------|-----|--|-----|-----|-----|-----|
| | | | | | P _{da} # (kips) | | P _{dm} (psi) for P _d /P _{da} = | | P _{da} # (kips) | | P _{dm} (psi) for P _d /P _{da} = | | P _{da} # (kips) | | P _{dm} (psi) for P _d /P _{da} = | | | | |
| Nom. Thick. | Face Ply | Nom. Size | No. | | 0.8 | 0.6 | 0.4 | 0.2 | 0.8 | 0.6 | 0.4 | 0.2 | 0.8 | 0.6 | 0.4 | 0.2 | | | |
| 1/2 | #1 | 2x6 | 4 | 7.5 | 201.2 | 1.1 | 1.7 | 1.9 | 2.0 | 199.4 | 0.8 | 1.4 | 1.6 | 1.7 | 197.6 | 0.6 | 1.1 | 1.3 | 1.5 |
| | | | 5 | 6.5 | 266.7 | 1.2 | 2.0 | 2.2 | 2.4 | 264.0 | 0.8 | 1.6 | 1.8 | 2.0 | 261.3 | 0.6 | 1.2 | 1.5 | 1.8 |
| | | | 7 | 6.0 | 356.2 | 1.3 | 2.5 | 2.8 | 3.1 | 352.0 | 0.9 | 1.8 | 2.3 | 2.7 | 347.8 | 0.6 | 1.2 | 1.9 | 2.3 |
| | | | 9 | 5.5 | 444.6 | 1.4 | 2.8 | 3.4 | 3.8 | 438.7 | 0.9 | 1.9 | 2.8 | 3.2 | 433.0 | 0.6 | 1.3 | 2.3 | 2.8 |
| 1/2 | #3 | 2x6 | 4 | 7.0 | 129.4 | 0.7 | 1.3 | 1.8 | 1.9 | 128.2 | 0.5 | 1.0 | 1.5 | 1.7 | 127.0 | 0.4 | 0.7 | 1.2 | 1.4 |
| | | | 5 | 6.5 | 171.4 | 0.8 | 1.5 | 2.1 | 2.3 | 169.7 | 0.6 | 1.1 | 1.7 | 2.0 | 168.0 | 0.4 | 0.8 | 1.3 | 1.7 |
| | | | 7 | 5.5 | 229.0 | 0.9 | 1.7 | 2.6 | 3.0 | 226.3 | 0.6 | 1.2 | 1.9 | 2.6 | 223.6 | 0.4 | 0.9 | 1.4 | 2.1 |
| | | | 9 | 5.5 | 285.8 | 1.0 | 1.9 | 2.9 | 3.7 | 282.0 | 0.7 | 1.3 | 2.1 | 3.1 | 278.4 | 0.4 | 0.9 | 1.6 | 2.4 |
| 3/4 | #1 | 2x6 | 4 | 8.0 | 229.7 | 1.4 | 1.9 | 2.0 | 2.1 | 227.8 | 1.0 | 1.6 | 1.7 | 1.8 | 225.9 | 0.7 | 1.3 | 1.4 | 1.6 |
| | | | 5 | 7.0 | 275.3 | 1.4 | 2.2 | 2.4 | 2.6 | 272.8 | 1.0 | 1.8 | 2.0 | 2.2 | 270.3 | 0.7 | 1.4 | 1.7 | 1.9 |
| | | | 7 | 6.5 | 365.3 | 1.6 | 2.8 | 3.1 | 3.4 | 361.3 | 1.1 | 2.1 | 2.6 | 2.9 | 357.3 | 0.7 | 1.5 | 2.2 | 2.5 |
| | | | 9 | 6.0 | 454.1 | 1.7 | 3.1 | 3.8 | 4.1 | 448.4 | 1.1 | 2.2 | 3.1 | 3.5 | 442.9 | 0.7 | 1.6 | 2.6 | 3.0 |
| 3/4 | #3 | 2x6 | 4 | 7.5 | 147.7 | 0.9 | 1.7 | 2.0 | 2.1 | 146.5 | 0.7 | 1.3 | 1.7 | 1.8 | 145.3 | 0.5 | 0.9 | 1.4 | 1.6 |
| | | | 5 | 7.0 | 177.0 | 1.0 | 1.8 | 2.3 | 2.5 | 175.4 | 0.7 | 1.3 | 2.0 | 2.1 | 173.7 | 0.5 | 1.0 | 1.5 | 1.9 |
| | | | 7 | 6.0 | 234.9 | 1.1 | 1.9 | 3.0 | 3.3 | 232.3 | 0.7 | 1.4 | 2.2 | 2.8 | 229.7 | 0.5 | 1.0 | 1.7 | 2.4 |
| | | | 9 | 5.5 | 291.9 | 1.1 | 2.1 | 3.2 | 4.0 | 288.3 | 0.8 | 1.5 | 2.4 | 3.4 | 284.7 | 0.5 | 1.1 | 1.8 | 2.6 |
| 1-1/8 | #1 | 2x6 | 4 | 8.5 | 247.3 | 1.9 | 2.2 | 2.3 | 2.4 | 245.6 | 1.4 | 1.8 | 1.9 | 2.1 | 243.9 | 1.0 | 1.6 | 1.7 | 1.8 |
| | | | 5 | 8.0 | 293.6 | 1.9 | 2.6 | 2.7 | 2.9 | 291.3 | 1.4 | 2.2 | 2.3 | 2.5 | 289.0 | 1.1 | 1.8 | 2.0 | 2.2 |
| | | | 7 | 7.0 | 384.8 | 2.1 | 3.4 | 3.6 | 3.8 | 381.2 | 1.5 | 2.8 | 3.0 | 3.3 | 377.6 | 1.1 | 2.1 | 2.6 | 2.9 |
| | | | 9 | 6.5 | 474.6 | 2.2 | 4.0 | 4.4 | 4.7 | 469.5 | 1.5 | 2.9 | 3.7 | 4.0 | 464.4 | 1.1 | 2.1 | 3.1 | 3.5 |
| 1-1/8 | #1 | 2x8 | 4 | 11.0 | 313.7 | 2.6 | 3.0 | 3.1 | 3.2 | 312.2 | 1.9 | 2.5 | 2.6 | 2.7 | 310.7 | 1.5 | 2.2 | 2.3 | 2.4 |
| | | | 5 | 10.5 | 376.7 | 2.7 | 3.6 | 3.7 | 3.9 | 374.6 | 2.0 | 3.0 | 3.2 | 3.4 | 372.6 | 1.5 | 2.6 | 2.8 | 2.9 |
| | | | 7 | 9.5 | 501.5 | 3.0 | 4.8 | 5.0 | 5.2 | 498.3 | 2.2 | 4.0 | 4.3 | 4.5 | 495.1 | 1.6 | 3.2 | 3.7 | 4.0 |
| | | | 9 | 9.0 | 625.3 | 3.2 | 5.9 | 6.2 | 6.6 | 620.7 | 2.4 | 4.5 | 5.3 | 5.7 | 616.2 | 1.7 | 3.4 | 4.5 | 4.9 |

Table A2-2B PSSP DESIGNS FOR HIGHER STRENGTH STRINGERS ($F_v = 380$ psi)
(Columns and Beam-Columns)

Panel Width: 48 in.

| Top & Bottom Skins | | Stringers | | Req'd* Bearing Length Ea. End | | Panel Height = 7 ft | | | | | | Panel Height = 8 ft | | | | | | Panel Height = 9 ft | | | | | |
|-----------------------|-------------|--------------|-----|--|--|-----------------------------|-----|-----|--|-----|--|-----------------------------|-----|-----|--|-----|--|-----------------------------|-----|-----|--|-----|--|
| | | | | | | P _{da} # (kips) | | | P _{dm} (psi) for P _d /P _{da} = | | | P _{da} # (kips) | | | P _{dm} (psi) for P _d /P _{da} = | | | P _{da} # (kips) | | | P _{dm} (psi) for P _d /P _{da} = | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| Nom. Thick. | Face Ply | Nom. Size | No. | | | 0.8 | 0.6 | 0.4 | 0.2 | | | 0.8 | 0.6 | 0.4 | 0.2 | | | 0.8 | 0.6 | 0.4 | 0.2 | | |
| 1/2 | #1 | 2x4 | 4 | 3.5 | | 130.7 | 0.6 | 1.1 | 1.4 | 1.6 | | 128.5 | 0.4 | 0.7 | 1.2 | 1.3 | | 126.5 | 0.2 | 0.5 | 0.9 | 1.2 | |
| | | | 5 | 3.5 | | 109.5 | 0.6 | 1.1 | 1.6 | 1.8 | | 106.4 | 0.4 | 0.8 | 1.3 | 1.5 | | 103.4 | 0.2 | 0.5 | 0.9 | 1.3 | |
| | | | 7 | 3.0 | | 219.5 | 0.6 | 1.1 | 1.9 | 2.3 | | 214.8 | 0.3 | 0.7 | 1.3 | 1.9 | | 191.1 | 0.2 | 0.5 | 1.0 | 1.7 | |
| | | | 9 | 2.5 | | 268.0 | 0.5 | 1.1 | 2.0 | 2.7 | | 261.5 | 0.2 | 0.7 | 1.3 | 2.2 | | 203.1 | 0.3 | 0.7 | 1.2 | 1.8 | |
| 1/2 | #3 | 2x4 | 4 | 3.5 | | 84.0 | 0.4 | 0.7 | 1.1 | 1.5 | | 82.6 | 0.3 | 0.5 | 0.8 | 1.2 | | 81.3 | 0.2 | 0.4 | 0.6 | 0.9 | |
| | | | 5 | 3.0 | | 109.0 | 0.4 | 0.8 | 1.2 | 1.7 | | 107.0 | 0.3 | 0.5 | 0.9 | 1.3 | | 105.0 | 0.1 | 0.3 | 0.6 | 1.0 | |
| | | | 7 | 2.5 | | 141.1 | 0.4 | 0.8 | 1.3 | 1.9 | | 138.1 | 0.2 | 0.5 | 0.9 | 1.4 | | 135.1 | 0.1 | 0.3 | 0.6 | 1.0 | |
| | | | 9 | 2.5 | | 172.3 | 0.4 | 0.8 | 1.3 | 2.0 | | 168.1 | 0.2 | 0.5 | 0.9 | 1.5 | | 148.5 | 0.1 | 0.4 | 0.7 | 1.2 | |
| 3/4 | #1 | 2x4 | 4 | 3.5 | | 152.3 | 0.6 | 1.2 | 1.3 | 1.5 | | 150.0 | 0.5 | 1.0 | 1.1 | 1.3 | | 147.9 | 0.4 | 0.7 | 0.9 | 1.1 | |
| | | | 5 | 3.5 | | 176.5 | 0.6 | 1.5 | 1.8 | 2.0 | | 175.5 | 0.5 | 1.0 | 1.5 | 1.7 | | 172.7 | 0.3 | 0.7 | 1.2 | 1.5 | |
| | | | 7 | 3.0 | | 229.3 | 0.8 | 1.5 | 2.3 | 2.7 | | 224.6 | 0.5 | 1.0 | 1.7 | 2.3 | | 220.5 | 0.3 | 0.6 | 1.2 | 1.9 | |
| | | | 9 | 2.5 | | 278.5 | 0.6 | 1.5 | 2.4 | 3.2 | | 272.2 | 0.4 | 0.9 | 1.7 | 2.6 | | 264.2 | 0.2 | 0.6 | 1.2 | 2.0 | |
| 3/4 | #3 | 2x4 | 4 | 3.5 | | 97.9 | 0.5 | 0.9 | 1.4 | 1.5 | | 96.4 | 0.4 | 0.7 | 1.1 | 1.3 | | 95.1 | 0.2 | 0.5 | 0.8 | 1.1 | |
| | | | 5 | 3.5 | | 114.7 | 0.5 | 1.0 | 1.5 | 2.0 | | 112.9 | 0.4 | 0.7 | 1.1 | 1.6 | | 111.0 | 0.2 | 0.5 | 0.8 | 1.2 | |
| | | | 7 | 3.0 | | 147.4 | 0.5 | 1.0 | 1.5 | 2.2 | | 144.5 | 0.3 | 0.7 | 1.1 | 1.6 | | 141.7 | 0.2 | 0.5 | 0.8 | 1.2 | |
| | | | 9 | 2.5 | | 179.0 | 0.5 | 1.0 | 1.6 | 2.3 | | 175.0 | 0.3 | 0.7 | 1.1 | 1.7 | | 171.2 | 0.2 | 0.4 | 0.8 | 1.3 | |
| 1-1/8 | #1 | 2x4 | 4 | 3.5 | | 170.1 | 1.2 | 1.4 | 1.5 | 1.6 | | 168.0 | 0.8 | 1.1 | 1.2 | 1.4 | | 166.0 | 0.6 | 0.9 | 1.1 | 1.2 | |
| | | | 5 | 3.5 | | 197.2 | 1.2 | 1.8 | 2.0 | 2.1 | | 194.5 | 0.8 | 1.5 | 1.7 | 1.8 | | 191.9 | 0.6 | 1.1 | 1.4 | 1.6 | |
| | | | 7 | 4.0 | | 249.8 | 1.2 | 2.2 | 3.0 | 3.2 | | 245.7 | 0.8 | 1.5 | 2.4 | 2.8 | | 241.8 | 0.6 | 1.1 | 1.8 | 2.4 | |
| | | | 9 | 3.5 | | 300.8 | 1.2 | 2.2 | 3.4 | 4.0 | | 295.1 | 0.8 | 1.5 | 2.4 | 3.4 | | 289.6 | 0.5 | 1.1 | 1.8 | 2.7 | |

Table A2-2B (Concluded)

Panel Width: 48 in.

| Top & Bottom Skins | | Stringers | Req'd* Bearing Length Ea. End | Panel Height = 7 ft | | | | Panel Height = 8 ft | | | | Panel Height = 9 ft | | | | | | |
|--------------------|-------------|--------------|--|--|-----|-----|-----|--|---------------------------|-----|-----|--|-----|---------------------------|-----|-----|-----|-----|
| | | | | P _{dm} (psi) for P _d /P _{da} = | | | | P _{dm} (psi) for P _d /P _{da} = | | | | P _{dm} (psi) for P _d /P _{da} = | | | | | | |
| Nom. Thick. | Face Ply | Nom. Size | No. | P _{da} (kips) | 0.8 | 0.6 | 0.4 | 0.2 | P _{da} (kip.) | 0.8 | 0.6 | 0.4 | 0.2 | P _{da} (kips) | 0.8 | 0.6 | 0.4 | 0.2 |
| 1/2 | #1 | 2x6 | 4 | 201.2 | 1.1 | 2.1 | 2.5 | 2.7 | 199.4 | 0.8 | 1.5 | 2.1 | 2.3 | 197.6 | 0.6 | 1.1 | 1.8 | 2.0 |
| | | | 5 | 266.7 | 1.2 | 2.3 | 3.0 | 3.2 | 264.0 | 0.8 | 1.7 | 2.5 | 2.8 | 261.3 | 0.6 | 1.2 | 2.1 | 2.4 |
| | | | 7 | 356.2 | 1.3 | 2.5 | 3.8 | 4.2 | 352.0 | 0.9 | 1.8 | 2.9 | 3.6 | 347.8 | 0.6 | 1.2 | 2.1 | 3.1 |
| | | | 9 | 444.6 | 1.4 | 2.8 | 4.4 | 5.2 | 438.7 | 0.9 | 1.9 | 3.1 | 4.4 | 433.0 | 0.6 | 1.3 | 2.1 | 3.6 |
| 1/2 | #3 | 2x6 | 4 | 129.4 | 0.7 | 1.3 | 2.0 | 2.6 | 128.2 | 0.5 | 1.0 | 1.5 | 2.1 | 127.0 | 0.4 | 0.7 | 1.2 | 1.6 |
| | | | 5 | 171.4 | 0.8 | 1.5 | 2.4 | 3.1 | 169.7 | 0.6 | 1.1 | 1.7 | 2.5 | 168.0 | 0.4 | 0.8 | 1.3 | 1.9 |
| | | | 7 | 229.0 | 0.9 | 1.7 | 2.6 | 3.7 | 226.3 | 0.6 | 1.2 | 1.9 | 2.8 | 223.6 | 0.4 | 0.9 | 1.4 | 2.1 |
| | | | 9 | 285.8 | 1.0 | 1.9 | 2.9 | 4.1 | 282.0 | 0.7 | 1.3 | 2.1 | 3.1 | 278.4 | 0.4 | 0.9 | 1.6 | 2.4 |
| 3/4 | #1 | 2x6 | 4 | 229.7 | 1.4 | 2.2 | 2.3 | 2.5 | 227.8 | 1.0 | 1.8 | 2.0 | 2.1 | 225.9 | 0.7 | 1.4 | 1.7 | 1.9 |
| | | | 5 | 275.3 | 1.4 | 2.7 | 3.2 | 3.4 | 272.8 | 1.0 | 2.0 | 2.7 | 3.0 | 270.3 | 0.7 | 1.4 | 2.3 | 2.6 |
| | | | 7 | 365.3 | 1.6 | 2.9 | 4.2 | 4.6 | 361.3 | 1.1 | 2.1 | 3.3 | 3.9 | 357.3 | 0.7 | 1.5 | 2.5 | 3.4 |
| | | | 9 | 454.1 | 1.7 | 3.1 | 4.9 | 5.6 | 448.4 | 1.1 | 2.2 | 3.6 | 4.8 | 442.9 | 0.7 | 1.6 | 2.6 | 4.0 |
| 3/4 | #3 | 2x6 | 4 | 147.7 | 0.9 | 1.7 | 2.5 | 2.6 | 146.5 | 0.7 | 1.3 | 1.9 | 2.3 | 145.3 | 0.5 | 0.9 | 1.5 | 2.0 |
| | | | 5 | 177.0 | 1.0 | 1.8 | 2.7 | 3.4 | 175.4 | 0.7 | 1.3 | 2.0 | 2.8 | 173.7 | 0.5 | 1.0 | 1.7 | 2.2 |
| | | | 7 | 234.5 | 1.1 | 1.9 | 3.0 | 4.1 | 232.5 | 0.7 | 1.4 | 2.2 | 3.1 | 229.7 | 0.5 | 1.0 | 1.7 | 2.1 |
| | | | 9 | 291.9 | 1.1 | 2.1 | 3.2 | 4.5 | 288.3 | 0.8 | 1.5 | 2.4 | 3.4 | 284.7 | 0.5 | 1.1 | 1.8 | 2.1 |
| 1-1/8 | #1 | 2x6 | 4 | 247.3 | 1.9 | 2.5 | 2.4 | 2.5 | 245.6 | 1.4 | 1.9 | 2.0 | 2.2 | 243.9 | 1.0 | 1.8 | 1.8 | 1.9 |
| | | | 5 | 293.0 | 1.9 | 3.1 | 3.2 | 3.4 | 291.3 | 1.4 | 2.6 | 2.8 | 2.9 | 289.0 | 1.1 | 2.0 | 2.4 | 2.6 |
| | | | 7 | 384.8 | 2.1 | 3.8 | 4.9 | 5.2 | 381.2 | 1.5 | 2.8 | 4.1 | 4.5 | 377.0 | 1.1 | 2.1 | 3.3 | 3.9 |
| | | | 9 | 474.6 | 2.2 | 4.0 | 5.9 | 6.4 | 469.5 | 1.5 | 2.9 | 4.5 | 5.5 | 464.4 | 1.1 | 2.1 | 3.4 | 4.7 |
| 1-1/8 | #1 | 2x8 | 4 | 313.7 | 2.6 | 3.4 | 3.3 | 3.4 | 312.2 | 1.9 | 2.7 | 2.8 | 2.9 | 310.7 | 1.5 | 2.3 | 2.5 | 2.6 |
| | | | 5 | 376.7 | 2.7 | 4.4 | 4.5 | 4.7 | 374.6 | 2.0 | 3.7 | 3.9 | 4.1 | 372.6 | 1.5 | 2.9 | 3.4 | 3.6 |
| | | | 7 | 501.5 | 3.0 | 5.0 | 6.8 | 7.1 | 498.0 | 2.2 | 4.2 | 5.8 | 6.2 | 495.1 | 1.6 | 3.2 | 4.9 | 5.4 |
| | | | 9 | 625.3 | 3.2 | 6.1 | 8.5 | 8.9 | 620.7 | 2.4 | 4.5 | 6.9 | 7.7 | 616.2 | 1.7 | 3.4 | 5.5 | 6.7 |

PSSP Upgrading Example - Column

Try one of the PSSP designs as an added column in upgrading a basement for shelter. Assume a closed shelter, therefore no blast or other lateral load on the PSSP.

Assume use of a PSSP design on p. A2-18 that is, the one with $\frac{1}{2}$ " th. #3 top and bottom skins with 4 lower strength 2x4 stringers. Table A2-2A shows a max. column load P of 84 kips, which includes an increase of normal use design by 4x and use of $\mu=1$ (see p. A2-7, 4th paragraph).

Thus, for example, the 84^k column, supporting a floor contributory area of 5' by 6', or 30 sq', will take a blast loading on the floor over the basement of:

$$p_s = \frac{84000}{30} \times \frac{1}{144} = 19 \text{ psi}$$

A more precise figure, used below for demonstration and not to imply a degree of accuracy, would be:

$$p_s = 19.44 \text{ psi (blast loading)}$$

If soil loads are added on the floor for fallout shielding, say 200 psf:

$$P(\text{static loads}) = P_s \times \frac{1}{4} \times 2 = \frac{19.44}{4} \times 2 = 9.72 \text{ psi}$$

where $\frac{1}{4}$ represents removing the multiple of 4 taken (in the table) for blast loads, and 2 represents removing the effect of $\mu=1$ in preparing the table.

The fallout soil, if left on the floor for less than 2 mos. merits a 15% increase in allowable stress, thus, the remaining static load capacity

$$P(\text{static loads}) = 9.72 - \left[\frac{200 \times \frac{1}{144}}{1.15} \right] \\ = 9.72 - 1.21 = 8.51 \text{ psi}$$

Reconverted to blast resistance capacity (but with 200 psf soil added to the floor load):

$$p_s = 8.51 \times 4 \times \frac{1}{2} = 17 \text{ psi (blast loading)}$$

NOTATION

- A = total x-sectional area of longitudinal grain material in both plywood skins and stringers (in.²)
- b = least dimension of solid rectangular cross-section (in.)
- c = distance from N.A. (bending) to extreme fiber in compression (in.)
- d = greater dimension of solid rectangular cross-section (in.)
- d' = depth of PSSP stringers (in.)
- E = modulus of elasticity (psi)
- (EI_g) = stiffness factor for moment deflection [1(Sec.2.4.3)] (lbs-in.² for full panel) (from Step 4, Appendix A1)
- (EI_n) = stiffness factor for bending moment [1(Sec.2.5.3)] 1lb-in.² for full panel) (from Step 8, Appendix A1)
- F_c = allowable compressive stress (parallel to grain) for plywood skins (psi) [2(p.17)], corrected for buckling [1(Sec.2.5.4)]
- I_g = gross moment of inertia of cross-section (in.⁴)
- I_n = bending moment of inertia of full panel (in.⁴)
- ℓ = clear span of member (simply-supported/pin-ended) (in.)
- ℓ' = width of PSSP skins (perpendicular to stringers) (in.)
- M = allowable bending moment (in.-lb), under combined loading
- M_{max} = maximum moment caused by transverse loads only (in.-lb)
- P = allowable axial load (lbs), under combined loading
- P_a = allowable axial load (lbs), if axial load only exists
- P_d = dynamic (blast) load value related to P (lbs)
- P_{da} = dynamic (blast) load value related to P_a (lbs)
- P_m = smallest of calculated allowable transverse (only) loads (in PSSPs, calculated loads for: deflection, bending moment, rolling shear and horizontal shear) (psi) (from Appendix A1 design of PSSPs)
- P_{dm} = dynamic (blast) load value related to p_m (psi)

NOTATION (concluded)

p'_m = an intermediate value between p_m and zero (psi)
 p'_{dm} = dynamic (blast) load value corresponding to p'_m (psi)
 r = radius of gyration (in.)
 S = section modulus of full panel (in.³)
 x = location being examined (length along member) (in.)
 y = deflection of column at M (in.)
 \bar{y} = deflection of column at M_{max} (transverse loads only) (in.)
 μ = ductility ratio = x_m / x_e (see Appendix A)

REFERENCES

1. "Design of Plywood Stressed-Skin Panels," Supplement 3 to Plywood Design Specification (PDS), American Plywood Association, P.O. Box 11700, Tacoma, Washington 98411, revised December 1976.
2. Plywood Design Specifications (PDS), American Plywood Association, revised April 1978.
3. National Design Specification for Wood Construction, National Forest Products Association, 1619 Massachusetts Avenue, N. W., Washington, D.C. 20036, 1977 edition, with Supplement, "Design Values for Wood Construction," published separately, 1980.
4. Eshbach, O. W., Handbook of Engineering Fundamentals, 2nd ed. (Wiley), 1952; p. 5-32 and 5-42 to -48. Also 3rd ed., with M. Souders, 1975; p. 518 and 528 to 534.
5. Murphy, H. L., and J. E. Beck, Maximizing Protection in New EOCs From Nuclear Blast and Related Effects: Guidance Provided by Lecture and Consultation, Stanford Research Institute¹⁰ Technical Report for U.S. Defense Civil Preparedness Agency,¹¹ September 1976. (AD-A039 499)
6. Manual of Steel Construction, American Institute of Steel Construction, Inc., Wrigley Building (8th floor), 400 North Michigan Avenue, Chicago, Illinois 60611, 7th ed., 1970; p. 2-198, panel 1.
7. Murphy, H. L., J. R. Rempel, and J. E. Beck, SLANTING IN NEW BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: A Consolidated Printing of Four Technical Reports, Stanford Research Institute¹⁰ Technical Reports, 3 vols., for U.S. Defense Civil Preparedness Agency,¹¹ October 1975. (AD-A023 237)
8. Murphy, H. L., and J. E. Beck, Slanting for Combined Nuclear Weapons Effects: EXAMPLES WITH ESTIMATES AND AIR BLAST ROOM FILLING, Stanford Research Institute¹⁰ Technical Report, for U.S. Defense Civil Preparedness Agency,¹¹ June 1973. (AD-783 061)
9. Newmark, N. M., Design of Openings for Buried Shelters, Report 2-67, U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi, July 1963; p. 151-182.

¹⁰ Now SRI International

¹¹ Now Federal Emergency Management Agency

Appendix A3

PLYWOOD USE FOR CLOSURES - DESIGN

Extracts (with minor revisions) from the main text and Appendix A1 of

Murphy, H. L., Upgrading Basements for Combined Nuclear Weapons Effects:
Predesigned Expedient Options, Stanford Research Institute* Technical
Report, for U.S. Defense Civil Preparedness Agency, # October 1977.
(AD-A054 409)

* Now SRI International

Now Federal Emergency Management Agency

CONTENTS

| | |
|--|-------|
| BACKGROUND | A3-1 |
| APPROACH | A3-1 |
| DESIGN PROCEDURE | A3-3 |
| DESIGN STRESSES - Blast Protection Use versus Normal Use | A3-4 |
| TYPICAL DESIGNS OF PLYWOOD PANELS AS CLOSURES | A3-4 |
| NOTATION | A3-9 |
| REFERENCES | A3-11 |

TABLES

| | |
|--|------|
| A3-1. PLYWOOD PANELS AS CLOSURES (ONE-WAY) | A3-5 |
| A3-2. PLYWOOD PANELS AS CLOSURES (TWO-WAY) | A3-7 |

Background

Appendices A1 and A2, in their early paragraphs, describe plywood uses toward meeting the need for expedient aperture closures and added overhead floor system supports, respectively, in the upgrading of existing basements for shelter use against the combined effects of a nuclear weapons detonation. This Appendix A3 closes the area of plywood applications by describing a design approach for simple use of plywood for closures, especially over those many shelter openings having a rather short span in at least one of its two directions.

Approach

Use was made of two publications and telephone discussions¹⁻³ in developing a design procedure for use of plywood to close apertures in existing basements. The tables of the simplified publication² could not be reproduced through use of the design manual¹ procedures; requested clarification brought the recommendation that the latter be used for the purposes contemplated herein.³

As before, in Appendices A1 and A2, design formulas¹(pp.22-3,Sec.4) were converted to the Notation herein and made dimensionally consistent. The revised formulas follow; plywood weight is ignored as dead load, and single spans, uniform loads, and simple supports are assumed.

The user is cautioned to apply care in units used in entering all values in the equations below; all equations are dimensionally consistent, i.e., there are no units hidden in the constants.

A. For uniform loads based on allowable bending stress:

$$p_b = 8 F_b S / \ell^2 \quad (\text{Eq.A3-1})^\dagger$$

where*

p_b = allowable load - bending moment (psi)

F_b = allowable bending stress (psi)

* Variables are defined herein at point of first use and in Notation at end of appendix.

† In Eq. A3-1, clear span can be used (per Reference 3 footnote of 1/6/78).

S = effective section modulus ($\text{in.}^3/\text{in. width}$)

ℓ = clear span (in.)

- B. For uniform loads based on allowable rolling shear stress:

$$p_s = 2 F_s (Ib/Q) / \ell \quad (\text{Eq. A3-2})$$

where

p_s = allowable load - rolling shear stress (psi)

F_s = allowable rolling shear stress (psi)

(Ib/Q) = rolling shear constant ($\text{in.}^2/\text{in. width}$)

ℓ = clear span (in.)

The useful allowable load p_m then becomes:

$$p_m = p_b \text{ or } p_s \text{ whichever is smaller (psi)} \quad (\text{Eq. A3-3})$$

- C. For bending deflection (elastic) under uniform load:

$$y_b = p_m \ell^4 / (76.8 I (1.1 E)) \quad (\text{Eq. A3-4})^*$$

where

y_b = bending deflection (elastic) under uniform load (in.)

I = effective moment of inertia ($\text{in.}^4/\text{in. width}$)

E = modulus of elasticity (psi)

- D. For shear deflection (elastic) under uniform load:

$$y_s = p_m C t^2 \ell^2 / (106 EI) \quad (\text{Eq. A3-5})$$

where

y_s = shear deflection (elastic) under uniform load (in.)

C = 120 or 60, for panels applied with face grain perpendicular to or parallel to supports, respectively.

t = nominal panel thickness (in.)

- E. For combined bending and shear deflection (elastic) under uniform load: either (a) add y_b and y_s from Equations 4 and 5; or (b) use Equation 4 only, but with the constant 1.1 dropped from the equation.

* Modified very slightly as to ℓ from Ref. 1, for simplification and because of negligible effect on the uses made of deflection calculations herein.

F. For plywood face bearing under uniform load (at ends over simple supports):

$$l_e = l / (2(F_{c\perp}/p_m - 1)) \quad (\text{Eq.A3-6})$$

where

l_e = required plywood (face) end bearing length at each end of panel (in.)

$F_{c\perp}$ = allowable bearing stress on plywood face, for load perpendicular to plane of outer ply actually in bearing (psi)

It is recommended that l_e be at least 1.5 in.

Design Procedure

The suggested design procedure consists of the following Steps:

1. Assume use of a particular plywood type, grade, nominal thickness t , and face ply(ies) species group (pp. 9, 14 and 15)[†] except that the latter must not be #5. Also assume that panel is uniformly loaded and simply supported,[‡] and assume value for span l (in.).

Neglect the plywood weight as a DL.

2. Determine values (p. 16)[†] for I , S (=KS), and (Ib/Q) , taking care to correct the units to in.^4 , in.^3 , and in.^2 (all per in. width), respectively. Take care to use proper values for plywood used with the face grain running parallel to the span (cols. 5-7)[†] or perpendicular to the span (col. 9-11),[†] as well as the appropriate table (1 or 2)[†] and section (Unsanded, Sanded, or Touch-Sanded Panels).[†] If permitted by available supplies, plywood panels are used with the face grain running parallel to the span, which takes advantage of the stronger direction of the plywood.

[†] See Reference 1; it is necessary that the designer hold this reference.

[‡] On two opposite sides; but Step 7 extends the procedure to plywood panels supported on four sides.

3. Study the plywood data (p.14)* and select appropriate use condition (Wet or Dry) and grade stress level (S-1, -2, or -3). Determine values (p. 17)* for F_b , F_s , $F_{c\perp}$, and E (all psi).
4. Solve Equations 1-3 for p_b , p_s , and p_m , respectively.
5. Solve Equation 6 for l_e .
6. If deflections are needed or desired, either:
 - (a) Solve Equations 4 and 5 for y_b and y_s , respectively ; then $y = y_b + y_s$; or
 - (b) Solve Equation 4 with the value 1.1 deleted on right side; then $y = y_b$.
7. For plywood panels supported on four sides, the procedure is as follows:^{2,3}
 - (a) Complete Steps 1-4 and 6 for each span direction, finding p_m and y for each direction;
 - (b) Reduce the p_m value associated with the larger y , by multiplying that p_m by the ratio of the smaller y to the larger y . The two y values will then be equal, and the total capacity p_m of the panel supported on four sides will be the sum of the p_m just reduced and the unchanged p_m associated with the smaller y of Step 7a; use the latter two p_m values to find l_e in each direction (Step 5).

Design Stresses - Blast Protection Use versus Normal Use

An Appendix A1 section with the same title applies fully herein, excepting that $\mu = 3$ is recommended for this appendix; thus, $p_{dm} = (5/6) p_m$, and F_b and F_s (but not $F_{c\perp}$ and E) are multiplied by four.

Typical Designs of Plywood Panels as Closures

Data in the preceding sections have been used to prepare the typical designs of plywood panels as closures shown in Tables A3-1A, -1B, -1C and -2. Computer programs used are listed in Table A3-3 of the original publication but not extracted herein.

* See Reference 1; it is necessary that the designer hold this reference.

Table A3-1A PLYWOOD PANELS AS CLOSURES (ONE-WAY)

Plywood panels considered herein are each stamped with American Plywood Association (APA) Type (Interior or Exterior), Grade and, in most cases, with Face Ply Species Group(s) (the latter exception is discussed further below), as follows:

| <u>Plywood Type and Grade</u> | <u>Table A3-1B&C Block Nos.</u> |
|--|---|
| C-D INTERIOR (APA), * usual: | 3,11 |
| If "interior with exterior glue" is specified: | 2,10 |
| UNDERLAYMENT INTERIOR (APA), usual: | 8,16 |
| If "interior with exterior glue" is specified: | 7,15 |
| C-D PLUGGED INTERIOR (APA), usual: | 8,16 |
| If "interior with exterior glue" is specified: | 7,15 |
| 2.4.1 STURD-I-FLOOR INTERIOR (APA), with veneer inner plies only | 17 |
| APPEARANCE GRADES (Interior) (APA), † usual: | 6,14 |
| If "interior with exterior glue" is specified: | 5,13 |
| C-C EXTERIOR (APA)* | 1,9 |
| UNDERLAYMENT EXTERIOR (APA) | 7,15 |
| C-C PLUGGED EXTERIOR (APA) | 7,15 |
| 2.4.1 STURD-I-FLOOR EXTERIOR (APA), with veneer inner plies only | 17 |
| APPEARANCE GRADES (Exterior) (APA), ‡ with Surface A or C, face & back: | 4,12 |
| With Surface B face or back: | 5,13 |

* Face Ply Species Groups are as follows: When stamped 24/0 on 1/2 in. (13 mm) thick plywood, Group 4; 32/16, Group 1; on 3/4 in. (19 mm): 42/20, Group 3; 48/24, Group 1.

† Generally applied where a high quality surface is required; includes N-N, N-A, N-B, N-D, A-A, A-B, A-D, B-B and B-D INTERIOR (APA) Grades.

‡ Generally applied where a high quality surface is required; includes A-A, A-B, A-C, B-B, B-C, HDO and MDO EXTERIOR (APA) Grades.

Table A3-1B PLYWOOD PANELS AS CLOSURES (ONE-WAY)*

| Block No. | PLYWOOD | | | | (SIDE-ON) PEAK AIR BLAST OVERPRESSURE VS. CL. SPAN | | | | | | | | | | | | |
|-----------|--------------|----------------|------------------|---------------|--|----------------|----------------|----------------|----------------|--------------|-------------|-------------|--------|----|----|----|----|
| | Nom. Th. in. | Surface Finish | Grade Str. Level | Face Ply Grp | Clear Span, in. | | | | | | | | | | | | |
| | | | | | 4 | 6 | 8 | 10 | 12 | 14 | 16 | 18 | 20 | 22 | 24 | 26 | 28 |
| 1. | 1/2 | UNSANDED | S-1 | 1 2,3 4 | 31 31 31 | 21 21 20 | 15 12 11 | 11 8 7 | 8 5 5 | 6 psi | | | | | | | |
| 2. | 1/2 | UNSANDED | S-2 | 1 2,3 4 | 31 31 31 | 21 18 17 | 14 10 10 | 9 7 6 | 6 5 5 | 5 | | | | | | | |
| 3. | 1/2 | UNSANDED | S-3 | 1 2,3 4 | 28 28 28 | 19 18 17 | 14 10 10 | 9 7 6 | 6 5 5 | 5 | | | | | | | |
| 4. | 1/2 | SANDED | S-1 | 1 2,3 4 | 36 36 36 | 24 23 22 | 18 13 12 | 12 8 8 | 8 6 5 | 6 5 | | | | | | | |
| 5. | 1/2 | SANDED | S-2 | 1 2,3 4 | 36 36 36 | 24 20 18 | 15 11 10 | 10 7 7 | 7 5 5 | 5 | | | | | | | |
| 6. | 1/2 | SANDED | S-3 | 1 2,3 4 | 32 32 32 | 21 20 18 | 15 11 10 | 10 7 7 | 7 5 5 | 5 | | | | | | | |
| 7. | 1/2 | TOUCH-S. | S-2 | 1 2,3 4 | 31 31 31 | 21 20 19 | 16 11 10 | 10 7 7 | 7 5 5 | 5 | | | | | | | |
| 8. | 1/2 | TOUCH-S. | S-3 | 1 2,3 4 | 28 28 28 | 19 19 19 | 14 11 10 | 10 7 7 | 7 5 5 | 5 | | | | | | | |
| 9. | 3/4 | UNSANDED | S-1 | 1 2,3 4 | 50 50 50 | 33 33 33 | 25 24 23 | 20 16 15 | 15 11 10 | 11 8 8 | 9 6 6 | 7 5 5 | 6 5 | | | | |
| 10. | 3/4 | UNSANDED | S-2 | 1 2,3 4 | 50 50 50 | 33 33 33 | 25 21 19 | 18 13 12 | 13 9 9 | 9 7 6 | 7 5 5 | 6 5 | 5 | | | | |
| 11. | 3/4 | UNSANDED | S-3 | 1 2,3 4 | 45 45 45 | 30 30 30 | 23 21 19 | 18 13 12 | 13 9 9 | 9 7 6 | 7 5 5 | 6 5 | 5 | | | | |
| 12. | 3/4 | SANDED | S-1 | 1 2,3 4 | 58 58 58 | 39 39 37 | 29 22 21 | 20 14 13 | 14 10 9 | 10 7 7 | 8 5 5 | 6 5 | 5 | | | | |
| 13. | 3/4 | SANDED | S-2 | 1 2,3 4 | 58 58 58 | 39 33 31 | 26 19 17 | 17 12 11 | 12 8 8 | 8 6 6 | 6 5 | 5 | | | | | |
| 14. | 3/4 | SANDED | S-3 | 1 2,3 4 | 53 53 53 | 35 33 31 | 26 19 17 | 17 12 11 | 12 8 8 | 8 6 6 | 6 5 | 5 | | | | | |
| 15. | 3/4 | TOUCH-S. | S-2 | 1 2,3 4 | 51 51 51 | 34 34 33 | 25 20 18 | 17 13 12 | 12 9 8 | 9 6 6 | 7 5 5 | 5 | | | | | |
| 16. | 3/4 | TOUCH-S. | S-3 | 1 2,3 4 | 46 46 46 | 31 31 31 | 23 20 18 | 17 13 12 | 12 9 8 | 9 6 6 | 7 5 5 | 5 | | | | | |
| 17. | 1-1/8 | TOUCH-S. | S-2 | 1-3 | 52 | 39 | 31 | 25 | 19 | 14 | 11 | 9 | 8 | 6 | 5 | 5 | |

* Face ply grain running in span direction (i.e., perpendicular to the two supports). Required bearing length at each end (beyond clear span) is 1½ in. (38 mm) in all cases.

Table A3-2 PLYWOOD PANELS AS CLOSURES (TWO-WAY)

The purpose of this Table is to provide conversion percentages (increases) so that the user can use the data of Table A3-1B to obtain overpressure versus clear span data for two-way plywood panels (that is, supported on all four sides of the opening/aperture to be closed).

This Table is based on using plywood panels with their face ply grain running in the direction of the shorter of the aperture's two clear spans. Its results are expressed in terms of the ratio of the longer to the shorter of the two clear spans; such results are expressed as percentage increases in overpressure resistance values applied to the values in Table A3-1B, with such increases related to the BLOCK NUMBERS of the table.

Recommended support bearing length on all four sides is $1\frac{1}{2}$ in.

| TABLES A3-1B&C <u>BLOCK NUMBERS</u> | RATIO OF LONGER TO SHORTER CLEAR SPANS | | | |
|--|--|---------------|--------------|------------|
| | <u>1:1</u> | <u>1.25:1</u> | <u>1.5:1</u> | <u>2:1</u> |
| 1 - 3 | 6% | 2% | 1% | * |
| 4 - 6 | 23 | 10 | 5 | 1% |
| 7, 8 | 7 | 3 | 1 | * |
| 9 - 11 | 15 | 6 | 3 | 1 |
| 12 - 14 | 47 | 19 | 9 | 3 |
| 15, 16 | 19 | 8 | 4 | 1 |
| 17 | 43 | 18 | 9 | 3 |

* Less than 1/2%

NOTATION

| | |
|--------------|--|
| C | 120 <u>or</u> 60, for panels applied with face grain perpendicular to <u>or</u> parallel to supports, respectively |
| E | modulus of elasticity (psi) |
| F_b | allowable bending stress (psi) |
| $F_{c\perp}$ | allowable bearing stress on plywood face, for load perpendicular to plane of outer ply actually in bearing (psi) |
| F_s | allowable rolling shear stress (psi) |
| I | <u>effective</u> moment of inertia ($\text{in.}^4/\text{in. width}$) |
| (Ib/Q) | rolling shear constant ($\text{in.}^2/\text{in. width}$) |
| L | span center-to-center of supports (in.) |
| t | clear span (in.) |
| ℓ_e | required plywood (face) end bearing length at <u>each</u> end of panel (in.) |
| p_b | allowable load - bending moment (psi) |
| p_{dm} | dynamic (blast) uniform load capacity (psi) |
| p_m | smaller of p_b or p_s = static uniform load capacity (psi) |
| p_s | allowable load - rolling shear stress (psi) |
| S | <u>effective</u> section modulus ($\text{in.}^3/\text{in. width}$) |
| t | nominal panel thickness (in.) |
| y | deflection (elastic) under uniform load (in.) |
| y_b | bending deflection (elastic) under uniform load (in.) |
| y_s | shear deflection (elastic) under uniform load (in.) |

REFERENCES

1. Plywood Design Specifications (PDS), American Plywood Association, 1119 A Street, Tacoma, Washington 98401, Revised December 1976.*
2. Plywood Design Manual - Shelving, American Plywood Association, 1119 A Street, Tacoma, Washington 98401, 1975.
3. Personal communications: Author with Wm. A. Baker, P.E., Head, Engineering Service, Applied Research Service, American Plywood Association, 1119 A Street, Tacoma, Washington 98401, July 22, 1977; and with James Elliott of Mr. Baker's staff, August 1, 1977.

* An April 1978 revision is now available and can be used; it was checked to determine the need for any recalculations for this extract from the Appendix A3 as previously published.

Appendix B1

WOOD BEAM AND COLUMN DESIGN - SIMPLY SUPPORTED

Revision of Appendix B, Design of Wood Beams, Simply Supported, as published in:

Murphy, H. L., and J. E. Beck, Slanting for Combined Nuclear Weapons Effects: BLAST-RESISTANT DESIGN/ANALYSIS WITH EXAMPLES, Stanford Research Institute¹ Final Report, for Defense Civil Preparedness Agency,² December 1974. (AD-A016 631)

Murphy, H. L., J. R. Rempel, and J. E. Beck, SLANTING IN NEW BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: A Consolidated Printing of Four Technical Reports, 3 Vols., Stanford Research Institute² Technical Reports, for Defense Civil Preparedness Agency,³ October 1975. (AD-A023 237)

Murphy, H. L., Upgrading Basements for Combined Nuclear Weapons Effects: Predesigned Expedient Options, Stanford Research Institute² Technical Report, for U.S. Defense Civil Preparedness Agency³, October 1977. (AD-A054 409)

¹ Now SRI International

² Now Federal Emergency Management Agency

CONTENTS

| | |
|---|-------|
| Wood Beams - Simply Supported | B1-1 |
| A. Design Procedure | B1-2 |
| B. Application to a Closure (Shelter Door) Design | B1-6 |
| C. Support Conditions Other Than Single-Span Simply Supported . . | B1-14 |
| Wood Columns - Simple Supports | B1-15 |
| A. Design Procedure | B1-15 |
| B. Numerical Example - Design Using Figure B1-2 | B1-22 |
| C. End Bearing and Sill/Bottom Plate Design | B1-23 |
| Peak Air Blast Resistance Capacity - Side-on versus Head-on | B1-26 |
| NOTATION | B1-27 |
| REFERENCES | B1-31 |

TABLES

| | | |
|------|---|-------|
| B1-1 | ALLOWABLE HORIZONTAL SHEAR VALUES F_v (psi) | B1-4 |
| B1-2 | SELECTED DIMENSION LUMBER SPECIES, SIZES AND GRADES | B1-7 |
| B1-3 | COLUMN FORMULAS - SIMPLE SOLID COLUMN DESIGN | B1-17 |
| B1-4 | END GRAIN IN BEARING (psi) | B1-24 |

FIGURES

| | | |
|------|---------------------|-------|
| B1-1 | WOOD BEAM DESIGN | B1-11 |
| B1-2 | COLUMN DESIGN, WOOD | B1-19 |

Appendix B1

WOOD BEAM AND COLUMN DESIGN - SIMPLY SUPPORTED

This appendix deals with solid wood used in beams and columns.³

Wood Beams - Simply Supported

The wood contemplated for use under the design procedures described herein is structural or stress-graded lumber, which has been carefully graded in accordance with the standard grading rules for the appropriate trade association. A complete list of such associations is available; see Reference [1]⁴ Supplement, page 19. It is urged that all lumber contemplated for shelter use - specifically, lumber in structural components or members whose stress-resisting capability is important to the survival of shelterees (in contrast to such things as a door cross-brace that simply holds together the structurally significant members) - be reinspected and regraded by even poorly qualified personnel using the appropriate association's grading rules.

Other items for the designer's general consideration are:

- The lack of homogeneity in wood members dictates that every effort be made to design wood structural members so that they interact in such a manner as to transfer load from a weaker, below-standard member to the better members. Examples are: really good blocking between floor joists; and use of tongue-and-groove planking as members used flat in a blast door. This is "repetitive-member use," see Reference [1] Supplement, Table 4A, 4th column.
- Only very tight knots should be accepted in a situation such as that of an unclad wood shelter blast door where an air blast loading could make a missile or bullet out of a knot that is even slightly loose.

³ Beam design chart solutions herein are for only single-span simply-supported (SS) beams; correction factors cover multi-span beams (section C, page B1-14). The design procedure also covers propped cantilever (PC) and fixed-fixed (FF) support conditions.

⁴ Brackets are used herein to indicate sources in the References list at the end of this appendix.

- Metal cladding may be indicated for some situations where wood is used, such as exposure to fires (or where required by local building code), but not necessarily when concern is only about exposure to a nuclear thermal pulse (which may well char the door without setting it on fire; the latter is a difficult thing to do to a flat wood wall).

Because this appendix is intended for use by engineers and architects, some technical competence in the usual design of wood structural members is assumed [2,3], and only those design considerations peculiar to nuclear blast effects loading will be treated in some detail in this appendix.

Reading/study of Appendix B2 may serve to increase the reader/user's understanding of wood design and use in upgrading.

A. Design Procedure

Because wood beams are available in specific dimensions, the general design approach is to select a trial member depth (measured in the direction of the applied load) and width, then find the air blast peak overpressure it can resist; this overpressure is compared to the specified overpressure to be resisted. The resistance of the selected member is based on elasto-plastic behavior and associated stress resistances in flexure (bending), horizontal shear, and bearing on a support, which resistances are checked in that order. Specifically, the flexure and horizontal shear resistances are found, and then a new trial member is selected, repeating these steps until the lesser of the two resistances is found to be sufficient to meet the expected blast load. The required bearing area is then found directly.

It is recommended that the beam design procedures and graphs that follow be used only for L/d values equal to or greater than five (5), because of doubt that they apply to "deep beams" (L/d less than 5).

The design steps are as follows:

(1) A design air blast peak overpressure is specified, also whether its loading geometry will provide: a side-on overpressure (as in a wood door mounted flush with the earth's surface); a fully reflected overpressure (as in the front wall of a rectangular building); or a peak value of the average loading caused by a combination of side-on and drag pressure (as in the side-wall or roof of a rectangular building) [4,Sec.4.38]. Related variables, in the same order of loading geometries, look like this:

$$P_{dm} = P_{so} \text{ or } P_r \text{ or } [(P_{so} + C_d q) L/2U] \quad (1)$$

where q is the dynamic (wind) blast pressure (unlike the q for structural resistance used in the remainder of this section) [4,Table 4.40].

(2) A trial size of wood beam (actual depth d , measured in direction of load, and thickness or width b) and kind of structural or stress-graded lumber are selected, then the grading association's design stresses are determined from their publications [1, Supplement, Table 4A].⁵ Need for the latter may be limited to F_b (extreme fiber stress in bending), F_v (horizontal shear stress), and $F_{c\perp}$ (compression stress perpendicular to grain, or bearing stress as used for beams only herein). For the short duration loadings furnished by nuclear air blast, dynamic values of the above three design stresses are recommended [5] as follows:

$$F_{db} = 4F_b ; F_{dv} = 4F_v ; \text{ and } F_{dc\perp} = F_{c\perp}$$

Some grading rules allow increases in design stress values for such things as: repetitive-member uses [1, Supplement, Table 4A, fourth column]; and, members used flatwise [1, Supplement, page 20, paragraph 6].

(3) A design ductility ratio μ is selected (see discussion in earlier Appendix A, General Comments on Blast-Resistant Design/Analysis General Approach). A value of 3 is recommended [5], certainly as an upper limit, and with 1.3 or 2 even better [6].

(4) A short design procedure [5] omits use of any loading decay (i.e., uses instead an instantaneously applied long duration load, or step pulse), load-mass factors, modulus of elasticity, elasto-plastic resistance function per se, etc., all in favor of the following approach: A step pulse is assumed, which is reasonable particularly when large yield weapons and short wood beams (therefore having very short periods of natural vibration) are considered.⁶ The other things ignored have been found to have little effect on the structural member selected for most applications; and needed parameters then have the following relationship:

$$p_{dm}/q = 1 - (1 / (2\mu))$$

where q is the ultimate resistance to blast loading of the wood beam. Using the recommended value of $\mu = 3$, the equation becomes: $p_{dm} = (5/6) q$.

(5) Span L (center-center of supports) and support conditions are known or assumed. Formulas are included herein for three beam support conditions: simply supported (SS); propped cantilever (PC); and both ends fixed (FF).

⁵ But if a Table B1-1 value for F_v is higher (than that given in Ref. [1]), use it.

⁶ Alternatives to this use of a step pulse are chart solutions and the Newmark β Method [7] or (better) the Modified Newmark β Method (by J. E. Beck) [8, p. 6-162].

Table B1-1

ALLOWABLE HORIZONTAL SHEAR VALUES F_v (psi)

| | Maximum Moisture Content | | |
|--|--------------------------|------------|------------|
| | Unseasoned | 19 percent | 15 percent |
| Aspen | 85 | 90 | 95 |
| Balsam Fir | 85 | 95 | 95 |
| Black Cottonwood | 70 | 75 | 80 |
| California Redwood | 115 | 120 | 130 |
| Coast Sitka Spruce | 90 | 95 | 100 |
| Coast Species | 90 | 95 | 100 |
| Douglas Fir-Larch | 130 | 140 | 145 |
| Douglas Fir-South | 130 | 140 | 145 |
| Eastern Hemlock-Tamarack | 120 | 130 | 135 |
| Eastern Spruce | 95 | 105 | 110 |
| Eastern White Pine | 90 | 95 | 100 |
| Eastern Woods | 85 | 95 | 95 |
| Engelmann Spruce/Alpine Fir | 95 | 105 | 110 |
| Hem-Fir | 105 | 110 | 115 |
| Idaho White Pine | 95 | 100 | 105 |
| Lodgepole Pine | 95 | 105 | 110 |
| Mountain Hemlock | 130 | 140 | 150 |
| Northern Aspen | 90 | 95 | 100 |
| Northern Pine | 100 | 105 | 110 |
| Northern Species | 90 | 95 | 100 |
| Northern White Cedar | 85 | 95 | 100 |
| Ponderosa Pine-Sugar Pine | 100 | 105 | 110 |
| Red Pine | 100 | 110 | 115 |
| Sitka Spruce | 105 | 115 | 120 |
| Southern Pine | 125 | 135 | 145 |
| Spruce-Pine-Fir | 95 | 105 | 110 |
| Western Cedar | 100 | 105 | 110 |
| Western Hemlock | 125 | 135 | 145 |
| Western White Pine | 90 | 100 | 105 |
| White Woods (Western Woods, West Coast Woods, Mixed Species) | 95 | 100 | 105 |

Source: National Design Specification for Wood Construction, 1977 Edition,
National Forest Products Association, 1619 Massachusetts Avenue, N.W.,
Washington, D. C. 20036; art. 3.4.4.2

Author Comments: Use column of above table that specifies "19 percent"
moisture content. For wood species not shown, consult "Design Values
for Wood Construction," 1980 Supplement to above Source.

(6) Flexural or bending resistance q_b (in terms of load/unit area) is calculated for the trial member:

$$M = wL^2c = q_b bL^2c = F_{db} S = F_{db} bd^2 / 6$$

$$q_b = F_{db}(d/L)^2 / (6c) = 2F_b(d/L)^2 / (3c) \quad (2)$$

where $c = 1/8$ (SS) and (PC), $1/12$ (FF).

(7) Horizontal shear resistance q_v (in terms of load/unit area) is also calculated for the trial member, with horizontal shear equal to vertical shear and taken at a distance d in from each end of the member: [2(p.4-12), 5(p.161)]

$$V = w(L-2d)c' = q_v b(L-2d)c' = 2AF_{dv} / 3 = 2bdF_{dv} / 3$$

$$q_v = 2F_{dv} d / (3c'(L-2d)) = 8F_v d / (3c'(L-2d)) \quad (3)$$

where $c' = 1/2$ (SS) and (FF), $5/8$ (PC), the latter value being approximate but close enough for the purposes herein. NOTE: EQ. 2 AND 3 INCLUDE THE MULTIPLE 4 OF STEP 2.

(8) Wood beam resistance q is then equal to the lesser value between q_b and q_v ; q is converted to peak air blast pressure by using:

$$p_{dm} = q (1 - (1 / (2\mu))) \quad (4)$$

or, when the recommended value of $\mu = 3$ is used, $p_{dm} = (5/6) q$.

(9) If p_{dm} is less than the design air blast peak overpressure specified in the first step herein, a larger beam, or a different wood or grade having larger design stresses, must be tried. If p_{dm} is larger than the design overpressure, then it may be desirable to try a smaller beam, or a different wood or grade, in an effort toward closer design. In either case, a new trial member requires that the designer return to the second step and repeat the procedure to this point.

(10) Required bearing length L' at each end of the wood beam is calculated as follows:

$$V = q_b Lc' = F_{c1} bL'$$

$$L' = qLc' / F_{c1} \quad (5)$$

where the values of c' are the same as in step 7 above. It is recommended that L' be at least 2 inches.

Another presentation of wood beam formulas is given in Appendix B2 (page B2-20).

Limitations on the above design procedure are stated in the two applications that follow.

B. Application to a Closure (Shelter Door) Design

An application of wood beam design occurs when low-cost blast doors must be designed for shelters, in new designs or existing structures. For an application in existing structures, particularly, a pre-design or chart approach was needed as follows:

- An estimate, calculated or judgmental, is made of the blast resistance of the wall adjacent to an aperture (door or window opening) for which a wood blast door is needed. The only designed structural element will be a wood beam, or series of wood beams side-by-side and preferably tongue-and-groove,⁷ simply supported on the two sides of the door frame (that has been either strengthened or found adequate to take the load from the door onto the wall).
- Stress-graded wood of various kinds (species and grades) in standard thicknesses⁸ (2, 3, 4 inches, nominal; 1.5, 2.5, 3.5 inches, actual) are checked for availability. See Table B1-2 for several popular woods and their allowable stresses.

a. The pre-design or chart approach developed for simplified handling of this problem is as follows, using solid, multiple wood beams, side-by-side:

(1) Obtain a copy of the industry association grading rules for each kind of wood contemplated for possible use; from this, make a tabulation (for each kind of wood and each thickness) of design stresses (psi) stated for use under normal loading for:

⁷ If not t&g (tongue-and-groove), use a light plywood sheet covering on the blast side; if either t&g or plywood-covered, "repetitive-member use" in F_b design values is appropriate [1, Supplement, Table 4A, 4th column].

⁸ Thickness and width are the terms applied to the smaller and larger cross-section dimensions, respectively, in the industry [1, Supplement, page 20, paragraph 6]. Engineers use thickness and width the same way in columns, but in beams they use width and depth as the cross-section dimensions perpendicular and parallel to the direction of loading, respectively (for example, the width of a beam 1.5"x3.5" in cross-section would be 1.5" if used edgewise, 3.5" if used flatwise (to the load direction)).

Table B1-2
SELECTED DIMENSION LUMBER SPECIES, SIZES AND GRADES *
(CONSTRUCTION GRADES)

| Size and Grade | Species | | | | | |
|--|------------------------|-----------------|---|---------------|---------------|------|
| | Douglas Fir-Larch | Western Hemlock | Western Pines (Ponderosa, Lodgepole, Sugar, and Idaho White) | Southern Pine | Northern Pine | |
| Allowable Unit Stresses in Normal Use, psi† | | | | | | |
| Structural Light Framing (2" to 4" th., 2" to 4" wide) | | | | | | |
| Stud (2x4s only) | F _b | 925 | 800 | 600 | 900 | 725 |
| | F _v | 95 | 90 | 70 | 90 | 70 |
| | F _{c⊥} | 385 | 280 | 190 | 405 | 280 |
| | E (x 10 ⁶) | 1.5 | 1.3 | 1.2 | 1.4 | 1.1 |
| | F _c | 600 | 550 | 425 | 775 | 475 |
| Light Framing (2" to 4" th., 4" wide) | | | | | | |
| Construction | F _b | 1200 | 1050 | 775 | 1150 | 950 |
| | F _v | 95 | 90 | 70 | 100 | 70 |
| | F _{c⊥} | 385 | 280 | 190 | 405 | 280 |
| | E | 1.5 | 1.3 | 1.2 | 1.4 | 1.1 |
| | F _c | 1150 | 1050 | 775 | 1100 | 875 |
| Standard | F _b | 675 | 600 | 425 | 675 | 525 |
| | F _v | 95 | 90 | 70 | 90 | 70 |
| | F _{c⊥} | 385 | 280 | 190 | 405 | 280 |
| | E | 1.5 | 1.3 | 1.2 | 1.4 | 1.1 |
| | F _c | 925 | 850 | 650 | 900 | 725 |
| Joists and Planks (2" to 4" th., 5" and wider) | | | | | | |
| No. 1 | F _b | 1750 | 1550 | 1100 | 1700 | 1400 |
| | F _v | 95 | 90 | 70 | 90 | 70 |
| | F _{c⊥} | 385 | 280 | 190 | 405 | 280 |
| | E | 1.8 | 1.6 | 1.4 | 1.7 | 1.4 |
| | F _c | 1250 | 1150 | 875 | 1250 | 975 |
| No. 2 | F _b | 1450 | 1250 | 925 | 1400 | 1100 |
| | F _v | 95 | 90 | 70 | 90 | 70 |
| | F _{c⊥} | 385 | 280 | 190 | 405 | 280 |
| | E | 1.7 | 1.4 | 1.3 | 1.6 | 1.3 |
| | F _c | 1050 | 975 | 725 | 1000 | 825 |
| No. 3 | F _b | 850 | 750 | 550 | 800 | 650 |
| | F _v | 95 | 90 | 70 | 90 | 70 |
| | F _{c⊥} | 385 | 280 | 190 | 405 | 280 |
| | E | 1.5 | 1.3 | 1.2 | 1.4 | 1.1 |
| | F _c | 675 | 625 | 450 | 625 | 525 |

* Table is for visually stress graded lumber only, used at 19% maximum moisture content.

† Notation used is: F_b for extreme fiber in bending (repetitive member use); F_c for compression parallel to grain; F_v for horizontal shear; $F_{c\perp}$ for compression perpendicular to grain; and E for modulus of elasticity. For dynamic uses in this report, F_b , F_c , and F_v stresses are multiplied by 2.0 to 4.

‡ F_c values in italics are for bending members only; not recommended for PSSP stringers. See SOURCE below, main report not supplement, article 4.2.2.
SOURCE: "Design Values for Wood Construction," 1980 Supplement to the 1977 Edition of National Design Specification for Wood Construction, National Forest Products Association, 1619 Massachusetts Avenue, N.W., Washington, D. C. 20006.

- Bending design stress (in extreme fiber), in repetitive-member use, F_b
- Horizontal shear design stress, F_v
- Compression perpendicular to grain design stress, F_{c1}

(2) Conversion of design stresses to dynamic values (step 2 above) is unnecessary hereunder; the chart p_{dm} includes this conversion and the chart is therefore entered directly with the design stresses for normal loading. Similarly included is the factor (5/6) for $p_{dm} = (5/6) q$ (per design steps 4 and 8 above). Increases for "flatwise" use are not included in the chart p_{dm} (see design step 2 above).

(3) For each wood and thickness, determine the blast resistance in terms of free-field overpressure:

Enter the table on the page facing Figure B1-1 and read values A and B, for each pair of values of span L (in.) and (actual, not nominal) beam depth d (in.).

Enter the left portion of Figure B1-1 with the A and B values as follows: Use A (at top of figure) with the "curves" for horizontal shear F_v values and read q_n (or p_{dm}) on left (ordinate) scale; use B (at bottom of figure) with the "curves" for bending stress F_b values and read q_n (or p_{dm}) on left scale; use only the smaller value of q_n (or p_{dm}) read!

(4) For each wood and thickness still of interest, determine the required bearing length at each end of the wood beam:

Use the F_{c1} value found above and the p_{dm} value just found, and calculate the required bearing length L' (in.) at each end of the beam, from the following modification of Eq. 5:

$$L' = 0.6 p_{dm} L / F_{c1} \quad (6)$$


but not less than 2 in. Strictly speaking, if the beam-ends in bearing are exposed to the air blast, Eq. 6 should be:

$$L' = 0.6 p_{dm} L / (F_{c1} - p_{dm}).$$

VALUES OF A AND B FOR FIGURE B1-1


| Span L (in.) | d=1.5 in. | | =2.5 in. | | =3.5 in. | | =4.5 in. | | =5.5 in. | | =7.25 in. | | =9.25 in. | | =11.25 in. | |
|-----------------|-----------|-----|----------|-----|----------|-----|----------|-----|----------|-----|-----------|-----|-----------|-----|------------|-----|
| | A | B | A | B | A | B | A | B | A | B | A | B | A | B | A | B |
| 12 | 167 | 104 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 14 | 136 | 77 | 278 | 213 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16 | 115 | 59 | 227 | 163 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18 | 100 | 46 | 192 | 129 | 318 | 252 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 20 | 88 | 38 | 167 | 104 | 269 | 204 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 22 | 79 | 31 | 147 | 86 | 233 | 169 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 24 | 71 | 26 | 132 | 72 | 206 | 142 | 300 | 234 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 26 | 65 | 22 | 119 | 62 | 184 | 121 | 265 | 200 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 28 | 60 | 19 | 109 | 53 | 167 | 104 | 237 | 172 | 324 | 257 | 0 | 0 | 0 | 0 | 0 | 0 |
| 30 | 56 | 17 | 100 | 46 | 152 | 91 | 214 | 150 | 289 | 224 | 0 | 0 | 0 | 0 | 0 | 0 |
| 32 | 52 | 15 | 93 | 41 | 140 | 80 | 195 | 132 | 262 | 197 | 0 | 0 | 0 | 0 | 0 | 0 |
| 34 | 48 | 13 | 86 | 36 | 130 | 71 | 180 | 117 | 239 | 174 | 0 | 0 | 0 | 0 | 0 | 0 |
| 36 | 45 | 12 | 81 | 32 | 121 | 63 | 167 | 104 | 220 | 156 | 0 | 0 | 0 | 0 | 0 | 0 |
| 38 | 43 | 10 | 76 | 29 | 113 | 57 | 155 | 93 | 204 | 140 | 309 | 243 | 0 | 0 | 0 | 0 |
| 40 | 41 | 9 | 71 | 26 | 106 | 51 | 145 | 84 | 190 | 126 | 284 | 219 | 0 | 0 | 0 | 0 |
| 42 | 38 | 9 | 68 | 24 | 100 | 46 | 136 | 77 | 177 | 114 | 264 | 199 | 0 | 0 | 0 | 0 |
| 44 | 37 | 8 | 64 | 22 | 95 | 42 | 129 | 70 | 167 | 104 | 246 | 181 | 0 | 0 | 0 | 0 |
| 46 | 35 | 7 | 61 | 20 | 90 | 39 | 122 | 64 | 157 | 95 | 230 | 166 | 0 | 0 | 0 | 0 |
| 48 | 33 | 7 | 58 | 18 | 85 | 35 | 115 | 59 | 149 | 88 | 216 | 152 | 314 | 248 | 0 | 0 |
| 50 | 32 | 6 | 56 | 17 | 81 | 33 | 110 | 54 | 141 | 81 | 204 | 140 | 294 | 228 | 0 | 0 |
| 52 | 31 | 6 | 53 | 15 | 78 | 30 | 105 | 50 | 134 | 75 | 193 | 130 | 276 | 211 | 0 | 0 |
| 54 | 29 | 5 | 51 | 14 | 74 | 28 | 100 | 46 | 128 | 69 | 184 | 120 | 261 | 196 | 0 | 0 |
| 56 | 28 | 5 | 49 | 13 | 71 | 25 | 96 | 43 | 122 | 64 | 175 | 112 | 247 | 182 | 0 | 0 |
| 58 | 27 | 4 | 47 | 12 | 69 | 24 | 92 | 40 | 117 | 60 | 167 | 104 | 234 | 170 | 315 | 251 |
| 60 | 26 | 4 | 45 | 12 | 66 | 23 | 88 | 38 | 112 | 56 | 159 | 97 | 223 | 158 | 300 | 234 |
| 62 | 25 | 4 | 44 | 11 | 64 | 21 | 85 | 35 | 108 | 52 | 153 | 91 | 213 | 146 | 285 | 219 |
| 64 | 25 | 4 | 42 | 10 | 61 | 20 | 82 | 33 | 104 | 49 | 146 | 86 | 203 | 139 | 271 | 206 |
| 66 | 24 | 3 | 41 | 10 | 59 | 19 | 79 | 31 | 100 | 46 | 141 | 80 | 195 | 131 | 259 | 194 |
| 68 | 23 | 3 | 40 | 9 | 57 | 18 | 76 | 29 | 95 | 44 | 136 | 76 | 187 | 123 | 247 | 182 |
| 70 | 22 | 3 | 38 | 9 | 56 | 17 | 74 | 28 | 93 | 41 | 131 | 72 | 180 | 116 | 237 | 172 |
| 72 | 22 | 3 | 37 | 8 | 54 | 16 | 71 | 26 | 90 | 39 | 126 | 68 | 173 | 110 | 227 | 163 |
| 74 | 21 | 3 | 36 | 8 | 52 | 15 | 68 | 25 | 87 | 37 | 122 | 64 | 167 | 104 | 218 | 154 |
| 76 | 21 | 3 | 35 | 7 | 51 | 14 | 67 | 23 | 85 | 35 | 118 | 61 | 161 | 99 | 210 | 146 |
| 78 | 20 | 2 | 34 | 7 | 49 | 13 | 65 | 22 | 82 | 33 | 114 | 58 | 155 | 94 | 203 | 139 |
| 80 | 19 | 2 | 33 | 7 | 48 | 13 | 63 | 21 | 80 | 32 | 111 | 55 | 150 | 89 | 196 | 132 |
| 82 | 19 | 2 | 32 | 6 | 47 | 12 | 62 | 20 | 77 | 30 | 107 | 52 | 146 | 85 | 189 | 125 |
| 84 | 19 | 2 | 32 | 6 | 45 | 12 | 60 | 19 | 75 | 28 | 104 | 50 | 141 | 81 | 183 | 120 |
| 86 | 18 | 2 | 31 | 6 | 44 | 11 | 58 | 18 | 73 | 27 | 101 | 47 | 137 | 77 | 177 | 114 |
| 88 | 18 | 2 | 30 | 5 | 43 | 11 | 57 | 17 | 71 | 26 | 99 | 45 | 133 | 74 | 172 | 109 |
| 90 | 17 | 2 | 29 | 5 | 42 | 10 | 56 | 17 | 70 | 25 | 96 | 43 | 129 | 70 | 167 | 104 |
| 92 | 17 | 2 | 29 | 5 | 41 | 10 | 54 | 16 | 68 | 24 | 94 | 41 | 126 | 67 | 162 | 100 |
| 94 | 16 | 2 | 28 | 5 | 40 | 9 | 53 | 15 | 66 | 23 | 91 | 40 | 123 | 65 | 157 | 95 |
| 96 | 16 | 2 | 27 | 5 | 39 | 9 | 52 | 15 | 65 | 22 | 89 | 38 | 119 | 62 | 153 | 92 |
| 98 | 16 | 2 | 27 | 4 | 38 | 9 | 51 | 14 | 63 | 21 | 87 | 36 | 116 | 59 | 149 | 88 |
| 100 | 15 | 2 | 26 | 4 | 38 | 8 | 49 | 13 | 62 | 20 | 85 | 35 | 113 | 57 | 145 | 84 |
| 102 | 15 | 1 | 26 | 4 | 37 | 8 | 48 | 13 | 60 | 19 | 83 | 34 | 111 | 55 | 142 | 81 |
| 104 | 15 | 1 | 25 | 4 | 36 | 8 | 47 | 12 | 59 | 19 | 81 | 32 | 108 | 53 | 138 | 78 |
| 106 | 15 | 1 | 25 | 4 | 35 | 7 | 46 | 12 | 58 | 18 | 79 | 31 | 106 | 51 | 135 | 75 |
| 108 | 14 | 1 | 24 | 4 | 35 | 7 | 45 | 12 | 57 | 17 | 78 | 30 | 103 | 49 | 132 | 72 |
| 110 | 14 | 1 | 24 | 3 | 34 | 7 | 45 | 11 | 56 | 17 | 76 | 29 | 101 | 47 | 129 | 70 |
| 112 | 14 | 1 | 23 | 3 | 33 | 7 | 44 | 11 | 54 | 16 | 74 | 28 | 99 | 45 | 126 | 67 |
| 114 | 14 | 1 | 23 | 3 | 33 | 6 | 43 | 10 | 53 | 16 | 73 | 27 | 97 | 44 | 123 | 65 |
| 116 | 13 | 1 | 23 | 3 | 32 | 6 | 42 | 10 | 52 | 15 | 71 | 26 | 95 | 42 | 120 | 63 |
| 118 | 13 | 1 | 22 | 3 | 32 | 6 | 41 | 10 | 51 | 14 | 70 | 25 | 93 | 41 | 116 | 61 |
| 120 | 13 | 1 | 22 | 3 | 31 | 6 | 41 | 9 | 50 | 14 | 69 | 24 | 91 | 40 | 115 | 59 |
| 122 | 13 | 1 | 21 | 3 | 30 | 5 | 40 | 9 | 50 | 14 | 67 | 24 | 89 | 38 | 113 | 57 |
| 124 | 12 | 1 | 21 | 3 | 30 | 5 | 39 | 9 | 49 | 13 | 66 | 23 | 88 | 37 | 111 | 55 |
| 126 | 12 | 1 | 21 | 3 | 29 | 5 | 38 | 9 | 48 | 13 | 65 | 22 | 86 | 36 | 109 | 53 |
| 128 | 12 | 1 | 20 | 3 | 29 | 5 | 38 | 8 | 47 | 12 | 64 | 21 | 84 | 35 | 107 | 51 |
| 130 | 12 | 1 | 20 | 2 | 28 | 5 | 37 | 8 | 46 | 12 | 63 | 21 | 83 | 34 | 105 | 50 |
| 132 | 12 | 1 | 20 | 2 | 28 | 5 | 37 | 8 | 45 | 12 | 62 | 20 | 81 | 33 | 103 | 48 |
| 134 | 11 | 1 | 19 | 2 | 28 | 5 | 36 | 8 | 45 | 11 | 61 | 20 | 80 | 32 | 101 | 47 |
| 136 | 11 | 1 | 19 | 2 | 27 | 4 | 35 | 7 | 44 | 11 | 60 | 19 | 79 | 31 | 99 | 46 |
| 138 | 11 | 1 | 19 | 2 | 27 | 4 | 35 | 7 | 43 | 11 | 59 | 18 | 77 | 30 | 97 | 44 |
| 140 | 11 | 1 | 19 | 2 | 26 | 4 | 34 | 7 | 43 | 10 | 58 | 18 | 76 | 29 | 96 | 43 |
| 142 | 11 | 1 | 18 | 2 | 26 | 4 | 34 | 7 | 42 | 10 | 57 | 17 | 75 | 28 | 94 | 42 |
| 144 | 11 | 1 | 18 | 2 | 26 | 4 | 33 | 7 | 41 | 10 | 56 | 17 | 74 | 28 | 93 | 41 |

In above, A = d / (L-2d) x 1000, and B = (d/L)² x (2/3) x 10000



$b = 1.5$ in

200



(5) As an illustrative example: Using Douglas Fir-Larch 2x4s (on edge, solidly side-by-side), Structural Light Framing, Stud grade, read from Tabl B1-1: F_b (repetitive-member use) is 925 psi, F_v is 140 psi, and $F_{c\perp}$ is 385 psi. Span L is 40 in. center-center of supports. Enter table facing Figure B1-1 and read: A is 106, and B is 51. Enter Figure B1-1 with A and B and read: for A of 106 and F_v of 140, q_n is 19.8 psi; for B of 51 and F_b of 925, q_n is about 9.4 psi. Thus, the q_n of 9.4⁹ psi is the smaller, and p_{dm} of 31.5 psi is the peak air blast (free field) overpressure design resistance of this solid door of 2x4s on edge (assuming that the door frame has been checked and found adequate).⁹

Required bearing length on each end of each 2x4 is calculated using Eq. 6 and $F_{c\perp}$ of 385 minus p_{dm} (assuming the blast hits the supporting ends of the 2x4s, as it usually would), or an $F_{c\perp}$ of, say, 350 psi: $L' = 0.6 \times 31.5 \times 40 / 350 = 2\text{-}1/4$ in. bearing length on each end.

(6) The above example assumes that the closure is covered with plywood (e.g., 1/4 in.). If not: use F_b for single-member use [1, Table 4A, third column]; use a stress multiple of 2.6 (not 4),¹⁰ use a μ of 1.5 (with same step pulse); and, therefore, read q_n (not p_{dm}) when using Figure B1-1, and calculate $p_{dm} = 2.6 (2/3) q_n = 1.73 q_n$. Thus, the single-member use applied to the above illustrative example changes the resulting p_{dm} from 31.5 psi to $p_{dm} = 1.73 q_n = 1.73 \times 9.4 = 16.3$ psi.

b. The chart approach is as follows when using beams spaced as in floor stringers (chart is only for beam widths b of 1.5 and 3.5 in., each spaced at 12, 16 and 24 in. center-center):

Using the same wood beams, span L (40 in.), F_v of 140 psi, A of 106, B of 51, and $F_{c\perp}$ of 385 psi as in the illustrative example above, find F_b (single-member use) of 800 psi [1, Supplement, Table 4A]; enter Figure B1-1 as before and read q_n values (q_n of 19.8 from A of 106 and F_v of 140; q_n of 8.2 from B of 51 and F_b of 800) of which 8.2 psi is the lower. The q_n value is stated only for illustration; the reader/user should move to the right from finding the intersection of B and F_b values - finding that the total load TL in pounds per square foot of covering (in normal use) over the spaced wood beams is: 150 psf TL for beam width b of 1.5 in. and spacing j of 12 in.; 113 psf for 16 in. spacing; and 75 psf for 24 in. spacing.

⁹ The increase factor from q_n to p_{dm} is 3.333. It represents a 100% increase for short duration (impact) loading [1, sec. 2.2.5.3], another 100% increase to use up the assumed factor of safety for repetitive-member use (reader/user may want to reduce this to 30% by hand calculation, if no regrading has been done), and a reduction by (5/6) for using $\mu = 3$ (reader/user may also want to reduce this by hand calculation); thus, the overall factor is $2 \times 2 (5/6) = 3.333 \dots$, or $p_{dm} = 3.333 q_n$.

¹⁰ Representing increases of 100% for short duration (impact) loading and 30% for factor of safety in single-member use.

These normal-use design TL values can be corrected for air blast loading by use of a multiple of 1.73 (as in paragraph (C) just above), giving 260, 195, and 130 psf for spacings of 12, 16, and 24 in., respectively, as calculated, or such results may be read directly from the outer (top and bottom) scales of the right graph, Figure B1-1.

C. Support Conditions Other Than Single-Span Simply Supported (SS)

The foregoing deals with single-span beams, on simple (non-moment carrying) supports (SS). For two-equal-span beams on simple supports (PC), formulas for one span (of the two) are on pages B2-20 and -21, Appendix B2, using constants for PC. (The formulas for FF conditions are of little interest to the upgrading sizing herein.)

If the contemplated wood beam use involves one beam extending over more than a single span: find q_{nv} and q_{nb} for a single-span beam as before (i.e., from A-F_v and B-F_b, respectively); find related p_{dmv} and p_{dmb} ; and find related TL_v and TL_b. Correct these values for multiple-span beams (with all simple supports) as follows [9,p.5-41]:

| | <u>2-span</u> | <u>3-span</u> | <u>4-span</u> | <u>5-span</u> |
|---|---------------|---------------|---------------|---------------|
| q_n , p_{dm} , and TL with subscript b: | 1.000 | 1.250 | 1.168 | 1.190 |
| q_n , p_{dm} , and TL with subscript v: | 0.800 | 0.833 | 0.824 | 0.836 |

Use the lower value of each: q_n , p_{dm} , and TL.

Wood Columns - Simple Supports

The wood columns contemplated in this design section have square ends and receive/deliver loads through well-fitted joints (not fixed). (Such conditions are sometimes called pin-ended.) The columns may or may not have intermediate supports.

Much of the guidance about wood and the wood beam design approach (both as presented in the preceding section on wood beams) apply to column design. Accordingly, the column design procedure that follows is considerably abbreviated, as compared to the beam design section, and depends a lot on an illustrative example.

A. Design Procedure

a. Column (normal-use) design formulas are shown in Table B1-3. Note the sketch and use of two different L/d ratios where there is an intermediate support for the weak direction; per Eq. 7, only the larger L/d value is used further. Use the table facing Fig. B1-2A to get each needed L/d value; enter the table with span L and depth d (both d_1 and d_2 of the sketch in Table B1-3 are termed "depth" - call them larger and smaller d 's, and similar for the L 's); read the L/d value. The sketch of Table B1-3 actually shows a part-column with two sets of intermediate supports; if only the weaker direction has intermediate support, L_2 is the end-to-end column length. If the (larger) design L/d value is greater than 50, the selected member and/or its lateral supports is/are inadequate; change member or supports.


Determine the modulus of elasticity E and the design value for compression stress parallel to grain F_c for the wood member selected (1, Supplement, Table 4A); regrading is urged (time permitting), just as it was for wood beams.

Using Figure B1-2A, enter graph 1 with the F_c value; go up to the appropriate E value (or interpolate vertically between the two curves bracketing the E value), then right to read a value for K (on scale between graphs 1 and 2). If the design L/d value is less than or equal to K , continue to the right until hitting the appropriate L/d curve (or interpolate horizontally between L/d curves); using the same F_c (as used with graph 1) go vertically to the F_c line of graph 3 (or interpolate vertically); then go horizontally to the graph 4 line representing the nominal (actual) column dimensions; finally, go vertically to read P and P_d .

The final P found comes from use of Eq. 13. For P_d , multiples of 2 on F_c for short duration (impact) loading, and 1.3 for a 30% factor of safety, are reduced by a factor of 0.5 from using a μ of 1; thus P_d equals $(2 \times 1.3 \times 0.5)$ or 1.3 times P .

Table B1-3

COLUMN FORMULAS - SIMPLE SOLID COLUMN DESIGN [3]
(Pin-ended conditions assumed)



For conditions shown in the sketch:

Use larger of L_1 / d_1 and L_2 / d_2 as the L / d for design (7)

Slenderness ratio L / d must be ≤ 50 (8)

For $L / d \leq 11$: $F'_c = F_c$ (9)

For $L / d > 11$, but $\leq K$:

$$K = 0.671 \sqrt{E / F_c} \quad (10)$$

$$F'_c = F_c (1 - 1/3 (L / dK)^4) \quad (11)$$

$$\text{For } L / d \geq K: F'_c = 0.3E / (L / d)^2 \quad (12)$$

$$P = AF'_c = bdF'_c \quad (13)$$

L / d VALUES FOR FIGURE B1-2

| L (in.) | d (in.) | | | | | | | |
|---------|---------|------|------|------|------|------|------|-------|
| | 1.5 | 2.5 | 3.5 | 4.5 | 5.5 | 7.25 | 9.25 | 11.25 |
| 18 | 12.0 | 7.2 | 5.1 | 4.0 | 3.3 | 2.5 | 1.9 | 1.6 |
| 20 | 13.3 | 8.0 | 5.7 | 4.4 | 3.6 | 2.8 | 2.2 | 1.8 |
| 22 | 14.7 | 8.8 | 6.3 | 4.9 | 4.0 | 3.0 | 2.4 | 2.0 |
| 24 | 16.0 | 9.6 | 6.9 | 5.3 | 4.4 | 3.3 | 2.6 | 2.1 |
| 26 | 17.3 | 10.4 | 7.4 | 5.8 | 4.7 | 3.6 | 2.8 | 2.3 |
| 28 | 18.7 | 11.2 | 8.0 | 6.2 | 5.1 | 3.9 | 3.0 | 2.5 |
| 30 | 20.0 | 12.0 | 8.6 | 6.7 | 5.5 | 4.1 | 3.2 | 2.7 |
| 32 | 21.3 | 12.8 | 9.1 | 7.1 | 5.8 | 4.4 | 3.5 | 2.8 |
| 34 | 22.7 | 13.6 | 9.7 | 7.6 | 6.2 | 4.7 | 3.7 | 3.0 |
| 36 | 24.0 | 14.4 | 10.3 | 8.0 | 6.5 | 5.0 | 3.9 | 3.2 |
| 38 | 25.3 | 15.2 | 10.9 | 8.4 | 6.9 | 5.2 | 4.1 | 3.4 |
| 40 | 26.7 | 16.0 | 11.4 | 8.9 | 7.3 | 5.5 | 4.3 | 3.6 |
| 42 | 28.0 | 16.8 | 12.0 | 9.3 | 7.6 | 5.8 | 4.5 | 3.7 |
| 44 | 29.3 | 17.6 | 12.6 | 9.8 | 8.0 | 6.1 | 4.8 | 3.9 |
| 46 | 30.7 | 18.4 | 13.1 | 10.2 | 8.4 | 6.3 | 5.0 | 4.1 |
| 48 | 32.0 | 19.2 | 13.7 | 10.7 | 8.7 | 6.6 | 5.2 | 4.3 |
| 50 | 33.3 | 20.0 | 14.3 | 11.1 | 9.1 | 6.9 | 5.4 | 4.4 |
| 52 | 34.7 | 20.8 | 14.9 | 11.6 | 9.5 | 7.2 | 5.6 | 4.6 |
| 54 | 36.0 | 21.6 | 15.4 | 12.0 | 9.8 | 7.4 | 5.8 | 4.8 |
| 56 | 37.3 | 22.4 | 16.0 | 12.4 | 10.2 | 7.7 | 6.1 | 5.0 |
| 58 | 38.7 | 23.2 | 16.6 | 12.9 | 10.5 | 8.0 | 6.3 | 5.2 |
| 60 | 40.0 | 24.0 | 17.1 | 13.3 | 10.9 | 8.3 | 6.5 | 5.3 |
| 62 | 41.3 | 24.8 | 17.7 | 13.8 | 11.3 | 8.6 | 6.7 | 5.5 |
| 64 | 42.7 | 25.6 | 18.3 | 14.2 | 11.6 | 8.8 | 6.9 | 5.7 |
| 66 | 44.0 | 26.4 | 18.9 | 14.7 | 12.0 | 9.1 | 7.1 | 5.9 |
| 68 | 45.3 | 27.2 | 19.4 | 15.1 | 12.4 | 9.4 | 7.4 | 6.0 |
| 70 | 46.7 | 28.0 | 20.0 | 15.6 | 12.7 | 9.7 | 7.6 | 6.2 |
| 72 | 48.0 | 28.8 | 20.6 | 16.0 | 13.1 | 9.9 | 7.8 | 6.4 |
| 74 | 49.3 | 29.6 | 21.1 | 16.4 | 13.5 | 10.2 | 8.0 | 6.6 |
| 76 | 50.7 | 30.4 | 21.7 | 16.9 | 13.8 | 10.5 | 8.2 | 6.8 |
| 78 | 52.0 | 31.2 | 22.3 | 17.3 | 14.2 | 10.8 | 8.4 | 6.9 |
| 80 | 53.3 | 32.0 | 22.9 | 17.8 | 14.5 | 11.0 | 8.6 | 7.1 |
| 82 | 54.7 | 32.8 | 23.4 | 18.2 | 14.9 | 11.3 | 8.9 | 7.3 |
| 84 | 56.0 | 33.6 | 24.0 | 18.7 | 15.3 | 11.6 | 9.1 | 7.5 |
| 86 | 57.3 | 34.4 | 24.6 | 19.1 | 15.6 | 11.9 | 9.3 | 7.6 |
| 88 | 58.7 | 35.2 | 25.1 | 19.6 | 16.0 | 12.1 | 9.5 | 7.8 |
| 90 | 60.0 | 36.0 | 25.7 | 20.0 | 16.4 | 12.4 | 9.7 | 8.0 |
| 92 | 61.3 | 36.8 | 26.3 | 20.4 | 16.7 | 12.7 | 9.9 | 8.2 |
| 94 | 62.7 | 37.6 | 26.9 | 20.9 | 17.1 | 13.0 | 10.2 | 8.4 |
| 96 | 64.0 | 38.4 | 27.4 | 21.3 | 17.5 | 13.2 | 10.4 | 8.5 |
| 98 | 65.3 | 39.2 | 28.0 | 21.8 | 17.8 | 13.5 | 10.6 | 8.7 |
| 100 | 66.7 | 40.0 | 28.6 | 22.2 | 18.2 | 13.8 | 10.8 | 8.9 |
| 102 | 68.0 | 40.8 | 29.1 | 22.7 | 18.5 | 14.1 | 11.0 | 9.1 |
| 104 | 69.3 | 41.6 | 29.7 | 23.1 | 18.9 | 14.3 | 11.2 | 9.2 |
| 106 | 70.7 | 42.4 | 30.3 | 23.6 | 19.3 | 14.6 | 11.5 | 9.4 |
| 108 | 72.0 | 43.2 | 30.9 | 24.0 | 19.6 | 14.9 | 11.7 | 9.6 |
| 110 | 73.3 | 44.0 | 31.4 | 24.4 | 20.0 | 15.2 | 11.9 | 9.8 |







Figure B1-2A
COLUMN DESIGN, WOOD





PRECEDING PAGE BLANK-NOT FILLED




Figure B1-2B

B1-21

b. Use of the 1.3 multiple is recommended only if regrading is done. If not, it is recommended that P_d be taken as equal to P , thus leaving intact the 30% factor of safety to cover grading errors and/or buckling hazards.

See page B2-29, Appendix B2, for a calculations example of handling combined (fallout shielding) soil loads and blast loads. (There are deliberate but minor differences in some of the details, between Appendices B1 and B2, which are attributable to the general nature of B1 versus the more specific nature of B2 (here basement shelter for fallout and only low blast levels.)

c. For checking adequacy of designed columns in terms of their end bearing, and also for some comments on sill or bottom plate or blocking "design," see section "C. End Bearing and Sill/Bottom Plate Design," below.

B. Numerical Example - Design Using Figure B1-2

As an illustrative example: assume 2x4s are to be checked for their blast capacity in use as upgrading columns; Idaho White Pine is available, for which F_c is 650 psi and E is 1.2 million psi in Standard grade [1, Supplement, p. 11; or table on p. B2-16, Appendix B2]; column height L (L is also used in this section) is 96 in. Using table facing Figure B1-2A, L/d values are 64 for narrow (weaker) direction (d is 1.5 in.) and 27.4 for wide (stronger) direction (d is 3.5 in.); the larger L/d of 64 controls (Eq. 7). According to Eq. 8, this column is unusable (buckling hazard is too great).

The 2x4s can be used if supported at mid-height, in the weak direction, which is one alternative; however, let's take the other, that is, use a larger column by assuming that 4x4s are to be checked instead (normally, such a great increase would not be called for unless the designer is way off in his first guess, but poetic licence is taken here in order to demonstrate the two things that can happen in using Figure B1-2). Values for F_c and E are unchanged; L/d is 27.4 as before. Entering B1-2A with F_c of 650 and E of 1.2 million, read K as 29; since L/d is less than K , continue horizontally, interpolating horizontally between curves for L/d of 28 and 26, that is about 3/4 of the way from the 26 to the 28 curve ($1.4/2 \approx 3/4$); go vertically from this interpolated point (about on 0.73 of bottom scale) to F_c of 650 in graph 3; then horizontally (along about the F'_c of 470 line) to the specific line for 4x4 (3.5x3.5) in graph 4 (no interpolating in this area!); then vertically to read P as 5.8 kips (5,800 pounds) and P_d as about 7.5 kips (7,500 pounds). (From calculations on page B2-28, Appendix B2: L/d is 27.43; K is 28.83; F'_c is 472, thus F'_c/F_c for bottom scale is 0.726; P is 5,782, from which P_d is 7,517.)¹¹

¹¹ Numerical results are shown to illustrate the work, not to imply a degree of accuracy in design/analysis.

Now, assuming that the wood and grade are Douglas Fir-Larch and Construction, find F_c of 1,150 psi and E of 1.5 million psi from same sources as before. Using Figure B1-2A, graph 1 (interpolate vertically between E curves), find K as 24, meaning that L/d of 27.4 is greater than K , and Figure B1-2B must be used (instead of graphs 2 and 3 of B1-2A). Using B1-2B, enter with L/d of 27.4 and E of 1.5 million, read F'_c as 595; using graph 4 of B1-2A, enter with F'_c of 595 and read (for 4x4s) P of 7.3 kips (7,300 pounds) and P_d of 9.5 kips (9,500 pounds). (Again, from calculations on page B2-28, Appendix B2: L/d is 27.43 as before; K is 24.23; F'_c is 598; P is 7,327, from which P_d is 9,525.)

C. End Bearing and Sill/Bottom Plate Design

a. Adequacy of columns for end grain in bearing (top and bottom) should be checked. The method can be shown by example, using the two columns in the numerical example of the preceding section: Table B1-4 (fourth column) shows the design value for end bearing F_g for 4x4s as 1,390 psi for the Idaho White Pine and as 2,020 psi for the Douglas Fir-Larch. With the 4x4 (3.5x3.5) end area of 12.25 in.², the two example columns have end bearing capacities of 17,028 and 24,745 pounds if bearing is through metal plates, and 12,771 and 18,559 pounds if on less rigid materials (wood, concrete, etc.); see the comment along the bottom of Table B1-4. With the two example columns blast capacities P_d of 7,500 and 9,500 pounds, there is ample end bearing capacity even under the 75% limitation. Further, the design values F_g of Table B1-4 are subject to duration of loading factors [1, Sec. 2.2.5.3]: increase the F_g values by 15% for loads of 2 months or less (as with fallout-shielding soil), and 100% for impact loads (such as air blast)! Thus, column adequacy for end grain in bearing might be concluded to be generally of no concern; nonetheless the checks should be made.

b. Sill or bottom plate "design" could be complex, involving as it does a beam with concentrated loads (the columns, plus foot plates if any) and supported by an elastic/plastic/fracturing foundation (the usual light, concrete floor slab). Such design is considered unwarranted for the purposes herein. It should be accepted that the floor slab will crack/break up and will be pushed down, under and adjacent to the bottom plate, should the upgraded floor system over the basement receive an air blast overpressure loading; such action absorbs energy. Recent tests indicate a very high floor slab resistance to column punching from blast duration loads (see page 18 of main text).

For the added loading of soil placed on the first floor for fallout shielding upgrading, it is doubted that the concrete basement floor will experience anything more than localized cracking, if that, under the following approach:

Table B1-4

END GRAIN IN BEARING (psi)

Design values for end grain not bearing parallel to grain on a rigid surface F_g
in pounds per square inch

| Species | Wet service conditions ¹ | Dry service conditions ¹ | | Glued laminated timber |
|---|-------------------------------------|-------------------------------------|------------------------|------------------------|
| | | Sawn lumber ² | | |
| | | More than 4" thick | Not more than 4" thick | |
| Ash - White | 1370 | 1510 | 2060 | 2400 |
| Alder | 400 | 820 | 1110 | 1300 |
| Bald Cypress | 890 | 980 | 1330 | 1560 |
| Birch | 1340 | 1310 | 1780 | 2080 |
| Brown Sweetgum | 1350 | 1260 | 1720 | 2010 |
| Black - Walnut | 620 | 690 | 930 | 1090 |
| Black - Hardwood - Virginia | 1560 | 1720 | 2270 | 2620 |
| Black - Hardwood - Spruce | 1310 | 1270 | 1670 | 1940 |
| Black - Spruce | 950 | 1040 | 1420 | 1660 |
| Black - Spruce | 950 | 1040 | 1420 | 1660 |
| Black - Wood - Maple | 765 | 840 | 1150 | 1340 |
| Chinquapin - Green - Gliese ⁴ | 1570 | 1730 | 2360 | 2750 |
| Chinquapin - Green ⁴ | 1340 | 1480 | 2020 | 2350 |
| Chinquapin - Spruce | 1220 | 1340 | 1820 | 2130 |
| Eastern - Hemlock - Tamarack ⁴ | 1150 | 1270 | 1730 | 2020 |
| Eastern - Spruce | 970 | 1070 | 1460 | 1700 |
| Eastern - White Pine ⁴ | 900 | 1000 | 1360 | 1580 |
| Eastern - Woods | 820 | 900 | 1230 | 1440 |
| Engelmann Spruce - Alpine for | 810 | 890 | 1220 | 1420 |
| Engelmann ⁴ | 1110 | 1220 | 1670 | 1940 |
| Hickory - Hard - Pecan | 1370 | 1510 | 2050 | 2400 |
| Hickory - White Pine | 930 | 1020 | 1390 | 1630 |
| Hickory - Pine | 970 | 1060 | 1450 | 1690 |
| Maple - Black and Sugar | 1140 | 1250 | 1710 | 2000 |
| Maple - Hard - Oak | 1070 | 1170 | 1600 | 1870 |
| Norfolk - Alder | 740 | 810 | 1110 | 1290 |
| Norfolk - Pine | 1040 | 1150 | 1570 | 1830 |
| Norfolk - Spruce | 880 | 970 | 1320 | 1540 |
| Norfolk - White Pine | 740 | 810 | 1110 | 1290 |
| Norfolk - White Pine | 1050 | 1160 | 1590 | 1850 |
| Pine - White - Spruce - Pine | 910 | 1000 | 1370 | 1600 |
| Pine | 880 | 970 | 1320 | 1540 |
| Pine - Spruce | 940 | 1030 | 1480 | 1730 |
| Pine - Spruce | 1110 | 1200 | 1650 | 2320 |
| Pine - Spruce - Pine | 1040 | 1130 | 1580 | 2690 |
| Pine - Spruce | 1120 | 1210 | 1660 | 2300 |
| Pine - Spruce - Pine | 1140 | 1230 | 1680 | 1650 |
| Pine - Spruce - Pine | 1160 | 1250 | 1700 | 1780 |
| Pine - Spruce - Pine | 1180 | 1270 | 1720 | 1750 |
| Pine - Spruce - Pine | 1200 | 1290 | 1740 | 2170 |
| White - Alder | 430 | 700 | 1400 | 1630 |
| White - Alder - White - Alder | 870 | 890 | 1220 | 1420 |
| White - Alder - White - Alder | 870 | 890 | 1220 | 1420 |
| White - Alder - White - Alder | 890 | 890 | 1340 | 1560 |

Author's address: Department of Mathematics, University of California, San Diego, 950 University Avenue, San Diego, CA 92093, USA. E-mail: shrawan@ucsd.edu

For example, the fact that a person is a member of a particular group does not, *ex se*, entitle her to a particular right or duty, regardless of her other characteristics.

For the first time, we have shown that the observed increase in the number of high-grade metastases is not a result of a selection of a subset of metastases.

1. The first step is to identify the key components of the system. This involves understanding the hardware, software, and data involved in the process.

Source: National Design Specification for Wood Construction, 1977 Edition, National Forest Products Association, 1619 Massachusetts Avenue, N. W., Washington, D. C. 20005, art. 2.4, Table 2A.

Author comments: When stress in end-grain bearing exceeds 75% of above values, bearing shall be on a metal plate or strap, or on other durable, rigid, homogeneous material of adequate strength, per Source. (This criterion should be applied to both top and bottom ends of each stud or post.)

Use a bottom plate consisting of stress-graded selected dimension lumber (better than, say, utility grade), used flatwise, "2x" and at least as wide as the greater dimension of the columns (preferably wider) for a column spacing of 12 in. to 24 in.


For greater column spacings, use any blocking available under each column flatwise and perhaps stacked, preferably with the bottom block wider than just prescribed for a single member bottom plate.

For column spacings of, say, 4 ft or more, one should leave off thinking of a continuous bottom plate as the column spacing grows larger and take recourse in use of a grillage under each column; the basic premise is to spread the load on the floor slab and underlying soil.

Peak Air Blast Resistance Capacity - Side-on versus Head-on

Peak applied air blast pressure resistance capacity (psi), determined above for the particular applied situation (with its design stresses from the grading association), was just that, as felt by the structure member. If the member is used so that the blast wave strikes it head-on, e.g., as if the member is part of the front wall of a building struck by the blast wave, then the blast wave is fully reflected, making it equivalent in loading force to a much stronger wave applied only side-on. To relate these two situations by putting both in terms of air blast peak free-field overpressure resistance (that is, out in the open, unaffected by structures), use the scales below:

FREE-FIELD OVERPRESSURE (WHEN APPLIED SIDE-ON)



FREE-FIELD OVERPRESSURE (WHEN APPLIED HEAD-ON OR FULLY REFLECTED)

For example, a free-field overpressure of 45 psi hitting the member side-on gives the same peak loading to the member as a free-field overpressure of 16 psi hitting the member head-on/fully reflected.

NOTATION

- A = area of beam cross-section (in.²)
- b = width of beam (in.)
- C_d = drag coefficient (= ratio of drag pressure on object to dynamic/wind pressure in free field)
- c, c' = dimensionless coefficients
- d = depth of wood beam (in.)
- d = for columns, see figure in Table B1-3 (in.)
- F_b = extreme fiber stress in bending (psi)
- F_{db} = dynamic F_b (psi)
- F_c = compression stress parallel to grain (psi)
- F_c' = F_c corrected for buckling hazard (psi)
- F_{c1} = compression stress perpendicular to grain, or bearing stress (psi)
- F_{dc1} = dynamic F_{c1} (psi)
- F_v = horizontal shear stress (in wood) (psi)
- F_{dv} = dynamic F_v (psi)
- K = column slenderness ratio; see Table B1-3
- L = span length of beam (center-center of supports unless otherwise indicated) (in.)
- L = column overall length or unsupported length (see Table B1-3) (in.)
- L' = bearing length at each end of wood beam (in.)
- M = bending moment (in.-lb)
- P = total load (TL) column load capacity (normal use) (lb)
- P_d = total load (TL) column load blast capacity (lb)
- P_{dm} = peak (unit) value of applied (air blast) loading (psi)
- P_r = peak reflected (air blast) overpressure (psi)

NOTATION (concluded)

p_{so} = peak side-on (air blast) overpressure (psi)

q = resistance of member, ultimate (psi)

q_b = bending q (psi)

q_n = resistance under normal use design (psi)

q_v = horizontal shear q (psi)

S = section modulus (in.³)

U = shock velocity (air blast) (fps)

V = vertical shear (lb)

w = load per unit length of beam (psf)

μ = ductility ratio (of maximum deflection to yield deflection)

REFERENCES

1. National Design Specification for Wood Construction, 1977 Edition, National Forest Products Association, 1619 Massachusetts Avenue, N.W., Washington, D.C., 20036, with 1980 supplement, Design Values for Wood Construction.
2. Timber Construction Manual, 2nd Edition, American Institute of Timber Construction, Englewood, Colorado, 1974 (or later edition).
3. Wood Handbook, U. S. Forest Products Laboratory, 1974; Supt. of Documents, Washington, D.C. 20402.
4. Glasstone, S., and P. J. Dolan, The Effects of Nuclear Weapons, 3rd Edition, U. S. Departments of Defense and Energy, 1977.
5. Newmark, N. M., Design of Openings for Buried Shelters, Report 2-67, U. S. Army Engineer Waterways Experiment Station, Vicksburg, Miss., July 1963.
6. Discussions with project consultant, Professor W. J. Hall, University of Illinois.
7. Newmark, N. M., "A Method of Computation for Structural Dynamics," Journal of the Engineering Mechanics Division, American Society of Civil Engineers, Proc. Paper 2094, July 1959; also ASCE Transactions, Vol. 127, Part I, Paper No. 3384, 1962.
8. Murphy, H. L., Upgrading Basements for Combined Nuclear Weapons Effects: Predesigned Expedient Options, Stanford Research Institute¹² Technical Report, for U. S. Defense Civil Preparedness Agency,¹³ October 1977. (AD-A054 409)
9. Eshbach, O. W., Handbook of Engineering Fundamentals, 2nd edition, (Wiley), 1952.

¹² Now SRI International.

¹³ Now Federal Emergency Management Agency

Appendix B2

HOME BASEMENTS UPGRADING IN HOST AREAS

CONTENTS

| | |
|---|-------|
| Introduction | B2-1 |
| Design/Analysis Annex Work | B2-3 |
| Applications | B2-5 |
| ANNEX | B2-16 |
| WOOD BEAM DESIGN FORMULAS - UNIFORMLY DISTRIBUTED LOADS | B2-20 |
| COLUMN FORMULAS - SIMPLE SOLID COLUMN DESIGN | B2-22 |
| NOTATION | B2-31 |
| REFERENCES | B2-35 |

TABLES

| | | |
|------|---|-------|
| B2-1 | TOP BEAM CAPACITIES | B2-6 |
| B2-2 | COLUMN CAPACITIES | B2-7 |
| B2-3 | ALLOWABLE SPANS FOR FLOOR JOISTS | B2-11 |
| B2-4 | JOIST DIMENSIONS - WIDTH x DEPTH (in.) | B2-11 |
| B2-5 | END GRAIN IN BEARING (psi) | B2-15 |
| B2-6 | ALLOWABLE HORIZONTAL SHEAR VALUES F_v (psi) | B2-19 |

FIGURE

| | | |
|------|----------------------------------|------|
| B2-1 | FLOOR JOISTS UPGRADING | B2-8 |
|------|----------------------------------|------|

Appendix B2

HOME BASEMENTS UPGRADING IN HOST AREAS¹

Introduction

With the advent of CRP (Crisis Relocation Planning) there is considerable interest in upgrading the floor over host area basements, in order that mass may be added to that floor (commonly soil over a sheet of plastic film) for fallout protection, perhaps even upgraded enough for say, 2 or 3 psi peak air blast overpressure protection, in addition to the added soil for fallout protection.

Commonly such floors are of wood subflooring (and often with wood finish flooring); carried by wood joists (with cross-bridging or blocking); in turn carried on the outer basement walls and a steel beam on a pipe column(s) running along the long-direction centerline of the basement. The pipe column(s) are supported on some kind of footing to spread the load, or infrequently on piling.

The prescribed floor live loading for a residential dwelling first floor is, and has been, 40 psf (pounds per square foot) [1(p.5-222)]² under usual allowable design stresses [1,2].

All wood members that are depended upon (designed) to carry specified or calculated loads must be stress-graded by species and type of member, which data can in turn be used to look up allowable design stresses [2].

The discussion herein is for a "typical" basement, that is, one containing as many commonly-used features as possible; variations are many!

To discuss each of the structural elements just mentioned:

(1) The flooring must be not only strong enough for the 40 psf design live load plus the dead load of the flooring, both uniformly distributed loads, but also strong enough to carry safely (to the joists) the intermittent concentrated loads, such as that from heavy household

¹ Support for preparation of this appendix was provided under FEMA contracts with the Center for Planning and Research, Inc., Palo Alto, California and SRI International, Menlo Park, California.

² Brackets are used herein to indicate sources in the References list at the end of this appendix.

appliances. The result is that the flooring, considered by itself, is stronger than enough to handle the uniformly distributed dead load and 40 psf design live load.

(2) The floor joists - say, 2x6 or deeper,³ and blocked or cross-bridged to prevent twisting along their bottom edges - are supported on an outer basement wall (along the long side of the basement, so that joist spans are in the shorter dimension of a rectangular house or of a rectangular portion of a larger house). Each floor joist is supported also on the steel beam discussed further below, and seldom if ever does one continuous wood joist run from one outer basement wall to the other but most often consists of two joists nailed together (for erection purposes, not flexural continuity) over the steel beam. Floor joists are used at intervals of 12 in. or 16 in. (rarely at 24 in.), measured center-to-center. Joist design must also consider (as prescribed by local building code) concentrated live loads, but the uniformly distributed 40 psf live load (also prescribed) usually controls design because of the ability of the joist blocking or cross-bridging to distribute concentrated and other loads to adjoining joists. In fact, the joists (and the flooring materials directly supporting loads) may be totally prescribed by the local building code, thus requiring no design work except perhaps for prudent checking.

(3) The supporting steel beam⁴ for the floor joists, and its pipe⁵ column(s) and footing(s):

(a) May carry only its share of the first floor live (40 psf) and dead (weight of materials built into the building) loads;

(b) More likely, however, the steel beam will carry directly above it an interior bearing partition that in turn carries half of the total ceiling load and attic load (latter, if habitable, 30 psf live load; uninhabitable, 20 psf [1]); and,

(c) Half the roof dead and live loads (latter is 20 to 100 or more psf, per local building code) are sometimes carried by an attic bearing partition (or row of columns) through the first floor bearing partition to the supporting steel beam under the first floor.

³ Nominal dimensions; actual (finished) dimensions are smaller, i.e., a 2x6 is 1½ in. x 5½ in. (current) or 1-5/8 in. x 5½ in. (formerly).

⁴ What is described herein as a supporting steel beam may be, instead, a built-up or solid wood beam, but such substitution has little effect on the discussion in and purpose of this report.

⁵ The most common support; however, another steel shape or a wood member(s) may be used.

Returning to the general discussion: A floor system, especially one with wood flooring and joists, is designed to meet both deflection and strength limits, with deflection often the controlling criterion (one dislikes walking on a springy floor, regardless of repeated assurances that it is safe). What this means, however, is that the floor is actually stronger than it needs to be TO CARRY LOADS, that is, to carry more than the prescribed design live and dead loads and still remain within safe design stresses. Further, the allowable stresses have built-in factors of safety that are reduced for unusual loads such as those from wind and earthquake, so can certainly be exploited for such an emergency need as supplementing the building's fallout and low level air blast protection. Finally, actual live loads expected to occur are usually less than prescribed (code) live loads described earlier; for example, a residential basement converted to a fallout shelter by adding soil a foot or so deep on the first floor is not apt also to have its usual live loads (people and furniture) to consider, certainly not to normal use levels.

Design/Analysis Annex Work

The Annex shows an analysis of an assumed floor joist system (2x8s on 16 in. centers) in its usual and an upgraded situation (support added at mid-span). Other supporting work included the design of top beams to transfer loads from the joists to columns spaced to carry $1\frac{1}{2}$ joists per column, and the design/analysis of several potential column sizes. The work and results are described in more detail for each member type in the following paragraphs.

(1) Annex sheets provide:

(a) Notation used.

(b) A tabulation of design stresses for one lower and one higher strength, widely available, wood species of two grades each, the latter to cover Dimension Lumber of two sizes: 2 in. to 4 in. thick, 4 in. wide; and 2 in. to 4 in. thick, 5 in. and wider.

(c) A set of wood beam design formulas for uniformly distributed loads: flexure; horizontal shear; end bearing length required; and, deflection limits as prescribed by building codes.

(d) A set of column design formulas.

(2) Another sheet (Usual Floor Joist Design) uses the above design formulas and allowable stresses to develop the allowable clear span for 2x8s on 16-in. centers, when using the lower and higher strength woods described above. Allowable spans (center-center of supports) proved to be 11 ft and 13 ft 4 in. for lower and higher strengths, respectively. The work uses a live load of 40 psf and a dead load of 10 psf.

But concern here is for host area shelter (see lower portion of the Annex sheet):

First, the deflection criteria may be ignored without hazard to the structure, which in this example increases the allowable live load for the higher strength wood (keeping the span unchanged);

Second, fallout shielding soil loads might be assumed as applied for two months or less, for which the design code allows an increase of 15 percent in live load;

Third, air blast loads only are impact live loads, for which the code allows a 100 percent increase (not additive to the above 15 percent!) in live load, to which one might add a 30 percent increase representing the current estimated factor of safety in wood grading (at 5 percent risk probability); and,

Fourth, combined shielding soil and air blast live loads may be handled as shown on the Annex sheet.

The approach leaves the residential basement undamaged by fallout protection, but risks damage if an attack occurs. The last admonition on the sheet, "re-check adequacy of end bearings," may be met by using Equations 10-12 on the Annex sheet, Wood Beam Design Formulas.

Dynamic factors for air blast are ignored in this appendix, because it is felt that a home getting less than, say, 5 psi air blast peak free field loading will feel an interior air blast pulse with a rise time long enough to make the effect no worse than that from a softly applied static load of short duration.

(3) The next Annex sheet begins the design work by assuming that these 2x8 joists on 16-in. centers have added mid-span supports installed for upgrading; thus the same lower and higher strength joists have their spans changed to 5 ft 6 in. and 6 ft 8 in. (both center to center), respectively. Deflection criteria are NOT used for the emergency purposes contemplated by upgrading work.

The sheet shows the design calculations and results: fallout soil (assuming 100 pcf) shielding capacity alone of soil 26.4 in. thick and 29.4 in. thick, for lower and higher strength woods, respectively; and, an example combined protection capacity of 12 in. deep soil (assuming 95 pcf), plus 1.96 psi and 2.36 psi blast overpressure (long duration), with the technique shown so that other combinations of fallout and blast protection may be calculated. Required bearing lengths are also shown on the sheet.

The adequacy of the flooring materials, to support these new total loads, was assumed to be sufficient for the reason stated in paragraph 1 of the Introduction. Such adequacy should be checked, of course; the approach for the flooring materials is the same as for any wood beam examined with the use of the Annex sheet on beam formulas.

(4) The work included the design of top beams (3 sheets), showing those with capacities of interest for joist loads of the range encountered above. Results⁶ of the top beam designs are shown in Table B2-1. Top beam capacities shown exclude the allowable stress increases (15 and 100 percent) for short duration loads discussed above under floor joist design; similar increases apply to top beams.

(5) The work also covered examination of various sizes of columns (3 sheets) for their load capacity, with the rectangular, non-square sizes also checked for capacity where mid-height supports (and at third-points in some cases) in the weak direction have been added. Results are shown in Table B2-2.

Figure B2-1 shows schemes for floor joists upgrading: one with wood posts at a spacing of $1\frac{1}{2}$ floor joists per post, with top beams to transfer joist loads to the posts; the other with a stud directly under each joist and using a top (or tie) plate to prevent twisting of the bottom edges of the joists. The top (or tie) plate may be unneeded if the joists have adequate blocking or cross-bridging (and each joist bottom edge has enough bearing area for the top of a stud).

Applications

Obviously, if one could go into a house and identify fully the wood floor joist material used (species, size and grade of wood) and happened to have a copy of the applicable grading rules (shirt-pocket size for the particular grading association OR Reference [2] with back editions), design stresses could be applied as they have been in the preceding section and the Annex, leading to analysis of the joists and design of joist upgrading and of top beams and columns. Such a situation is unlikely to apply.

An alternate approach might be as described in the following paragraphs:

(1) Assume that the floor over the basement was built according to a building code calling for 40 psf live load on the first floor and allowing 10 psf for dead load (weight of flooring materials and joists). (Many buildings were not built according to code or the code was not enforced, but many are stronger (especially if owner built) and probably a lot are weaker (e.g., as in speculative housing built to cut corners).)

⁶ Numerical results are shown to illustrate the work, not to imply a degree of accuracy in design/analysis.

Table B2-5

TOP BEAM CAPACITIES

1st Member Design
 Spacing Lower Upper

Top Beam Capacities of 2 Beams per Column


| | | | | | |
|--------------------------|-----|---|------|------|----------|
| Triple 2x8s, edgewise | 12" | } | 2509 | 1081 | 11.3 kst |
| | 16" | | | | |
| | 24" | | | | |
| Quadruple 2x6s, edgewise | 12" | } | 2588 | 1024 | 10.3 kst |
| | 16" | | | | |
| | 24" | | | | |

NOTE: See Annex sheets (3), Top Beams, for design method including required bearing lengths on top and bottom surfaces of these two top beam schemes.

Table B2-7
COLUMN CAPACITIES


| | | Member Strengths | |
|--|--|------------------|--------|
| | | Lower | Higher |
| Column Capacities (8 ft long) in pounds: | | | |
| 2x4 column (too long and slim, per code) | | | |
| a. | 2x4 column, with mid-ht support: (meaning laterally, in weak direction) | 1848 | 2305 |
| b. | 4x4 column: | 5782 | 7327 |
| 2x6 column (too long and slim, per code) | | | |
| c. | 2x6 column, with mid-ht support: | 3143 | 4348 |
| d. | 2x6 column, with 3rd-point supports: | 5346 | 8621 |
| 2x8 column (too long and slim, per code) | | | |
| e. | 2x8 column, with mid-ht support: | 4143 | 5731 |
| f. | 2x8 column, with 3rd-point supports: | 7047 | 11364 |
| g. | 4x6 column: | 9914 | 13822 |
| h. | 4x6 column, with mid-ht support: | 13302 | 22292 |

NOTE: Above capacities should be reduced for the column's own weight and may be increased for various live load durations (see Annex sheet 2 of Columns for Upgrading).



NOT TO SCALE

Figure B2-1A FLOOR JOISTS UPGRADING



NOT TO SCALE

Figure B2-1B

(2) Measure the actual joist width b , depth d , and center-to-center span⁷ L of the joist being checked. Also measure the c-c. spacing j between joists. Use all four dimensions in inches, unless otherwise indicated below.

(3) Enter Table B2-3, using the nominal b and d (see Table B2-4), and actual j and L dimensions (all in inches, except L in feet and inches here); read the values for E and F_b . (For example: 2x8s on 16 in. centers, span 11 ft 8 in., read E as 1,200,000 psi and F_b as 1,040 psi.) Interpolate as necessary if the table doesn't include the specific field measurements obtained. If the actual b and d measurements agree with the column of Table B2-4 headed "Actual (older)," multiply the E value read in Table B2-3 by the "Corr. Factor" shown in Table B2-4.

As an alternative to the Table B2-3 approach, use the following formulas (no "Corr. Factor"; all actual dimensions, in inches):

$$E = 15.625 (j / b) (L / d)^3 \quad (\text{psi})$$

$$F_b = 0.26042 (j / b) (L / d)^2 \quad (\text{psi})$$

Both table and formula approaches assume floor designs based on 40 psf live load, 10 psf dead load, and live load deflection limited to 1/360th of the span.

(4) Values for F_v and F_{c1} (both in psi) can be calculated from the following:⁸

$$F_v = 22.6736 + 71.3296 (E / 1,000,000)$$

$$F_{c1} = -135.76 + 313.498 (E / 1,000,000)$$

⁷ Joist span is measured between the centers of its supports, usually a steel beam down the basement center and an outer basement wall.

⁸ Least squares regression equations shown were obtained by use of elasticity moduli and allowable stress values [2] for six grades each of eight species of widely available construction woods: Douglas Fir-Larch; Western Hemlock; Ponderosa, Sugar, Idaho White, and Lodgepole Pines; Southern Pine; and Northern Pine; all when used at 19 percent or less moisture content. (Number of significant digits shown does not imply a degree of accuracy in the results.) Range of E values used was 1.0 to 1.8 million psi; of F_v , 100-140 psi; of F_{c1} , 190-405 psi. With 36 pairs of values used for each of the two equations, the range of percentage differences between each actual value and value calculated with the applicable equation was: for F_v , 16.9 percent to -18.3 percent; for F_{c1} , 33.9 percent to -37.3 percent.

Table B2-3

ALLOWABLE SPANS FOR FLOOR JOISTS
(40 psf LL and 10 psf DL.)

DESIGN CRITERIA: Deflection - For 40 lbs. per sq. ft. live load. Limited to span in inches divided by 360. Strength - Live load of 40 lbs. per sq. ft. plus dead load of 10 lbs. per sq. ft. determines the required fiber stress value.

| JOIST SIZE & SPACING (IN.) | | Modulus of Elasticity, "E", in 1,000,000 psi | | | | | | | | | | | | | | |
|----------------------------------|------|--|--------------|---------------|--------------|---------------|--------------|--------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|--|
| | | 08 | 09 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 22 | |
| 2x6 | 12 0 | 8-6 720 | 8-10 780 | 9-2 830 | 9-6 890 | 9-9 940 | 10-0 990 | 10-3 1040 | 10-6 1090 | 10-9 1140 | 10-11 1190 | 11-2 1230 | 11-4 1280 | 11-7 1320 | 11-11 1410 | |
| | 16 0 | 7-9 790 | 8-0 860 | 8-4 920 | 8-7 980 | 8-10 1040 | 9-1 1090 | 9-4 1150 | 9-6 1200 | 9-9 1250 | 9-11 1310 | 10-2 1360 | 10-4 1410 | 10-6 1460 | 10-10 1550 | |
| | 24 0 | 6-9 900 | 7-0 980 | 7-3 1050 | 7-6 1120 | 7-9 1190 | 7-11 1250 | 8-2 1310 | 8-4 1380 | 8-6 1440 | 8-8 1500 | 8-10 1550 | 9-0 1610 | 9-2 1670 | 9-6 1780 | |
| 2x8 | 12 0 | 11-3 720 | 11-8 780 | 12-1 830 | 12-6 890 | 12-10 940 | 13-2 990 | 13-6 1040 | 13-10 1090 | 14-2 1140 | 14-5 1190 | 14-8 1230 | 15-0 1280 | 15-3 1320 | 15-9 1410 | |
| | 16 0 | 10-2 790 | 10-7 850 | 11-0 920 | 11-4 980 | 11-8 1040 | 12-0 1090 | 12-3 1150 | 12-7 1200 | 12-10 1250 | 13-1 1310 | 13-4 1360 | 13-7 1410 | 13-10 1460 | 14-3 1550 | |
| | 24 0 | 8-11 900 | 9-3 980 | 9-7 1050 | 9-11 1120 | 10-2 1190 | 10-6 1250 | 10-9 1310 | 11-0 1380 | 11-3 1440 | 11-5 1500 | 11-8 1550 | 11-11 1610 | 12-1 1670 | 12-6 1780 | |
| 2x10 | 12 0 | 14-4 720 | 14-11 780 | 15-5 830 | 15-11 890 | 16-5 940 | 16-10 990 | 17-3 1040 | 17-8 1090 | 18-0 1140 | 18-5 1190 | 18-9 1230 | 19-1 1280 | 19-5 1320 | 20-1 1410 | |
| | 16 0 | 13-0 790 | 13-6 850 | 14-0 920 | 14-6 980 | 14-11 1040 | 15-3 1090 | 15-8 1150 | 16-0 1200 | 16-5 1250 | 16-9 1310 | 17-0 1360 | 17-4 1410 | 17-8 1460 | 18-3 1550 | |
| | 24 0 | 11-4 900 | 11-10 980 | 12-3 1050 | 12-8 1120 | 13-0 1190 | 13-4 1250 | 13-8 1310 | 14-0 1380 | 14-4 1440 | 14-7 1500 | 14-11 1550 | 15-2 1610 | 15-5 1670 | 15-11 1780 | |
| 2x12 | 12 0 | 17-5 720 | 18-1 780 | 18-9 830 | 19-4 890 | 19-11 940 | 20-6 990 | 21-0 1040 | 21-6 1090 | 21-11 1140 | 22-5 1190 | 22-10 1230 | 23-3 1280 | 23-7 1320 | 24-5 1410 | |
| | 16 0 | 15-10 790 | 16-5 860 | 17-0 920 | 17-7 980 | 18-1 1040 | 18-7 1090 | 19-1 1150 | 19-6 1200 | 19-11 1250 | 20-4 1310 | 20-9 1360 | 21-1 1410 | 21-6 1460 | 22-2 1550 | |
| | 24 0 | 13-10 900 | 14-4 980 | 14-11 1050 | 15-4 1120 | 15-10 1190 | 16-3 1250 | 16-8 1310 | 17-0 1380 | 17-5 1440 | 17-9 1500 | 18-1 1550 | 18-5 1610 | 18-9 1670 | 19-4 1780 | |

¹The required extreme fiber stress in bending, F_b , in pounds per square inch is shown below each span.

²Use single or repetitive member bending stress values (F_b) and modulus of elasticity values (E).

³For more comprehensive tables covering a broader range of bending stress values (F_b) and Modulus of Elasticity values (E), other spacing of members and other conditions of loading, see the Uniform Building Code.

⁴The spans in these tables are intended for use in covered structures or where moisture content in use does not exceed 19 percent.

Source: Dwelling Construction Under the Uniform Building Code, 1976 Edition,
International Conference of Building Officials, Whittier, California
90601

Table B2-4

JOIST DIMENSIONS - WIDTH x DEPTH (in.)

| Nominal | Actual (current) | Actual (older) & E Corr. Factor |
|---------|------------------|---------------------------------|
| 2x6 | 1.5x5.5 | 1-5/8 x 5-1/2 0.923 |
| 2x8 | 1.5x7.25 | 1-5/8 x 7-1/2 0.834 |
| 2x10 | 1.5x9.25 | 1-5/8 x 9-1/2 0.852 |
| 2x12 | 1.5x11.25 | 1-5/8 x 11-1/2 0.864 |

(5) Plan to install an additional support line under the mid-span points of all joists. Identify the measurements made under paragraph 2 as b for actual width of joist, d for actual depth, j for joist spacing center-to-center (c-c.), and change L to HALF the c-c. span measured for the full, original joist (paragraph 2), all in inches. Calculate the allowable unit total load TL on the joists with new mid-span supports as follows (TL in pounds per square foot (psf)):

$$TL = 154 \text{ bdF}_v / (j (L-2d))$$

$$\text{or} = 192 \text{ bd}^2\text{F}_b / (jL^2)$$

whichever is less.

About 10 psf of this TL will roughly cover the flooring materials, joists, top beam if any, and posts or studs, so that the dead load DL of 10 psf (approximately) can be subtracted from the TL to obtain the allowable live load LL on the floor. The equations exclude any allowed stress increases for load duration of two months or less (15 percent) or impact (100 percent), or for removing the design factor of safety (30 percent). Such increases are handled as described in paragraph 2 of the preceding section, Design/Analysis Annex Work; the comments there about the adequacy of the flooring to carry the above TL between floor joists, also apply here.

(6) If p is the total load (pounds) per joist, as transmitted to the top beam if any, or directly to a stud, it equals the TL (as calculated, but plus any allowed percentage increases, both as just described) times the contributory (floor) area, jL; that is:

$$p = (TL) jL / 144.$$

(7) The required joist bearing area, bL' (actual width b; bearing length L' along joist; both in inches) on the bottom of the joist at mid-span can be calculated from the following:

$$bL' = p / F_{c1}$$

with L' in inches, using F_{c1} (psi) as that for the joist (paragraphs 2-4 above).

If the bL' required by the joist is not provided by the stud or top beam, a wood block may be needed under the joist (even if the block crushes under blast loading, it will be absorbing energy), or recourse to a steel plate may be necessary.

The required bearing area on the top and underside of a top beam can be similarly calculated, but using the appropriate F_{c1} value for the top beam wood; calculation sheets in the Annex also show the methods.

It is assumed that upgrading materials used, presumably obtained from lumberyards, will be known as to species, size and grade of wood, and thus that allowable design values - F_b (both single- and repetitive-member use), F_c , F_{c1} , F_v and E - are obtainable from Reference [2] or the applicable association grading rules. Reference [2] includes associations' addresses, and it is urged that the rules be used, time permitting, to verify the grading of each piece of lumber.

(8) Top beams may be omitted by putting a stud under each joist, using a scab board on each side of the stud-joist junction if both members are the same width, or using a top (or tie) plate (Figure B2-1).

If top beams are to be used, posts should be located under the two end joists to be served by each top beam. If the post spacing is to be other than $1\frac{1}{2}$ times the joist spacing, a new top beam design should be prepared by a competent civil engineer with wood design experience. For post spacing at $1\frac{1}{2}$ times the joist spacing, design work has been done, as reported in the preceding section and in Table B2-1. The following calculations may be used to generalize, based on the column spacing at $1\frac{1}{2}$ times the joist spacing ONLY.⁹

Four top beam designs (2 sizes, each at two strengths) are shown in Table B2-1; they may be used as follows:

Top Beam Capacities ($1\frac{1}{2}$ floor joists per column):

Triple 2x8s, edgewise:⁹

$$p = 25.6 F_v$$

Quadruple 2x6s, edgewise:⁹

$$p = 25.9 F_v$$

with the load-per-joist p in pounds, excluding all add-on percentages related to load duration and factor of safety.

(9) Eight column designs (all 8 ft long and using "2x" or "4x" members) are identified as "a." through "h." in Table B2-2; some may be generalized as follows (P is allowable axial load in pounds):

a. $P = 0.00154 E$

e. $P = 0.00319 E$

c. $P = 0.00242 E$

b., d., f., g., and h.: Design column, using "Column Formulas" of Annex.

⁹ Checked for joist spacings of 24 in. or less.

Design values for E and F_c should be obtained as described in paragraph 7 above.

The column capacities in Table B2-2, including those from formulas just above, include no duration of load increases - see NOTE on Table B2-2.

Adequacy of these columns for end grain in bearing (Idaho White Pine = 1390 psi and Douglas Fir-Larch = 2020 psi applied to the lower and higher member strengths, respectively, see Table B2-5 fourth column) has been checked and all are adequate. Note that the F_g design values of Table B2-5 are subject to the same duration of loading increases (15% and 100% for example), as are the column capacities of Table B2-2.

(10) Sill or bottom plate "design" could be complex, involving a beam with concentrated loads (the columns, plus foot plates if any) and supported by an elastic/plastic/fracturing foundation (the usual light, concrete floor slab). Such design is considered unwarranted for the purposes herein. It should be accepted that the floor slab will crack/break up and will be pushed down, under and adjacent to the bottom plate, should the upgraded floor system over the basement receive an air blast overpressure loading; such action absorbs energy. Recent tests show a very high floor slab resistance to column punching from blast duration loads (see page 18 of main text).

For the added loading of soil placed on the first floor for fallout shielding upgrading, it is doubted that the concrete basement floor will experience anything more than localized cracking, if that, under the following approach:

Use a bottom plate consisting of stress-graded selected dimension lumber (better than, say, utility grade), used flatwise, "2x" and at least as wide as the greater dimension of the columns (preferably wider) for a column spacing of 12 in. to 24 in.

For greater column spacings, use any blocking available under each column flatwise and perhaps stacked, preferably with the bottom block wider than just prescribed for a single member bottom plate.

For column spacings of, say, 4 ft or more, one should leave off thinking of a continuous bottom plate as the column spacing grows larger and take recourse in use of a grillage under each column; the basic premise is to spread the load on the floor slab and underlying soil.

Design graphs for wood beams and columns are included in Appendix B1 herein.

Table B2-5

END GRAIN IN BEARING (psi)

Design values for end grain in bearing parallel to grain on a rigid surface F_g
in pounds per square inch

| Species | Wet service conditions ¹ | Dry service conditions ¹ | | |
|--|-------------------------------------|-------------------------------------|-------------------------------------|------------------------|
| | | Sawn lumber ² | | Glued laminated timber |
| | | More than 4" thick | Not more than 4" thick ³ | |
| Ash, Commercial White | 1370 | 1510 | 2060 | 2400 |
| Aspen | 740 | 820 | 1110 | 1300 |
| Balsam Fir | 890 | 980 | 1330 | 1560 |
| Beech | 1190 | 1310 | 1780 | 2080 |
| Birch, Sweet and Yellow | 1150 | 1260 | 1720 | 2010 |
| Black Cottonwood | 620 | 690 | 930 | 1090 |
| California Redwood (Close grain) | 1560 | 1720 | 2270 | 2620 |
| California Redwood (Open grain) | 1150 | 1270 | 1670 | 1940 |
| Coast Sitka Spruce | 950 | 1040 | 1420 | 1660 |
| Coast Species | 950 | 1040 | 1420 | 1660 |
| Cottonwood, Eastern | 765 | 840 | 1150 | 1340 |
| Douglas Fir - Larch (Dense) ⁴ | 1570 | 1730 | 2360 | 2750 |
| Douglas Fir - Larch ⁴ | 1340 | 1480 | 2020 | 2350 |
| Douglas Fir South | 1220 | 1340 | 1820 | 2130 |
| Eastern Hemlock - Tamarack ⁴ | 1150 | 1270 | 1730 | 2020 |
| Eastern Spruce | 970 | 1070 | 1460 | 1700 |
| Eastern White Pine ⁴ | 900 | 1000 | 1360 | 1580 |
| Eastern Woods | 820 | 900 | 1230 | 1440 |
| Engelmann Spruce - Alpine Fir | 810 | 890 | 1220 | 1420 |
| Hem. Fir ⁴ | 1110 | 1220 | 1670 | 1940 |
| Hickory and Pecan | 1370 | 1510 | 2050 | 2400 |
| Idaho White Pine | 930 | 1020 | 1390 | 1630 |
| Lodgepole Pine | 970 | 1060 | 1450 | 1690 |
| Maple, Black and Sugar | 1140 | 1260 | 1710 | 2000 |
| Mountain Hemlock | 1070 | 1170 | 1600 | 1870 |
| Northern Aspen | 740 | 810 | 1110 | 1290 |
| Northern Pine | 1040 | 1150 | 1570 | 1830 |
| Northern Species | 880 | 970 | 1320 | 1540 |
| Northern White Cedar | 740 | 810 | 1110 | 1290 |
| Oak, Red and White | 1060 | 1160 | 1590 | 1850 |
| Ponderosa Pine - Sugar Pine | 910 | 1000 | 1370 | 1600 |
| Red Pine | 880 | 970 | 1320 | 1540 |
| Sitka Spruce | 990 | 1090 | 1480 | 1730 |
| Southern Cypress | 1330 | 1460 | 1990 | 2320 |
| Southern Pine (Dense) | 1540 | 1690 | 2310 | 2690 |
| Southern Pine | 1320 | 1450 | 1970 | 2300 |
| Spruce - Pine - Fir | 940 | 1040 | 1410 | 1650 |
| Sweetgum and Tupelo | 1020 | 1120 | 1530 | 1780 |
| Western Cedars ⁴ | 1040 | 1140 | 1520 | 1750 |
| Western Hemlock | 1240 | 1360 | 1860 | 2170 |
| Western White Pine | 930 | 1030 | 1400 | 1630 |
| White Woods (Western Woods) | 810 | 890 | 1220 | 1420 |
| West Coast Woods (Mixed Species) | 810 | 890 | 1220 | 1420 |
| Yellow Poplar | 890 | 980 | 1340 | 1560 |

1 Wet and dry service conditions are defined in 4.1.4 for sawn lumber and 5.1.5 for glued laminated timber.

2 Applies to sawn lumber members which are at a moisture content of 19 percent or less when full design load is applied, regardless of moisture content at time of manufacture.

3 When 4-inch or thinner sawn lumber is surfaced at a moisture content of 15 percent or less and is used under dry service conditions, the values listed for glued laminated timber may be applied.

4 Values also apply when species name includes the designation "North".

Source: National Design Specification for Wood Construction, 1977 Edition, National Forest Products Association, 1619 Massachusetts Avenue, N. W., Washington, D. C. 20036; art. 2.3, Table 2A.

Author Comments: When stress in end-grain bearing exceeds 75% of above values, bearing shall be on a metal plate or strap, or on other durable, rigid, homogeneous material of adequate strength, per Source. (This criterion should be applied to both top and bottom ends of each stud or post.)

ANNEX

Stress-graded (visually only) lumber species-sizes-grades ¹ commonly available in local lumberyards were narrowed down to the following, categorized as "higher strength" and "lower strength" for use in an earlier study [4,p.C-3&5]:

Allowable Design Stresses in Normal Use (psi)

| <u>Size & Grade</u> | <u>F_b</u> ² | <u>F_v</u> ³ | <u>F_{c⊥}</u> ⁴ | <u>F_c</u> | <u>E</u> | <u>F_g</u> ⁵ |
|---|-----------------------------------|-----------------------------------|------------------------------------|----------------------|----------|-----------------------------------|
| <u>2 in. to 4 in. th., 4 in. wide</u> | | | | | | |
| Construction ⁶ | 1200 (1050) | 140 | 385 | 1150 | 1500000 | 2020 |
| Standard ⁷ | 450 (400) | 100 | 190 | 650 | 1200000 | 1390 |
| <u>2 in. to 4 in. th., 5 in. & wider ⁸</u> | | | | | | |
| No. 1 ⁶ | 1750 (1500) | 140 | 385 | 1250 | 1800000 | 2020 |
| No. 2 ⁷ | 925 (850) | 100 | 190 | 725 | 1300000 | 1390 |

¹ Reference [2] contains a full listing of wood species, sizes, grades, design values, etc. However, it lacks two needed tables from Reference [3], which are included herein as Tables B2-5 and B2-6.

All of above is Dimension Lumber; surfaced dry or surfaced green; used at 19 percent maximum moisture content.

² Repetitive-member use; single-member use values in parentheses [2,p.20]. Both uses are edgewise; for flatwise-use (increase) factors, see Reference [2,p.16].

³ Values taken from Reference [3,art.3.4.4.2]; see Table B2-6.

⁴ For bearing lengths L' less than 6 in. long and not nearer than 3 in. to end of member, correct F_{c⊥} by (1 + 0.375 / L')

⁵ Values taken from Reference [3,Table 2A,p.7]; see Table B2-5.

⁶ "Higher strength"; stresses for Douglas Fir-Larch [2].

⁷ "Lower strength"; stresses for Idaho White Pine, but useful (practically) for other Western Pines (Ponderosa, Sugar and Lodgepole) [2].

⁸ But not more than 12 in. [5,p.16-17].

(BLANK)

Table B2-6

ALLOWABLE HORIZONTAL SHEAR VALUES F_v (psi)

| | Maximum Moisture Content | | |
|--|--------------------------|------------|------------|
| | Unseasoned | 19 percent | 15 percent |
| Aspen | 85 | 90 | 95 |
| Balsam Fir | 85 | 95 | 95 |
| Black Cottonwood | 70 | 75 | 80 |
| California Redwood | 115 | 120 | 130 |
| Coast Sitka Spruce | 90 | 95 | 100 |
| Coast Species | 90 | 95 | 100 |
| Douglas Fir-Larch | 130 | 140 | 145 |
| Douglas Fir-South | 130 | 140 | 145 |
| Eastern Hemlock-Tamarack | 120 | 130 | 135 |
| Eastern Spruce | 95 | 105 | 110 |
| Eastern White Pine | 90 | 95 | 100 |
| Eastern Woods | 85 | 95 | 95 |
| Engelmann Spruce/Alpine Fir | 95 | 105 | 110 |
| Hem-Fir | 105 | 110 | 115 |
| Idaho White Pine | 95 | 100 | 105 |
| Lodgepole Pine | 95 | 105 | 110 |
| Mountain Hemlock | 130 | 140 | 150 |
| Northern Aspen | 90 | 95 | 100 |
| Northern Pine | 100 | 105 | 110 |
| Northern Species | 90 | 95 | 100 |
| Northern White Cedar | 85 | 95 | 100 |
| Ponderosa Pine-Sugar Pine | 100 | 105 | 110 |
| Red Pine | 100 | 110 | 115 |
| Sitka Spruce | 105 | 115 | 120 |
| Southern Pine | 125 | 135 | 145 |
| Spruce-Pine-Fir | 95 | 105 | 110 |
| Western Cedar | 100 | 105 | 110 |
| Western Hemlock | 125 | 135 | 145 |
| Western White Pine | 90 | 100 | 105 |
| White Woods (Western Woods, West Coast Woods, Mixed Species) | 95 | 100 | 105 |

Source: National Design Specification for Wood Construction, 1977 Edition,
National Forest Products Association, 1619 Massachusetts Avenue, N.W.,
Washington, D. C. 20036; art. 3.4.4.2

Author Comments: Use column of above table that specifies "19 percent"
moisture content. For wood species not shown, consult "Design Values
for Wood Construction," 1980 Supplement to above Source.

WOOD BEAM DESIGN FORMULAS - UNIFORMLY DISTRIBUTED LOADS

With simple end supports and with continuous supports, beam span L for horizontal shear design is measured center-to-center (c-c.) of supports. L is the same with continuous supports for flexure and deflection design; but with simple end supports, beam span L for flexure and deflection design should be the beam length between support faces plus half the REQUIRED bearing length L' at each end [3,art.3.2.1,p.8]. for simplification, however, L will be taken as c-c. of supports for all purposes herein.

Constant C is 360 under LL (live loads) only, and is 240 under LL plus DL (live plus dead loads). Check both conditions.

Constant C' varies with support conditions as shown: SS is simple supports; PC is propped cantilever; and FF is fixed-fixed.

| | <u>C' Constants</u> | | |
|--|----------------------------------|-----------|----------------------|
| | <u>SS</u> | <u>PC</u> | <u>FF</u> |
| | 8 | 8 | 12 |
| <u>FLEXURE:</u> | | | |
| $M = wL^2 / C' = F_b I / c = F_b b d^2 / 6$ | | | (1) |
| | | | ($I = b d^3 / 12$) |
| | | | ($c = d / 2$) |
| $L^2 = C' M / w = C' F_b b d^2 / (6w)$ | | | (2) |
| $w = C' M / L^2 = C' F_b b d^2 / (6L^2)$ | | | (3) |
| <u>HORIZONTAL SHEAR:</u> | 2 | 1.6 | 2 |
| $V = w (L - 2d) / C' = 2 b d F_v / 3$ | | | (4) |
| $L = (C' V / w) + 2d = (2C' b d F_v / (3w)) + 2d$ | | | (5) |
| $w = C' V / (L - 2d) = 2C' b d F_v / (3 (L - 2d))$ | | | (6) |
| <u>DEFLECTION:</u> | 5/384 | 1/185 | 1/384 |
| $y = L / C = C' w L^4 / EI = 12C' w L^4 / (E b d^3)$ | | | (7) |
| $L^3 = E b d^3 / (12C' w)$ | | | (8) |
| $w = (d / L)^3 E b / (12C' C)$ | | | (9) |

BEAM BEARING LENGTH L' (at each end):⁹

2 (10) 2

If $L' < 6$ in. AND bearing area is > 3 in. from end:

$$R = V = wL / C' = bF_{c1} (L' + 0.375) \quad (10)$$

$$L' = (wL / (bC'F_{c1})) - 0.375 \quad (11)$$


$$w = (bC'F_{c1} / L) (L' + 0.375) \quad (12)$$

If $L' \geq 6$ in. OR bearing area is < 3 in. from end: Drop 0.375 from Eq. 10-12. (For simplification, consider dropping the 0.375 in all cases.)

⁹ It is recommended that L' be not less than 2 in.

¹⁰ $C' = 1.6$ at fixed end; $C' = 2.67$ at simple support or "propped" end.

COLUMN FORMULAS - SIMPLE SOLID COLUMN DESIGN [3]
(Pin-ended conditions assumed)



L_1 and L_2 =
Distances between points of
lateral support of column in
planes 1 and 2, inches

d_1 and d_2
Dimensions of column in
planes of lateral support,
inches

For conditions shown in the sketch:

Use larger of L_1 / d_1 and L_2 / d_2 as the L / d for design (13A)

Slenderness ratio L / d must be ≤ 50 (13B)

For $L / d \leq 11$: $F'_c = F_c$ (14)

For $L / d > 11$, but $\leq K$:

$$K = 0.671 \sqrt{E / F_c} \quad (15)$$

$$F'_c = F_c (1 - 1/3 (L / dK)^4) \quad (16)$$

For $L / d \geq K$: $F'_c = 0.3E / (L/d)^2$ (17)

$$P = AF'_c = bdF'_c \quad (18)$$

Usual Floor Joist Design

Try 2×8 (1.5" x 7.25") floor joist, on 16" centers. Use:
 floor live load, $LL = 40 \text{ psf}$; floor dead load, $DL = 10 \text{ psf}$
 Thus $DL + LL = (10 + 40) \times \frac{16}{12} \times \frac{1}{12 \text{ ft}} = \frac{50}{9} \text{ pli} = w.$

Find usable c-c spans, for "lower" and "higher" member strengths - see Annex 1st page (above).

Flexure:

Eq. 2: $L^2 = 8 F_b \times 1.5 \times 7.25 \times \left(6 \times \frac{50}{9}\right) = \frac{\text{Lower } L}{\text{Higher } L} \left(\frac{\text{Strength}}{\text{Wood}} \right)$

$\frac{L}{182''}$

$$\begin{bmatrix} 925 \\ 1750 \end{bmatrix}$$

Horiz. Shear:

Horiz. Shear:
Eq. 5: $L = 2 \times 2 \times 1.5 \times 7.25 \sqrt{F_v / (3 \times 50)} + 2 \times 7.25 = 276$ 380

Deflection:

Deflection:
 Eg. 8: $L^3 = \frac{E \times 1.5 \times 7.25^3}{384} / ((2 \times \frac{5}{384} \times C_w) = 153 \quad 170 \quad C=240$
 $\left[\begin{matrix} 1.3 \times 10^6 \\ 1.8 \times 10^6 \end{matrix} \right] \quad \left[\begin{matrix} 240 \\ 360 \end{matrix} \right] \left[\begin{matrix} 50/q \\ 40/q \end{matrix} \right] \quad 1+4 \quad (160) \quad C=360$

End Bearing:

End Bearing:
Eq. 11: $L = \frac{50 \times L}{9} / (1.5 \times 2 \times F_{CL})$

| | |
|--|--|
| $\begin{bmatrix} 132 \\ 160 \end{bmatrix}$ | $\begin{bmatrix} 190 \\ 385 \end{bmatrix}$ |
|--|--|

$\frac{L}{1.29}$
USE 2"
(min.)

$\frac{L}{0.77}$
USE 2"
(min.)

Least L for lower, and least L for higher, are
132" (flexure controlling) and 160" (deflection,
with $C=360$, controlling) respectively.
These 2, L values are used for End Bearing calc's.

Note: (a) For upgrading design, ignore deflection as a design criterion.

(b) Above two L values agree exactly with Table B1-3.

HOST WELTER USE:

HOST WELTER USE:

But, $1g$ deflection, $s(E.g.) w = 8 F_b \sqrt{1.5 \times 7.25^2 / (6 L^2)} = 50/9$

$\left[\frac{92.5}{1750} \right] \left[\frac{132}{160} \right] \times 144 / 16 = \frac{50}{40}$

A. Fallout only (assuming soil @ 95 pcf)'s +15% for loads < 2 mos:

or

B. Combined: Fallout: Use \leq soil LL in A; say, 4.5 in. @ 100 pcf used:

Blast capacity (remove 15% of A; instead use


Blast capacity (~~remove~~ 15% of A_j instead use +100% for impact loads and +30% factor of

Blast capacity (Remove 15% of A_g instead use +100% for impact loads and +30% factor of safety given up) = $\frac{2.0 \times 1.3}{1.15} \times \left[\frac{8}{25} \right] = \frac{18}{0.13} = \frac{57}{0.39}$ psi " " (capacity remaining) per LL (Worst)

Upgrading Floor Joist Design

Try same 2x8 (1.5 x 7.25) floor joist, on 16" centers, but with an added mid-span support — same 2 strengths — spans now (132 ÷ 2) 66" and (160 ÷ 2) 80" for "lower" and "higher" strengths, respectively.

Find w . Use $DL = 10$ psf, as before. PC supports.

Flexure: 

Eq. 3: $w = 8 F_b 1.5 \times 7.25 / (6 L^2) =$

| Lower | | Higher | | |
|-------|--------------------------|--------|-----|--------|
| w | | w | | |
| 22.3 | | 28.7 | | pli TL |
| | $\times 1.14, TL = 201$ | | 259 | psf TL |
| | $\frac{16}{16} DL = -10$ | | -10 | " DL |
| | $LL = 191$ | | 249 | " LL |

$\left[\begin{smallmatrix} 925 \\ 1750 \end{smallmatrix} \right] \quad \left[\begin{smallmatrix} 66 \\ 80 \end{smallmatrix} \right] (j=16)$

Horiz. shear:

Eq. 6: $w = 2 \times 1.6 \times 1.5 \times 7.25 F_v / (3 \times (L - 2 \times 7.25)) =$

| Lower | | Higher | | |
|-------|------------|--------|-----|--------|
| w | | w | | |
| 22.5 | | 24.8 | | pli TL |
| | $TL = 223$ | | 223 | psf TL |
| | $DL = -10$ | | -10 | " DL |
| | $LL = 213$ | | 213 | " LL |

$\left[\begin{smallmatrix} 100 \\ 140 \end{smallmatrix} \right] \quad \left[\begin{smallmatrix} 66 \\ 80 \end{smallmatrix} \right]$

UPGRADING:

A. Fallout shielding only (assume $LL = 191$ 213 psf LL soil @ 100 pcf; add 15% for loads $\times 1.15$)

62 mos. duration (Ref. 3 art. 2.2.5.3) $LL = 220$ 245 psf (soil) LL

Soil th. = 26.4 29.4 in. soil

$[w = (LL + DL) \times 16/144 = 25.6$ 28.3 pli TL]

$\times 1.15$

| Lower | | Higher | | |
|-------|-------|--------|-----|---------------|
| w | | w | | |
| 191 | | 213 | | psf LL |
| 220 | | 245 | | psf (soil) LL |
| | -95 | | -95 | " " |
| | 125 | | 150 | psf (soil) LL |

B. Combined: Fallout: Use 5 soil LL in A. $\times 1.15$

Assuming 12" th. 95 pcf soil; +15% as before:

Blast capacity (remove 15% of A; instead use +100% for impact loads and +30% factor of safety given up) = $\frac{2.0 \times 1.3}{1.15} \times \left[\begin{smallmatrix} 125 \\ 150 \end{smallmatrix} \right] =$ 283 339 psf (blast) LL

$\div 1.44$ 1.96 2.36 psi " "

$[w = (LL_{soil} + LL_{blast} + DL) \times 16/144 = 43.1$ 49.3 pli TL]

$\left[\begin{smallmatrix} 95 \\ 95 \end{smallmatrix} \right] \left[\begin{smallmatrix} 283 \\ 339 \end{smallmatrix} \right] \left[\begin{smallmatrix} 10 \\ 10 \end{smallmatrix} \right]$

Bearing Length: (of floor joist on top beam or column or wall)

Eq. 11

At each end of 2-span joist:

$L' = wL / (1.5 \times 2.67 F_c) =$


| Lower | | Higher | | |
|-------|---|--------|--|----------------------------|
| L' | | L' | | |
| 2.22" | | 7.47" | | USE 2" A |
| | $\left[\begin{smallmatrix} 190 \\ 385 \end{smallmatrix} \right]$ | | | |
| 3.74" | | 2.56" | | B. USE NEXT HIGHER 1/2 in. |
| | $\left[\begin{smallmatrix} 190 \\ 385 \end{smallmatrix} \right]$ | | | |

At midspan: $2 \times L' = 2(wL) / (1.5 \times 1.6 F_c) =$ 7.41" 4.90"


$\left[\begin{smallmatrix} 12.48 \\ 8.54 \end{smallmatrix} \right]$ Same as above $\left[\begin{smallmatrix} 12.48 \\ 8.54 \end{smallmatrix} \right]$ A. B.

Assume that in each column line, there is a column under each of the 2 end joists, ignoring joists resting ^{on their full length} on the basement end walls.

Also, assume that column spacing is either at some whole number (integer) multiple of the joist spacing (usually 12, 16 or 24 in. c-c), or at an integer-divided-by-two multiple of the same. This means that all columns will be under joists; or that half or more will be, with the others located midway between joists. (An occasional irregularity in joist spacing should be treated so that the columns-per-joist ratio is not increased, but is decreased, over the predominating ratio.) If top beam must be discontinuous, break it between 2 joists, and put a column under each of the 2 joists, with top beam ends between joists and columns.



Use either half as a propped cantilever and design member;



Ref. 1;
A2-202
#14

Top Beams


(Sheet 2 of 3)

Ref: p 2-20-14

$$\text{(net)} V_1 = \frac{P \left(\frac{2L}{3}\right)^2}{2L^3} \left(\frac{2L}{3} + 2L\right) = \frac{4}{27} P = 0.15 P$$

$$R_2 = V_2 = \frac{P \left(\frac{2L}{3}\right)}{2L^3} \left(3L^2 - \left(\frac{2L}{3}\right)^2\right) = \frac{23}{27} P = 0.85 P$$

Net $0.15p = V_1$
 $= V_2 \text{ (max. V)}$



$$R_1 - P = V_1 \text{ (in actual case)} \therefore R_1 = 1.15 P$$

$$M_1 = \frac{4}{27} P \left(\frac{2L}{3}\right) = \frac{8}{81} PL = 0.099 PL$$

$$M_2 = P \left(\frac{2L}{3}\right) \left(\frac{L}{3}\right) \times \frac{\left(\frac{2L}{3} + L\right)}{2L^2}$$

$$M_2 = PL \times \frac{2}{3} \times \frac{1}{3} \times \frac{1}{2} \times \frac{5}{3} = \frac{5}{27} PL = 0.185 PL$$

FLEXURE:

EQ. NO.

$$M_{\max.} = 0.185 PL = F_b \times \frac{bd^2}{6} \quad [L = \text{c-c. of supports}] \quad 22$$

HORIZONTAL SHEAR:

$$V_{\max.} = 0.85 P = \frac{2}{3} F_v bd \quad 23$$

V for design is taken at d distance from support center
 (no effect in this case, however).

BEARING LENGTH (on top and bottom of top beam):

Top of top beam: $L' = \frac{P}{b F_{c\perp}} \quad 24$

Bottom of top beam:

Propped end: $R_1 = 1.15 P = b L' F_{c\perp}$ or $L' = \frac{1.15 P}{b F_{c\perp}} \quad 25$

Fixed end: $R_2 = 0.85 P = b L' F_{c\perp}$



This end is continuous, so total bearing length at midspan is $2 \times L'$ (that is, L' each way from column support R_2)

$$2 \times L' = \frac{2 \times 0.85 P}{b F_{c\perp}} \quad 26$$

Top Beams

(Sheet 3 of 3)

Case 1A



Using
Eq.

Triple 2x8's (1.5x7.25) edgewise, top beam

22 Flexure: $p = \frac{4.5 \times 7.25 \times F_b}{6 \times 0.185 L}$

| Joist Spacing | Member Strength Lower | Member Strength Higher | |
|---------------|-----------------------|------------------------|-----|
| 12" | 10951 | 20717 | 16. |
| 16" | 8213 | 15538 | " |
| 24" | 5475 | 10359 | " |

$L = 1.5 \times \text{joist spacing}$

23 Horizontal shear: $p = \frac{2 \times 4.5 \times 7.25 \times F_v}{3 \times 0.85}$

| Joist Spacing | Member Strength Lower | Member Strength Higher | |
|---------------|-----------------------|------------------------|-----|
| 12" | 2559 | 3582 | 16. |
| 16" | 190 | 385 | " |
| 24" | 140 | 290 | " |

Controlling.

Note: It would be expected that horiz. shear would be controlling over flexure in such short, heavily loaded members.

Bearing length: (On top and bottom of top beam)*

25 Propped end: $L' = \frac{1.15 p}{4.5 F_{c \perp}}$

| Joist Spacing | Member Strength Lower | Member Strength Higher | |
|---------------|-----------------------|------------------------|--|
| 12" | 3.44" | 2.38" | |
| 16" | 2.99" | 2.07" | |
| 24" | 5.09" | 3.51" | |

26 Overall at continuous support: $2L' = \frac{2 \times 0.85 p}{4.5 \times F_{c \perp}}$

Round to next higher 1/2 in.

Quadruple 2x6's (1.5x5.5) edgewise, top beam

(Flexure checked as not controlling)

23 Horiz. shear: $p = \frac{2 \times 6 \times 5.5 \times F_v}{3 \times 0.85}$

| Joist Spacing | Member Strength Lower | Member Strength Higher | |
|---------------|-----------------------|------------------------|--|
| All jo's | 2588 | 3624 | |

Bearing length: (As above)*

25 Propped end: $L' = \frac{1.15 p}{6 F_{c \perp}}$

| Joist Spacing | Member Strength Lower | Member Strength Higher | |
|---------------|-----------------------|------------------------|--|
| 12" | 2.61" | USE 2" min. | |
| 16" | 2.27" | USE 2" min. | |
| 24" | 3.86" | 2.67" | |

26 Overall at continuous end: $2L' = \frac{2 \times 0.85 p}{6 F_{c \perp}}$

Round to next higher 1/2 in.

* Use joist blocks and cap blocks (2 in. or thicker), as necessary, to provide required bearing lengths.

Columns for Upgrading

(Sheet 2 of 3)

Ex: 2x8 column, supported @ midht:

$$13 \quad L_2/d_2 = 96/7.25 = 13.2 \quad L_1/d_1 = 48/1.5 = 32$$

(controlling)

$$15 \quad K = \text{same as } 2 \times 6$$

$$17 \quad F'_c = \text{same as } 2 \times 6 \text{ (midht supp.)} =$$

$$18 \quad P = 1.5 \times 7.25 \times F'_c =$$

Member Strength

| | Lower | Higher | |
|---------|-----------|-------------------|-----|
| $E =$ | 1.3 | 1.8×10^6 | psi |
| $F_c =$ | 725 | 1250 | " |
| | $L/d > K$ | | |

| | | | |
|--|------|------|-----|
| | 381 | 527 | psi |
| | 4143 | 5731 | lb. |

2x8 column, supported @ 1/3 & 2/3 ht:

Same as 2x6 w/ same supports, down to:

$$16 \quad F'_c = \text{same}$$

$$18 \quad P = 1.5 \times 7.25 \times F'_c$$

$E, F_c \& K$'s as above.

| | $L/d < K$ | | |
|--|-----------|-------|-----|
| | 648 | 1045 | psi |
| | 7047 | 11364 | lb. |

4x6 column:

$$13 \quad L_1/d_1 = 96/3.5 = 27.43 \text{ (as above)}$$

$$16 \quad F'_c = F_c \left[1 - \frac{1}{3} \left(\frac{L/d}{K} \right)^4 \right] =$$

$$17 \quad F'_c = 0.3E / 27.43^2$$

$$18 \quad P = 3.5 \times 5.5 \times F'_c$$

$E, F_c \& K$'s as above.

| | $L/d < K$ | $L/d > K$ | |
|--|-----------|-----------|-----|
| | 515 | — | psi |
| | — | 718 | " |
| | 9914 | 13822 | lb. |

4x6 column, supported @ midht:

$$13 \quad L_1/d_1 = 48/3.5 = 13.71 \quad L_2/d_2 = 96/5.5 = 17.45$$

(controlling)

$$16 \quad F'_c = F_c \left[1 - \frac{1}{3} \left(\frac{L/d}{K} \right)^4 \right] =$$

$$18 \quad P = 3.5 \times 5.5 \times F'_c =$$

$E, F_c \& K$'s as above.

| | $L/d < K$ | | |
|--|-----------|-------|-----|
| | 691 | 1158 | psi |
| | 13302 | 22292 | lb. |

Above are "normal" design values for column axial loads;
for UPGRADING in haz areas (blast ≤ 5 psi):

A. Fallout shielding only — soil live loads, for example: *
Increase axial load P values above by 15%,
assuming load duration will be less than or equal to 2 mas.

B. Combined: * Fallout: Use soil load $< A$; subtract actual
soil load from 1.15 times column's normal, axial
live load capacity, leaving a residual capacity
for blast.

Blast: Using this residual capacity for blast,
remove the 15% put in for soil loads (2 mas. or
less), and substitute a 100% increase for
impact load (of blast) — that is:

$$\left[\frac{\text{Residual capacity for blast}}{\text{Blast}} \right] \times \frac{2}{1.15} = \text{Blast capacity (lb.)}$$

Divide Blast capacity (lb.) by column's contributory
floor area served (Sheet 1), to get blast capacity
(psf) — then divide by 144 to get it in psi.


(*) — Saving the factor of safety, (FS) of about 30% (or 1.30)
for buckling failure insurance.

Columns for Upgrading (Sheet 3 of 3)

Note that "2x" columns cannot be longer (See Eq. 13) than 75" [$L/d = 75 / 1.5 \leq 50$], unless they have lateral support in the weak ($1\frac{1}{2}$ ") direction.

Note that lateral supports can be provided by 1"x4" or 1"x6" boards, well-nailed, flat on both sides of columns, OR by blocking between columns* — either one carried to wedged contact with end basement walls, OR by 1"x4" or 1"x6" boards, well-nailed, as diagonals from top to bottom plates, counter-directional with one on each side of the column. Latter (diagonals) technique can be used to allow unobstructed opening between columns, wherever desired.

NOTE: Get a copy of latest (shirt-pocket) grading rules, and re-grade all wood members to be used in stress-graded situations.



Example:

$$\text{Joists per column} = 10/7 = 1.43$$

Fasten bottom plate with stud driver.

Always put column under last joist at each end (excluding one, or double, resting on each foundation wall).

Run diagonals on one side of column, at angle approx. 90° to those on other side of column line. Lateral supports for columns may be blocking, or face boards on each side of column line — made stable by diagonals, or by continuous blocking through entire column line and wedge-fitted to both end walls.

(*) Use of steel strapping is another alternative.

NOTATION ¹¹

- A = area of cross-section (in.²)
- b = breadth (edge width) of rectangular member (in.)
- b' = width of (floor) area supported (in.)
- C = deflection coefficient (= L / maximum deflection)
- C' = beam formula constant
- c = distance from neutral axis to extreme fiber (in.)
- DL = dead load (psf)
- d = depth of rectangular member (in.)
- E = modulus of elasticity (psi)
- F_b = design value for extreme fiber in bending (flexure) (psi)
- F_c = design value for compression parallel to grain (psi)
- F_c' = F_c, adjusted for L / d ratio (psi)
- F_{c⊥} = design value for compression perpendicular to grain (psi)
- F_g = design value for end grain in bearing parallel to grain (psi)
- F_v = design value in horizontal shear (psi)
- I = moment of inertia (in.⁴)
- j = joist spacing (in.)
- K = for columns, largest slenderness ratio, L / d, where intermediate column formula applies (see Eq. 15 and 16)
- L = span length of horizontal member (usually center-to-center of supports); or distance (c-c.) between column lateral support points (in.)

¹¹ Generally follows Reference [3].

NOTATION (concluded)

L' = required bearing length in compression perpendicular to grain (in.)

LL = live load (psf)

M = bending or resisting moment, maximum (in.-lb)

P = total concentrated load or axial load (lb)

p = load (live and dead) per joist on top beam, post/stud, etc. (lb)

pcf = pounds per cubic foot

pli = pounds per linear inch

psf = pounds per square foot

psi = pounds per square inch

q = design strength (beam) for static loads (psi)

S = section modulus (= I / c) (in.³)

TL = total load (= DL + LL) (psf)

t = thickness (in.)

V = vertical design shear (= horizontal) in beams (lb)

W = total uniformly distributed load (lb)

w = uniformly distributed load per unit length (pli)

y = deflection of member, usually at mid-length (in.)

REFERENCES

1. Manual of Steel Construction, American Institute of Steel Construction, Inc., Wrigley Building (8th floor), 400 North Michigan Avenue, Chicago, Illinois 60611, 7th ed., 1970. (Eighth edition, 1980, was received October 17, 1980.)
2. "Design Values for Wood Construction," 1980 Supplement to National Design Specification for Wood Construction, 1977 edition [Reference 3]. Shirt-pocket size grading rules may be obtained from the following grading associations:
 - NELMA Northeastern Lumber Manufacturers Association, Inc.
4 Fundy Road
Falmouth, Maine 04105
 - NHPMA Northern Hardwood and Pine Manufacturers Association, Inc.
Northern Building
Green Bay, Wisconsin 54301
 - NLCA National Lumber Grades Authority (Canada)
P. O. Box 97
Ganges, B.C., Canada VDS 1E0
 - RIS Redwood Inspection Service
1 Lombard Street
San Francisco, California 94111
 - SPIB Southern Pine Inspection Bureau
4709 Scenic Highway
Pensacola, Florida 32504
 - WCLIB West Coast Lumber Inspection Bureau
6980 S.W. Varnes Road
P.O. Box 23145
Portland, Oregon 97223
 - WWPA Western Wood Products Association
1500 Yeon Building
Portland, Oregon 97204
3. National Design Specification for Wood Construction, 1977 edition (Structural Lumber, Glued Laminated Timber, Timber Pilings, Fastenings), National Forest Products Association, 1619 Massachusetts Avenue, N.W., Washington, D.C. 20036.

4. Murphy, H. L., Upgrading Basements for Combined Nuclear Weapons Effects: Predesigned Expedient Options, Stanford Research Institute¹² Technical Report for Defense Civil Preparedness Agency,¹³ October 1977.
5. Gaylord, E. H., Jr., and C. N. Gaylord, editors, Structural Engineering Handbook, McGraw-Hill, 1968.

¹² Now SRI International

¹³ Now Federal Emergency Management Agency

Appendix D1

BLAST-RESISTANT DESIGN/ANALYSIS OF STEEL MEMBERS

CONTENTS

| | |
|---|-------|
| Introduction | D1-1 |
| Design in Steel | D1-1 |
| Stability Limitations | D1-3 |
| Structural Steel Material Properties | D1-3 |
| Resistance Expressions | D1-3 |
| Applications | D1-9 |
| A. Allowable Stresses | D1-9 |
| B. One-Way Flat Plate Closures, Simple Supports | D1-9 |
| C. Correction Factors for Other Steels | D1-12 |
| D. Correction Factors for Two-Way Plates | D1-12 |
| NOTATION | D1-13 |
| REFERENCES | D1-15 |

AD-A097 915

SRI INTERNATIONAL MENLO PARK CA

F/G 13/13

UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS: PREDE--ETC(U)


JUL 80 H L MURPHY

DCPA01-77-C-0227

NL

UNCLASSIFIED

13 OF 13



END
DATE
FILMED
9-88
DTIC

TABLES

| | |
|---|------|
| D1-1 Design Stress for Steel | D1-4 |
| D1-2 Resistance Expressions for Steel Structural Elements | D1-7 |

FIGURE

| | |
|---|-------|
| D1-1 Steel Plate/Sheet Design Chart | D1-11 |
|---|-------|

CONTENTS

| | |
|---|-------|
| Introduction | D1-1 |
| Design in Steel | D1-1 |
| Stability Limitations | D1-3 |
| Structural Steel Material Properties | D1-3 |
| Resistance Expressions | D1-3 |
| Applications | D1-9 |
| A. Allowable Stresses | D1-9 |
| B. One-Way Flat Plate Closures, Simple Supports | D1-9 |
| C. Correction Factors for Other Steels | D1-12 |
| D. Correction Factors for Two-Way Plates | D1-12 |
| NOTATION | D1-13 |
| REFERENCES | D1-15 |

Appendix D1

BLAST-RESISTANT DESIGN/ANALYSIS OF STEEL MEMBERS¹

Introduction

It is expected that the reader/user of this appendix will have first read Appendix A containing information applicable to blast-resistant design/analysis generally. This appendix provides information specific to such design/analysis using steel plates and rolled shapes.

As before (Appendix A), useful material developed by Newmark [1]² is included in quotes below (parenthetical insertions or connective words are by this writer).

Design in Steel

"(Blast-resistant) designs in structural steel . . . are based on plastic design principles. For members responding primarily in flexure, if the sections are sufficiently ductile to permit redistribution of moment after the first inelastic action begins, the yield moment is taken as the fully plastic moment of the cross-section.

"Structural carbon steel, i.e., ASTM A-7, A-36, or A-373, possesses a high degree of ductility and strain hardens markedly. Therefore, the zones of inelastic behavior in structural elements formed of these alloys will be widespread. A ductility factor (μ) in flexure of 10 has been used for design in these alloys.

"Higher strength steels . . . have less ductility and strain harden less than the above mild steels. The zones of inelastic behavior will be more limited in extent with limited plastic hinge rotational capacity. Therefore, a ductility factor of no more than 3 is recommended for designs of flexural members in these materials.

"Compression members should be designed for a ductility factor of 1.3. Tension members may be designed with the ductility factor appropriate for the material in flexure.

¹ Flat Plate/Sheet, Corrugated, and Builtup Sections.

² Brackets are used herein to indicate sources in the References list at the end of this appendix.

Stability Limitations

"In order that the yielded cross-section of a member continue to transmit the fully plastic moment through large rotations of the plastic hinge, limitations are placed on the cross-sectional dimensions to insure stability against buckling. Two types of instability are important for flexural members: (1) local buckling of elements of the section, and (2) lateral buckling of the compression flange. Lateral buckling is not commonly a problem for (floor or) door elements since the compressive flanges will ordinarily have continuous lateral support. However, in instances where compression flanges are (laterally) supported, the stability of the member should be evaluated following the procedures given in Reference [2]. . . . It is noted that tests have shown a lessened tendency towards buckling for rapid load application; therefore, the usual specified minimum values for yield stress may be used as the required stress level in equations for stability. . . .

"The following limitations on the dimensions of ASTM A-7, A-36, or A-373 steel sections are taken from Reference [2]. The relations are based on an axial yield stress level of 33 ksi, but tests have shown that sections meeting these requirements perform satisfactorily under rapid loading in spite of the increased yield point.

"Stability Requirement for A-7, A-36 and A-373 Steel Sections

Compression flange of WF, I or H section $b/t_f \leq 17$

Web in shear $d/w \leq 43$

where:

b = flange width (in.)

d = depth of section (in.)

t_f = flange thickness (in.)

w = web thickness (in.)

"Interaction expression for more complex stress states are given in Reference [2] which also contains more general expressions which must be used to set stability limitations on the dimensions of sections fabricated of higher strength steel.

"The structural resistance is defined by the yield level and the ductility. The product of these quantities is a measure of the energy absorption capacity of the structure. Continuity of structural elements provides an increased energy absorption capacity and should be provided where practicable in metal blast-resistant structures. To attain continuity, joints should be designed to develop the full flexural or axial capacity of the member; otherwise, deformations will be concentrated at the joints and the overall ductility of the element will be reduced.

"Welded construction can readily provide structural continuity. However, approved welding procedures, good weld and fabrication details, properly selected welding rods, and weldable base metal are essential if brittle response is to be avoided. Riveted or bolted joint details should be free of sheared edges and punched holes, and adequate edge distances should be provided.

Structural Steel Material Properties

"The (dynamic) design stresses (Table D1-1) are based on the yield strengths for the loading rate range expected in protective construction (References [1,3]).

Resistance Expressions

"The equations involved in the evaluation of the resistance of structural (steel) elements . . . are presented in . . . Table D1-2. These expressions define the flexural resistance, shearing resistance, (effective) natural period (of vibration) in flexure, and (centerline) yield deflection. The design stresses to be used with these expressions are in Table D1-1."

Table D1-1A

DESIGN STRESSES FOR STEEL

| Steel | Axial Stress f_{dy} , ksi | Shearing Stress v_{dy} , ksi | Allowable Bearing Stress | |
|---|-----------------------------------|--------------------------------------|--------------------------------|--------------------------------|
| | | | Single Shear f_{by} , ksi | Double Shear f_{by} , ksi |
| Structural Carbon, ¹ ASTM A-7, A-36, or A-373 | 42 | 25 | | |
| Corrugated Iron ² | 34 | 20 | | |
| Welds | 42 | 29 | | |
| Rivets ASTM A-141 | 40 | 30 | 60 | 80 |
| ASTM A-195 | 60 | 40 | 80 | 80 |
| Bolts ASTM A-307 | 32 | 19 | 40 | 40 |
| ASTM A-325 | 50 | 30 | 60 | 60 |

¹For higher strength structural steels, use an axial design stress, f_{dy} , equal to the smaller of 1.10 times the specified minimum yield or 0.90 times the specified minimum ultimate strength. For design shearing stress, v_{dy} , use 0.60 f_{dy} . (See facing page.)

²The value of f_{dy} has been selected to be used with a plastic modulus, Z , of 1.5 times the section modulus, S .

Source: Ref. 1, p. 153

Table D1-1B

| Steel | Yield Tens.* ksi | Ult. Tens.* ksi | Axial Stress f _{dy} , ksi | Shearing Stress v _{dy} , ksi |
|---------------------------------|------------------------|-----------------------|--|---|
| <u>Carbon:</u> | | | | |
| A529 | 42 | 60-85 | 50 | 25 |
| <u>High-Strength Low-Alloy:</u> | | | | |
| A242 (to 3/4" th. incl.) | 50 | 70 | 55 | 33 |
| A440 " | " | " | " | " |
| A441 " | " | " | " | " |
| A572 (to & incl., th.): | | | | |
| Grade 42 (4") | 42 | 60 | 46 | 28 |
| " 45 (1½") | 45 | 60 | 50 | 30 |
| " 50 (1½") | 50 | 65 | 55 | 33 |
| " 55 (1½") | 55 | 70 | 61 | 36 |
| " 60 (1") | 60 | 75 | 66 | 40 |
| " 65 (¾") | 65 | 80 | 72 | 43 |
| A588 (to 4" th. incl.) | 50 | 70 | 55 | 33 |

*Source: Manual of Steel Construction, 7th edition, 1970, American Institute of Steel Construction, Chicago; p. 5-212 thru -216.

NOTATION FOR TABLE D1-2

α = L_s/L_l (design as 1-way in short direction for $\alpha < \frac{1}{2}$)

A = total area of element, in²

A/b = A per inch width, in.

b = width of element of section, in.

d = depth of structural element, in.

E = elastic Youngs modulus, psi

f_{dy} = dynamic tensile yield stress, psi

I = moment of inertia of element, in⁴

I/b = I per inch width, in³

$k_1 = (77 + 180 \alpha^3) \frac{Et^3}{12L_s^4}$, psi/in

$k_2 = (307 + 500 \alpha^3) \frac{Et^3}{12L_s^4}$, psi/in

$K_\alpha^2 = 3 - 2\alpha\sqrt{\alpha^2 + 3} + 2\alpha^2$

L = 1-way plate span, in.

L_l = 2-way long span, in.

L_s = 2-way short span, in.

S = section modulus of element, in³

S/b = S per inch width, in²

t = plate thickness, in.

t_w = total web thickness of element, in.

v_{dy} = dynamic shearing yield stress, psi

W = plate weight, psf

Z = plastic modulus of section, in³

$Z \approx 1.5 S$ for corrugated plate
1.15 S for I or WF section

Z/b = Z per inch width, in²

Source: Ref. 1, p. 158

Table D1-2

RESISTANCE EXPRESSIONS FOR STEEL STRUCTURAL ELEMENTS

| | Flexure q_y , psi | Shear q_y , psi | Period in Flexure T , sec. | Yield Defl. at d_y , x_y in |
|--------------------------------|--|--|---|---|
| FLAT PLATE SECTION | | | | |
| <u>1-way</u> Simple Support | $2f_{dy} \left(\frac{t}{L}\right)^2$ | $2v_{dy} \left(\frac{t}{L}\right)$ | $9.4 \times 10^{-3} L^2 \sqrt{\frac{W}{Et^3}}$ | $\frac{5}{32} \frac{q_y L^4}{Et^3}$ |
| Fixed Support | $4f_{dy} \left(\frac{t}{L}\right)^2$ | $2v_{dy} \left(\frac{t}{L}\right)$ | $4.1 \times 10^{-3} L^2 \sqrt{\frac{W}{Et^3}}$ | $\frac{q_y L^4}{25.6 Et^3}$ |
| <u>2-way</u> Simple Support | $6f_{dy} \left(\frac{t}{K_\alpha L_s}\right)^2$ | $2v_{dy} \frac{t}{L_s} \left[\frac{2}{3}(1+\alpha)\right]$ | $2.2 \times 10^{-2} \sqrt{\frac{W}{k_1}}$ | $\frac{q_y}{k_1}$ |
| Fixed Support | $12f_{dy} \left(\frac{t}{K_\alpha L_s}\right)^2$ | $2v_{dy} \frac{t}{L_s} \left[\frac{2}{3}(1+\alpha)\right]$ | $1.9 \times 10^{-2} \sqrt{\frac{W}{k_2}}$ | $\frac{q_y}{k_2}$ |
| CORRUGATED SECTION | | | | |
| <u>1-way</u> Simple Support | $\frac{8f_{dy}}{L^2} \frac{Z}{b}$ | $\frac{2v_{dy}}{L} \frac{A}{b}$ | $2.7 \times 10^{-3} L^2 \sqrt{\frac{W}{E} \frac{b}{I}}$ | $\frac{5}{384} \frac{q_y L^4}{E} \frac{b}{I}$ |
| Fixed Support | $\frac{16f_{dy}}{L^2} \frac{Z}{b}$ | $\frac{2v_{dy}}{L} \frac{A}{b}$ | $1.2 \times 10^{-3} L^2 \sqrt{\frac{W}{E} \frac{b}{I}}$ | $\frac{q_y L^4}{207 E} \frac{b}{I}$ |
| BUILT-UP SECTION | | | | |
| <u>1-way</u> Simple Support | $\frac{8f_{dy}}{L^2} \frac{Z}{b}$ | $2v_{dy} \frac{dt_w}{bL}$ | $2.7 \times 10^{-3} L^2 \sqrt{\frac{W}{E} \frac{b}{I}}$ | $\frac{5}{384} \frac{q_y L^4}{E} \frac{b}{I}$ |
| Fixed Support | $\frac{16f_{dy}}{L^2} \frac{Z}{b}$ | $2v_{dy} \frac{dt_w}{bL}$ | $1.2 \times 10^{-3} L^2 \sqrt{\frac{W}{E} \frac{b}{I}}$ | $\frac{q_y L^4}{307 E} \frac{b}{I}$ |

Source: Ref. 1, p. 159

Applications

This section is limited to use of steel sheets and plates as barriers, especially as closures to prevent exterior air blast from entering the basement shelter. However, data useful for other steel applications, such as use of corrugated steel sheets, builtup sections, welds, rivets and bolts, are included elsewhere herein.

It is assumed that the reader/user has reviewed Appendix A herein.

Local availability of steel sheets, plates, and shapes is discussed below in Appendix E1.

A. Allowable Stresses

Allowable stresses for blast-resistant design are shown in Table D1-1. For design of sheet/plate closures, one needs a value for f_{dy} for the particular available steel planned for use, based on its specific ASTM specification number. The f_{dy} value should be in psi (ksi value times 1000 equals the psi value), and is used for both the axial and flexural allowable stresses. (Allowable shear stress v_{dy} is not needed for the applications contemplated herein.)

For an illustrative example: assume A36 steel for use; f_{dy} is 42 ksi (Table D1-1A) or 42,000 psi.

B. One-way Flat Plate Closures, Simple Supports

This design situation applies when the closure sheet or plate is simply supported (i.e., not clamped) on two opposite edges only. The applicable basic formula is the first one of Table D1-2; q_y is found, using known values of plate thickness t (in.) and the clear span L (in.) between supports. Also used is the formula relating p_{dm} (peak value of the blast pressure that can be resisted by the steel plate closure, psi) to q_y and the ductility factor μ .³

Graphic solutions for these combined (two) formulas, for A7/A36/A373 steels in thicknesses of 16 gage (0.06 in.) and 1/8" to 3/4", are shown in Figure D1-1, which is accompanied by a table of correction factors that is discussed further below.

Continuing our example: for 3/4" th. plate and clear span L of 50 in., read $p_{dm} = 18$ psi in Figure D1-1. (Curves of Figure D1-1 are ended arbitrarily at peak p_{dm} value of 50 psi and peak plate weight of about 500 pounds (for square plate of length L on each side).)

³ See third paragraph of earlier section on "Design in Steel" where $\mu = 10$ is recommended for carbon steels and $\mu = 3$ for higher strength steels.

CORRECTION FACTORS FOR FIGURE D1-1

For Carbon Steels

| <u>ASTM-</u> | <u>Factor</u> |
|--------------|---------------|
| A7 | 1.000 |
| A36 | 1.000 |
| A373 | 1.000 |
| A529 | 1.190 |

For High-Strength Steels

| <u>ASTM-</u> | <u>Factor</u> |
|--------------|---------------|
| A242 | 1.149 |
| A440 | 1.149 |
| A441 | 1.149 |
| A572 | |
| Grade 42 | 0.961 |
| " 45 | 1.044 |
| " 50 | 1.149 |
| " 55 | 1.274 |
| " 60 | 1.378 |
| " 65 | 1.504 |
| A588 | 1.149 |

For Two-way Plates

| Ratio of longer to shorter clear spans, L_1 / L_s | <u>Factor</u> |
|---|---------------|
| 1.0 | 3.000 |
| 1.1 | 2.736 |
| 1.2 | 2.531 |
| 1.3 | 2.366 |
| 1.4 | 2.232 |
| 1.5 | 2.121 |
| 1.6 | 2.028 |
| 1.7 | 1.948 |
| 1.8 | 1.879 |
| 1.9 | 1.820 |
| 2.0 | 1.768 |
| > 2.0 | 1.000 |




Figure D1-1 STEEL PLATE/SHEET DESIGNS (One-way, Simple Supports)

C. Correction Factors for Other Steels

Correction factors for use with Figure D1-1 are shown in a table accompanying the figure; they allow use of all other steels listed in Table D1-1, each with the appropriate ductility factor μ as discussed above. The figure is used as described just above, then the p_{dm} value obtained is multiplied by the correction factor for the steel used.

Continuing our example: for the same plate and span, but this time with A529 steel: p_{dm} of 18 psi is multiplied by the correction factor of 1.190 for A529 steel, giving a corrected $p_{dm} = 18 \times 1.190 = 21.4$ psi.

D. Correction Factors for Two-way Plates

Correction factors for use with Figure D1-1 are shown in the same accompanying table, and cover use of a two-way plate simply supported on all four edges, instead of the one-way simply supported plate that is the basis for the Figure. These correction factors vary with the ratio of longer clear span to shorter clear span, or L_L/L_S .

Continuing our example: using a two-way simply supported plate instead of one-way, shorter and longer clear spans are 50 and 60 in., respectively; use the shorter span with Figure D1-1 and read the same 18 psi for p_{dm} ; A529 steel dictates using a correction factor of 1.190 (as above); correcting for two-way versus one-way plates inserts another correction factor, that for $L_L/L_S = 60/50 = 1.2$, or a factor of 2.531 from the table accompanying the Figure. Putting this together:
 $p_{dm} = 18 \times 1.190 \times 2.531 = 54.2$ psi.

NOTATION

(Excluding notation defined there and used in Tables D1-1 and D1-2)

b = flange width (in.)

d = depth of section (in.)

ksi = kips (kilo-pounds) per square inch (1 kip = 1,000 psi)

psi = pounds per square inch

p_{dm} = peak air blast pressure applied to member, psi

t_f = flange thickness (in.)

w = web thickness (in.)

μ = x_m/x_e = the ductility factor (see Appendix A)

REFERENCES

1. Newmark, N. M., Design of Openings for Buried Shelters, Report 2-67, U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi, July 1963; Chapter 7.
2. Commentary on Plastic Design in Steel, Manual of Engineering Practice No. 41, American Society of Civil Engineers (ASCE), New York, New York, 1961.
3. Anderson, F. E., Jr., R. J. Hansen, H. L. Murphy, N. M. Newmark, and M. P. White, Design of Structures to Resist Nuclear Weapons Effects, ASCE Manual of Engineering Practice No. 42, 1961, and Supplement 1963 (combined into a "1964 Edition").

Appendix E1

STRUCTURAL STEEL LOCAL AVAILABILITY AND USE
FOR BLAST SHELTER UPGRADING

By: Ellis E. Pickering, P.E.
Senior Civil Engineer

CONTENTS

| | |
|--|-------|
| Introduction and Purpose | E1-1 |
| Shapes, Sizes, and Designations | E1-1 |
| A. Introduction | E1-1 |
| B. Structural Steel Plate | E1-2 |
| C. Rolled Structural Shapes | E1-2 |
| D. Pipe and Structural Tubing | E1-4 |
| E. Other Structural Steel Materials | E1-7 |
| Material Strength Grades | E1-9 |
| Principles of Use and Application | E1-10 |
| A. General Principles | E1-10 |
| a. Expedient Applications | E1-10 |
| b. Engineered Applications | E1-11 |
| B. Potential Applications | E1-11 |
| Local Availability | E1-11 |
| A. Manufacturing and Distribution System | E1-11 |
| B. Typical Availability | E1-15 |
| Dimensioning Practice For Rolled Structural Shapes | E1-18 |
| A. Wide-Flange Beams and Columns (W and HP Shapes) | E1-18 |
| B. Standard "I" Beams (S Shapes) | E1-18 |
| C. Channels (C and MC Shapes) | E1-19 |
| D. Angles (L Shapes) | E1-19 |
| E. Tees (MT, St, and Wt Shapes) | E1-19 |
| REFERENCES | E1-20 |

TABLES

| | | |
|------|---|-------|
| E1-1 | ROLLED STEEL SHAPES - DESIGNATIONS AND SIZES | E1-3 |
| E1-2 | SELECTED PIPE SIZES - DIMENSIONS AND WEIGHTS | E1-5 |
| E1-3 | STRUCTURAL TUBING SIZES - DIMENSIONS AND WEIGHTS | E1-6 |
| E1-4 | TYPICAL RR RAIL SECTIONS - DIMENSIONS AND WEIGHTS | E1-8 |
| E1-5 | TYPICAL SHEET PILE SECTIONS - DIMENSIONS AND WEIGHTS | E1-8 |
| E1-6 | POTENTIAL APPLICATIONS OF STRUCTURAL STEEL MATERIALS TO BLAST SHELTER UPGRADING | E1-12 |
| E1-7 | TYPICAL AVILABILITY OF STRUCTURAL STEEL MATERIALS AT REGIONAL WAREHOUSES AND LOCAL SUPPLIERS | E1-16 |

Appendix E1

STRUCTURAL STEEL LOCAL AVAILABILITY AND USE FOR BLAST SHELTER UPGRADING

Introduction and Purpose

Among the various materials useful for construction of closure systems for blast shelters and for strengthening the floor over such shelters, are the standard structural steel products including plates, structural shapes including "I" beams and channels, structural tubing, and pipe.

These materials are those normally used in the structural framing for buildings, bridges, industrial plants, and for other heavy construction purposes. Structural steel materials are stocked rather widely on a regional and local basis.

Structural steel materials may be used for "expedient" or "engineered" upgrading of potential blast shelters. Usually such uses will involve provision of closure or strengthening of floor systems, or most likely both. Structural steel materials will be particularly useful, and in many cases required, for provision of the higher levels of blast protection, or where closure or floor spans are long.

Design guidance for the use of structural steel products in both expedient and engineered blast shelter upgrading is given elsewhere in this report (main text and Appendix D1). The purpose of this appendix is to describe the general characteristics and uses of these materials and to identify sources of supply, together with typical regional and local availability.

The reader desiring more detailed information on structural steel should refer to standard references [e.g., 1],¹ or consult with a Professional Civil or Structural Engineer. Actual designs should be prepared by professional engineers if time is available.

Shapes, Sizes, and Designations

A. Introduction

Structural steel materials considered include plate, rolled shapes, pipe and structural tubing, sheet piling, and railroad rail. Standard shapes, sizes, and designations are discussed for each in the following paragraphs.

¹ Brackets are used herein to indicate sources in the References list at the end of this appendix.

B. Structural Steel Plate

Structural steel plate is manufactured in a variety of thicknesses, widths, and lengths. Materials are designated as strip, bar, or plate depending on the relationship of thickness to width. For the purposes of the present applications, the useful materials are limited to the bar and plate designations of 1/4" thickness or more, which are grouped in thickness and width classifications as follows: Nominal thicknesses (in.) are 1/4, 5/16, 3/8, 7/16, 1/2, 5/8, 3/4, and 1, within which widths of 3-1/2" to 8" are bars and over 8" are plates.

C. Rolled Structural Shapes

Hot rolled structural steel shapes include products formerly referred to as "I" Beams, "Wide Flange" or "WF" Beams, "H" Beams, Channels, and Tees. The present standard designation system (together with the former system) and size ranges are given in Table E1-1.

The designation system shown in Table E1-1 is a method of identification for shapes and sizes of rolled structural steel shapes, employing a standard nomenclature. Its primary use is as a form of abbreviation for identification on drawings, but it is also recognized throughout the trade including sources of supply. The present designation includes three items: (1) type, shape, or group symbol; (2) nominal shape, depth

and (3) the weight in pounds per linear foot (except for angles, where the thickness of the metal is given instead).

The designation system was changed in 1970 [1]. Both the current and former designation systems are given in Table E1-1 since older tables and drawings are still in use.

² Actual dimensions differ significantly from nominal dimensions for some shapes. See the last section of this appendix for further explanation.

Table E1-1

ROLLED STEEL SHAPES - DESIGNATIONS AND SIZES

| Generic Type or Group | Example Designation | | Size Ranges | |
|-------------------------------------|---------------------|----------|-------------|------------|
| | Present | Former | From | To |
| <u>Beams and Columns</u> | | | | |
| Wide Flange Beams and Columns | W8x40 | 8WF40 | W8x20 | W36x300 |
| Standard "I" Beams | S8x23 | 8I23 | S3x7.5 | S24x120 |
| Light Wide Flange Columns | W6x20 | 6WF20 | W4x13 | W6x25 |
| Light Beams | W10x15 | 10B15 | W6x16 | W16x31 |
| Miscellaneous Columns | M6x25 | 6M25 | M4x13 | M8x34.3 |
| Junior Beams | M10x9 | 10Jr9 | M6x4.4 | M12x11.8 |
| Miscellaneous Shapes | M8x20 | 8M20 | M8x22.5 | M10x29.1 |
| <u>"H" Shaped Bearing Piles</u> | HP12x74 | 12BP74 | HP12x63 | HP14x117 |
| <u>Structural Channels</u> | | | | |
| Standard Channels | C10x30 | 10C30 | C3x6 | C15x50 |
| Miscellaneous Channels | MC12x45 | 12x4C45 | MC8x18.7 | MC18x58 |
| Junior Channels | MC10x8.4 | 10JrC8.4 | MC10x6.5 | MC12x10.6 |
| <u>Structural Angles</u> | | | | |
| Equal Leg Angles | L5x5x3/4 | 45x5x3/4 | L3x3x3/16 | L8x8x1-1/8 |
| Unequal Leg Angles | L6x4x3/4 | 46x4x3/4 | L3x2x3/16 | L9x4x1 |
| <u>Structural Tees</u> | | | | |
| Cut from Wide Flange Shapes | WT8x25 | ST8WF25 | WT4x8.5 | WT18x150 |
| Cut from Standard "I" Beams | ST6x25 | ST6I25 | ST3x6.3 | ST12x60 |
| Cut from Miscellaneous Shapes | MT5x10.5 | ST5M10.5 | MT4x8.5 | MT5x14.6 |
| Cut from Light Beams | WT7x13 | ST7B13 | WT3x4.3 | WT8x15.5 |
| Cut from Junior Beams | MT6x5.9 | ST6Jr5.9 | MT3x2.2 | MT6x5.9 |

Examples of the full description of products under the present and former systems follow:

W8x40 - A Wide Flange Beam or column (W) of 8" depth and weighing 40 pounds per foot.

S8x23 - A standard "I" Beam (S) of 8" depth and weighing 23 pounds per foot.

C10x30 - A standard Channel (C) of 10" depth and weighing 30 pounds per foot.

L5x5x3/4 - An equal leg Angle (L) of 5"x5" dimensions (outer faces) and 3/4" thickness.

ST6x25 - A structural Tee cut from a standard "I" Beam (S) of 6" depth and weighing 25 pounds per foot.

Certain special structural shapes have not been included in Table E1-1 because of their limited availability. These include special car building and ship building Channels, bulb Angles, Zees, and small rolled Tee Beams. Sizes and shapes of the car building and ship building Channels are given in Reference [1]. Details on other special shapes can be found in manufacturers' catalogs.

D. Pipe and Structural Tubing

Steel pipe (circular section) is manufactured in standard sizes ranging from 1/8" to 12" nominal diameter in standard, extra strong, and double extra strong weights. The nominal diameter is an approximation of the inside diameter of the pipe in the larger sizes of standard weight. The extra strong and double extra strong weights have reduced inside diameters corresponding to the increased wall thicknesses.

Dimensions of selected sizes and weights of steel pipes are given in Table E1-2.

Structural tubing (square or rectangular section) is manufactured in sizes up to 12" in major dimension. Selected sizes and weights are given in Table E1-3.

Table E1-2
SELECTED PIPE SIZES - DIMENSIONS AND WEIGHTS

| Nominal Diameter (in.) | Outside Diameter (in.) | Inside Diameter (in.) | | | Wall Thickness (in.) | | | Weight Per Foot (lb) | | |
|------------------------------|------------------------------|--------------------------|--------|--------|-------------------------|-------|-------|-------------------------|-------|--------|
| | | S* | ES | DES | S | ES | DES | S | ES | DES |
| 3 | 3.500 | 3.068 | 2.900 | 2.300 | 0.216 | 0.300 | 0.600 | 7.58 | 10.25 | 18.58 |
| 4 | 4.500 | 4.026 | 3.826 | 3.152 | 0.237 | 0.337 | 0.674 | 10.79 | 14.98 | 27.54 |
| 5 | 5.563 | 5.047 | 4.813 | 4.063 | 0.258 | 0.375 | 0.750 | 14.62 | 20.78 | 38.55 |
| 6 | 6.625 | 6.065 | 5.761 | 4.897 | 0.280 | 0.432 | 0.864 | 18.97 | 28.57 | 53.16 |
| 8 | 8.625 | 7.981 | 7.625 | 6.875 | 0.322 | 0.500 | 0.875 | 28.55 | 43.39 | 72.42 |
| 10 | 10.750 | 10.020 | 9.750 | 8.750 | 0.365 | 0.500 | 1.000 | 40.48 | 54.74 | 104.13 |
| 12 | 12.750 | 12.000 | 11.750 | 10.750 | 0.375 | 0.500 | 1.000 | 49.56 | 65.42 | 125.49 |

* Designation: S = Standard Weight
ES = Extra Strong Weight
DES = Double Extra Strong Weight

Table E1-3

STRUCTURAL TUBING SIZES - DIMENSIONS AND WEIGHTS

| Outside Dimensions (in.) | Square Section | | | | | Outside Dimensions (in.) | Rectangular Section | | | | |
|--------------------------------|--|-------|-------|-------|-------|--------------------------------|--|-------|-------|-------|-------|
| | Weight Per Ft (lb) For Various Wall Thicknesses (in.) | | | | | | Weight Per Ft (lb) For Various Wall Thicknesses (in.) | | | | |
| | 1/2 | 3/8 | 5/16 | 1/4 | 3/16 | | 1/2 | 3/8 | 5/16 | 1/4 | 3/16 |
| 12x12 | 74.54 | 57.23 | 48.24 | 39.03 | N/A* | 12x6 | 54.15 | 41.93 | 35.49 | 28.83 | N/A |
| 10x10 | 60.95 | 47.03 | 39.74 | 32.23 | N/A | 10x6 | 47.35 | 36.83 | 31.24 | 25.44 | N/A |
| 8x8 | 47.35 | 36.83 | 31.24 | 25.44 | N/A | 8x6 | 40.55 | 31.73 | 26.99 | 22.04 | 16.85 |
| 7x7 | 40.55 | 31.73 | 26.99 | 22.04 | 16.85 | 8x4 | 34.48 | 27.04 | 23.02 | 18.82 | 14.41 |
| 6x6 | 34.48 | 27.04 | 23.02 | 18.82 | 14.41 | 7x5 | 34.48 | 27.04 | 23.02 | 18.82 | 14.41 |
| 5x5 | 27.68 | 21.94 | 18.77 | 15.42 | 11.86 | 6x3 | N/A | 19.39 | 16.65 | 13.72 | 10.58 |
| 4x4 | N/A | 16.84 | 14.52 | 12.02 | 9.31 | 5x3 | N/A | 16.84 | 14.52 | 12.02 | 9.31 |

* N/A = Not available

E. Other Structural Steel Materials

The materials listed in the previous paragraphs are those generally used in steel building framing, bridges, and industrial applications. In addition to these materials, other structural steel materials may be found to be useful. These include railroad rails and sheet steel piling.

Railroad rails in either a new or used condition offer considerable strength. Most rail is rolled to an American Society of Civil Engineers (ASCE) or an American Railway Engineering Association (AREA) pattern and is classified on both a pattern and weight per yard basis. Table E1-4 lists the properties of selected rail sections.

Sheet steel piling may be available near the coasts and in inland areas near lakes and rivers. It is rolled in several patterns with interlocking edges. Patterns include straight web, arch web, and Zee. Properties of typical sections are given in Table E1-5.

Table E1-4

TYPICAL RR RAIL SECTIONS - DIMENSIONS AND WEIGHTS*

| Weight Per Yard (lb) | Height (in.) | Base Width (in.) | Head Width (in.)# |
|-------------------------|-----------------|---------------------|----------------------|
| 155 | 8 | 6-3/4 | 3 |
| 140 | 7-5/16 | 6 | 3 |
| 132 | 7-1/8 | 6 | 3 |
| 115 | 6-5/8 | 5-1/2 | 2-23/32 |
| 100 | 6 | 5-3/8 | 2-11/16 |
| 75 | 4-13/16 | 4-13/64 | 2-15/32 |

* New Condition

Maximum at bottom of head

Table E1-5

TYPICAL SHEET PILE SECTIONS - DIMENSIONS AND WEIGHTS

| Section | Nominal Width (in.) | Depth (in.) | Thickness Web (in.) | Flange (in.) | Weight Per Ft (lb) |
|---------------|---------------------------|----------------|---------------------------|-----------------|--------------------------|
| Straight Web | 15 | ~ | 1/2 | - | 40 |
| | 15 | ~ | 3/8 | - | 35 |
| Arch Web | 19-5/8 | 3-1/4 | 3/8 | 3/8 | 36 |
| | 16 | 1-11/32 | 1/2 | 1/2 | 37.3 |
| | 16 | 1-11/32 | 3/8 | 3/8 | 30.7 |
| Deep Arch Web | 16 | 6 | 31/64 | 3/8 | 42.7 |
| | 16 | 5 | 3/8 | 3/8 | 36 |
| Zee | 21 | 11-1/2 | 3/8 | 1/2 | 56 |
| | 18 | 12 | 3/8 | 1/2 | 57 |
| | 18 | 12 | 3/8 | 3/8 | 40.5 |

Material Strength Grades

Structural steel is produced in various grades related to strength and weldability as prescribed in American Society for Testing and Materials (ASTM) specifications. Applicable specifications include:

| | |
|-----------|--|
| ASTM A7 | Steel for Bridges and Building |
| ASTM 36 | Structural Steel |
| ASTM A242 | High Strength Low Alloy Structural Steel |
| ASTM A373 | Structural Steel for Welding |
| ASTM A440 | High Strength Structural Steel |
| ASTM A441 | High Strength, Low Alloy Structural Manganese Vanadium Steel |

The principal variation among the types relates to strength as indicated by yield point. All are weldable except A440, which is not recommended for welded use. The yield point specification values (psi) are:

| | |
|------------|--------|
| A7 | 33,000 |
| A36 | 36,000 |
| A242 | 42,000 |
| A373 | 33,000 |
| A440 | 42,000 |
| A441 | 42,000 |
| Rail Steel | 39,000 |

The various standard products are generally produced in grades as follows:

Bar and Plate: A7, A36, A242, A373, A440, A441

Pipe: A7, A36

Railroad Rail: AREA Specification

Rolled Structural Shapes: A7, A36, A242, A373, A440, A441

Sheet Pile: A7, A36

Structural Tubing: A7, A36

Principles of Use and Application

A. General Principles

Structural steel materials are capable of providing relatively high degrees of blast-resistant upgrading as compared to wood; however, they present more difficult problems in fabrication and installation. The principle problems are cutting to size, plus fastening of individual members to each other and to the the basic shelter space structure. The methods of fabrication and installation will vary somewhat between expedient and engineered upgrading applications because of available time and skills.

a. Expedient Applications

The expedient upgrading process will be limited by available time and the skills of the work force. In this process the following general principles should be applied:

(1) The structure (closure, beam support, etc.) should be designed around the material readily available locally.

(2) All cutting to size should be accomplished at the point of supply, where flame cutting, sawing, or shearing may be readily accomplished. On the job cutting would present extreme difficulty, although rough oxyacetylene cutting may be possible if tools and skills are available.

(3) Fastenings should be restricted to simple bolting wherever possible. Bolt holes may be drilled locally although it also would be more efficient to have this done at the point of supply. Fastenings should be designed so as not to be stressed by the blast wave, i.e., the blast wave should add no tension or shear load to the fastenings.

(4) The size and weight of individual structural members should be limited to that which can be handled and erected by a few men without the use of heavy materials-handling equipment.

(5) Advantage should be taken of crisis build-up time to procure pre-cut and pre-drilled material, and to store it for immediate use in the proposed shelter space.

(6) Material strength grades should be limited to A7 or A36 grades wherever possible because of the greater ease in cutting, drilling, or welding.

b. Engineered Applications

The engineered application process permits the utilization of a normal time-frame for design, fabrication, and installation (where desired). The design should be accomplished by a Professional Civil or Structural Engineer and the conventional procurement, fabrication, and installation process should be followed. In this case:

(1) Advantage may be taken of higher strength materials.

(2) More sophisticated fastening systems may be employed to obtain material economy through the use of moment-resisting joints and other economic design features.

(3) Structural welding of subassemblies may be employed, and final erection may also utilize welding, if the structure is to be installed immediately. If the parts of subassemblies are to be stockpiled, however, certain principles listed above for expedient applications - i.e., those related to size, weight, and bolting - should be followed. Such stockpiling is applicable where immediate installation might interfere with the normal use of the proposed shelter space.

B. Potential Applications

Potential applications of structural steel materials in blast shelter upgrading are listed in Table E1-6. For specific design data, member sizing, and blast resistance, see Appendix D1.

Local Availability

A. Manufacturing and Distribution System

Structural steel products are manufactured on a regional basis with major production centers (mills) located in the Ohio Valley, Great Lakes region, Eastern Seaboard (Baltimore), Southeast (Alabama), Rocky Mountain region (Utah and Colorado), and California. In addition, imports are available generally at seaboard locations. The distribution system is from mill to regional warehouses, or to combination warehouse-fabrication yards, with either type owned by the major structural steel producers or large independents. The mill inventory also serves as a regional stock.

The regional network is supplemented by a system of local warehouses and small fabricators, usually of an independent nature. The local facilities obtain their supplies from regional warehouses or direct from mills for large orders.

Table E1-6
POTENTIAL APPLICATIONS OF STRUCTURAL STEEL MATERIALS
TO BLAST SHELTER UPGRADING *

| <u>Material</u> | <u>Potential Application</u> | <u>Application Notes</u> |
|--|--|---|
| <u>Structural Steel Plate</u> | Closure of small openings such as doors, windows, ventilation shafts, utility penetrations in floors, area ways, etc. Covering for structural steel frame closure for large openings. | Provide hold-down by bolting, loading with sand bags, bracing, etc. |
| <u>Rolled Structural Steel Shapes</u> Light-Weight Channels and "I" Beams | Closure of openings in flat-wise position Covering for main structural steel frame closure for large openings Framing to support plate covering for small openings | Tie together by tackwelding, transverse bolting through flanges, etc. Provide hold-down by bolting, loading with sand bags, bracing, etc. |

* Special attention must be given to attachment of closure and support systems to the structural framework of the building under consideration. In many cases the framework will require upgrading.

Table E1-6 (concluded)

| | | |
|---|--|--|
| Wide-Flange Beams, "H" Piles, "I" Beams, Channels, Angles, and Tee Beams | Structural frame to support closures for large openings such as vehicle doors, stairwells, and elevator shafts. Covering may include steel plate, wood planks, stressed skin plywood panels, etc. | Fastenings can be made by welding, drilling, and bolting, etc. Rather precise cutting is required |
| | Columns to strengthen existing columns; or added columns to reduce spans in beams, girders, and slabs. | Requires rather precise cutting to length, or wedging. Top and bottom bearing plates are required. |
| Pipe and Structural Tubing | Columns (see above). Rectangular tubing can be used in flat-wise position for direct closure of openings or for covering structural steel frames for large openings. Rectangular tubing may be used for fabrication of a structural frame for closure of large openings. | (See above). Tie together by tackwelding. Provide hold-down by bolting, covering with sand bags, etc. |
| Other Structural Steel Materials | Closure of openings in base-to-base position. Columns | See notes for flat-wise application. |
| Railroad Rails | Direct closure of openings Covering for structural steel frame for large openings. | See column notes above. Lock edges together. Provide hold-down by tackwelding, bolting, loading with sand bags, etc. |
| Sheet Pile | | |

Imported materials go to the independent regional establishments or to large volume local dealers.

Except in the least populated areas of the country, a regional or local warehouse may be expected to be found within one-day truck distance (say 100 miles) of any population center.

All establishments have capability of some fabrication, the minimum being drilling and cutting to size (flame cutting, shearing or sawing). Most also have welding and grinding facilities for prefabrication to some degree. These capabilities should be used to the maximum to reduce on-site problems.

Many salvage yards also maintain some sizes of both new and used structural shapes in limited quantities.

Railroad rails are usually procured by the railroads in large quantity direct from mills and are stockpiled at division points and other central locations. Both new and re-rail (used) materials may be procured from these sources under emergency conditions. Re-rail from main lines is used by the railroads for the construction of sidings, yards, etc. In some cases re-rail materials are handled by specialty salvage firms to be resold or converted to scrap.

Limited amounts of sheet pile will be found in regional warehouses; however, specialty firms deal in both new and used materials. Sheet pile will be generally found to be more available near the seaboard than elsewhere.

Local sources of structural steel products are easily identified from the yellow pages of telephone directories under the headings of "Steel Distributors and Warehouses," "Steel Fabricators," "Steel Mills," "Steel, Used," etc.

B. Typical Availability

Because of relatively high costs, neither regional nor local sources maintain inventories of all potential sizes and shapes of structural steel products. Large and specialty orders must usually be procured directly on mill order. The stockage will consist of those products and shapes used in relatively large quantities in the area served. These products will generally be limited to those used in the general building work of the area served, usually on medium-sized and smaller buildings, or the equivalent. In a large urban area, however, a fairly wide range of products and sizes would be found among all of the available suppliers. Typical availabilities are indicated in Table E1-7 for "regional warehouses" and for "local suppliers". In all cases, however, availability should be determined before proceeding with design.

Table E1-7

TYPICAL AVAILABILITY OF STRUCTURAL STEEL MATERIALS
AT REGIONAL WAREHOUSES AND LOCAL SUPPLIERS

| Material | Local Suppliers | Regional Warehouses |
|--|---|--|
| <u>Structural Steel Plate</u> | Usually carry a fairly complete stock of thicknesses from 1/4 in. to 3/4 in. and maybe 1 in. Maximum width of 8 ft, lengths to 20 ft. Any size width and length is easily flame cut. Usually limited to A36 steel. | Will carry same as local suppliers in a larger variety of lengths and widths. Thicknesses up to 4 in. may be available. Equipped for production cutting to size. Other grades available. |
| <u>Rolled Structural Steel Shapes</u> Wide Flange Beams and Columns | Will carry a range of depths in 2 in. increments from about 4 in. up to 16 or 18 in. Weights will be limited to one or two in each size range. Lengths to about 40 ft available in the larger sizes. Any length can be cut. Usually limited to A36 steel. | Carry same as local suppliers plus the larger depths to 36 in. in some quantity. Fairly complete range of weights available in each size range. Some high strength grades (A440, A441, and A242) available in most common sizes. Lengths to 60 ft available in most sizes and weights. |
| Standard "I" Beams | Generally carry a range of depths from 6 in. to 12 in. to 15 in. Usually only one weight carried. Lengths to about 40 ft available in the larger sizes. Any length can be cut. Usually carry only A36 grade. | All of the local supplies plus the larger sizes to 24 in. and smaller to 3 in. All weights usually available. Lengths to 60 ft. Higher strength grades usually available. |

Table E1-7 (concluded)

| | | |
|--|---|---|
| Light Wide-Flange Columns and Beams; Junior and Miscellaneous Shapes | Fairly large quantities of the smaller sizes, 8 in. depth and less, will be found because of use in light building construction. Weights will be limited to one per size usually. Lengths available to about 30 ft. Usually only A36 grade available. | Will carry a rather complete range of sizes and weights because of heavy use in building construction. Usually not carried in other than A36 grade. |
| "H" Piles | Usually not carried. | Usually carry complete range of sizes and weights. Longer lengths to 100 ft available in limited quantity. Not carried in other than A36 grade. |
| Standard Channels | Limited quantity of sizes and weights to about 15 in. carried. Lengths to about 40 ft. Any length can be cut. Usually stocked in A36 grade only. | Carry a fairly complete range of depths and weights to 60 ft length. May have higher strength grades. |
| Junior Channels | Usually not carried. | Ordinarily carried in all three sizes. |
| Angles | Fairly complete range of sizes available in the medium and smaller thicknesses. | Will carry same as local supplier plus heavier thicknesses. |
| Tees | Usually not stocked. Cut on order. | Usually not stocked. Cut on order. |
| <u>Pipe and Structural Tubing</u> | Usually not carried by local suppliers. | Carry a range of pipe in Standard (Schedule 40) and Extra Strong (Schedule 80) weights. Lengths to 20 ft. Large size (8 to 12 in.) Double Extra Strong possible. Range of square and rectangular tubing is carried. |

Dimensioning Practice For Rolled Structural Shapes

Dimensions of rolled structural shapes are generally given in nominal form for depth and width. As a result of a variety of factors including economy in the use of rolls, roll wear, roll re-dressing, etc., a substantial variation of actual dimension from the nominal is produced. The greatest variations result from the process of obtaining heavier weights per foot by "spreading the rolls," thus obtaining greater flange and web thicknesses. This practice permits the rolling of a variety of shapes with the same nominal dimensions on the same set of rolls. Any design or use of structural steel shapes for blast shelter upgrading purposes requires attention to the actual dimensions of the section as opposed to the nominal dimensions. Both nominal and actual (within rolling tolerances) dimensions of the available rolled shapes in the various weights are given in Reference [1], as well as in American Society of Civil Engineers and mill literature. Dimensioning practice varies with the type of shape and is summarized in the following paragraphs.

A. Wide-Flange Beams and Columns (W and HP Shapes)

For a given nominal depth (outside-to-outside of flanges dimension), there is a constant (inside-to-inside) dimension between flanges. The latter remains constant while the former varies with the weight of the section. For example, a W12 section has a constant actual inside flange dimension of about 10-7/8" (actual 10.908") for weights of 40 lb/ft and heavier, while the actual outside depth ranges from 11-7/8" to 14-3/8" with increasing weights per foot. The flange width also varies with the weight, being 8" for a 40 lb/ft section (W12x45) and 12-5/8" for a 190 lb/ft section (W12x190) [1(p.1-17 and 1-38)].

B. Standard "I" Beams (S Shapes)

Differing from wide-flange beam practice, standard "I" Beams are rolled with the actual depth (outside-to-outside of flanges dimension) being equal (within mill tolerances) to the nominal depth. Thus the nominal outside-to-outside depth is the constant, rather than the inside-to-inside depth as in the case of the wide-flange sections. Weight per foot variations result in changes in web thickness and flange width. Thus an 8x4 "I" Beam of 18.4 lb/ft (S8x18.4) has a web thickness of 1/4", a flange (maximum) thickness of 7/16" and a flange width of 4". Increasing the weight to 23 lb/ft (S8x23) results in a web thickness of 7/16" and a flange width of 4-1/8" while the flange thickness remains at 7/16" and the actual depth at 8".

C. Channels (C and MC Shapes)

Standard Channels are rolled and dimensioned in a similar manner to standard "I" Beams with the actual depth (outside-to-outside of flanges dimension) being constant and equal to the nominal depth. For each depth, increased weights result in increased web thickness and flange width while the flange thickness remains constant.

D. Angles (L Shapes)

Variation in weight per foot for Angles is obtained by uniform increase of thickness of legs.

E. Tees (MT, ST, and WT Shapes)

Since Tees are cut from the various beam shapes indicated, dimensioning practice follows that of the basic shape.

REFERENCES

1. Manual of Steel Construction, American Institute of Steel Construction, Inc., Wrigley Building (8th Floor), 400 North Michigan Avenue, Chicago, Illinois 60611; 7th edition, 1970. Note: A later edition is now available.

DISTRIBUTION LIST

Federal Emergency Management Agency
Mitigation and Research
ATTN: Administrative Officer
Washington, D.C. 20472 (60)

Defense Technical Information Center
Cameron Station
Alexandria, VA 22314 (12)

AFWL/Civil Engineering Division
ATTN: Technical Library
Kirtland Air Force Base, N.M. 87117

Assistant Secretary of the Army (R&D)
ATTN: Assistant for Research
Washington, D.C. 20301

Director, U.S. Army Engineer Waterways
Experiment Station
Postoffice Box 631
Vicksburg, Mississippi 39180

Director, Army Materials & Mechanics
Research Center
ATTN: Technical Library
Watertown, Mass. 02170

Director
Ballistic Research Laboratory
ATTN: Document Library
Aberdeen Proving Ground, MD 21005

Defense Logistics Agency
Civil Preparedness Office
Richmond, VA 23297

Director, Defense Nuclear Agency
ATTN: Technical Library
Washington, D.C. 20305

Mr. Samuel Kramer, Chief
Office of Federal Building Technology
Center for Building Technology
National Bureau of Standards
Washington, D.C. 20234

Chief of Naval Research
Washington, D.C. 20306

Dr. Leon Goure
Advanced International Studies, Inc.
Suite 1122, East-West Towers
4330 East-West Highway
Washington, D.C. 20014

Mr. Donald A. Bettge
Mitigation and Research
Federal Emergency Management Agency
1725 I Street, N.W.
Washington, D.C. 20472

Mr. Phillip M. Smith, Assoc. Director
Natural Resources & Commercial Services
Office of Scientific & Technology Policy
Executive Office Building
Washington, D.C. 20500

Civil Engineering Center/AF/PRECET
ATTN: Technical Library
Wright-Patterson Air Force Base
Dayton, Ohio 45433

Director, U.S. Army Engineer Waterways
Experiment Station
ATTN: Document Library
Postoffice Box 631
Vicksburg, Miss. 39180

Ballistic Research Laboratory
ATTN: Librarian
Aberdeen Proving Ground, MD 21005

Department of Energy
Headquarters Library, G-49
Washington, D.C. 20545

Department of Energy
Assistant Director for Field Operations
Department of Military Application
Washington, D.C. 20545 (1)
ATTN: Civil Effects Branch
Mr. L. J. Deal
Dr. Rudolph J. Engelmann

Director, Defense Nuclear Agency
ATTN: Mr. Tom Kennedy
Washington, D.C. 20305

Dr. Lewis V. Spencer
Radiation Theory Section 4.3
National Bureau of Standards
Washington, D.C. 20234

Commanding Officer
U.S. Naval Civil Engineering Laboratory
ATTN: Document Library
Port Hueneme, CA 93041

Agbabian Associates
250 North Nash Street
El Segundo, CA 90245

DISTRIBUTION LIST (continued)

Bell Telephone Laboratories
Whippany Road
Whippany, N. J. 07981
ATTN: Mr. E. Wilt
Mr. R. May
Mr. J. Foss

Mr. James E. Beck
James E. Beck and Associates
4216 Los Palo Avenue
Palo Alto, CA 94306

GARD, Inc.
7449 North Natchez Avenue
Niles, Illinois 60643

Dr. William Chenault
Human Science Research, Inc.
Westgate Industrial Park
7710 Old Springhouse Road
McLean, VA 22102

Dr. Leo Schmidt
Institute for Defense Analyses
400 Army-Navy Drive
Arlington, VA 22202

Los Alamos Scientific Laboratory
ATTN: Document Library
Los Alamos, N.M. 87544

Dr. Charles Fritz
National Academy of Sciences
2101 Constitution Avenue
Washington, D.C. 20418

Oak Ridge National Laboratory
ATTN: Librarian
Postoffice Box X
Oak Ridge, Tenn. 37830

Nuclear Engineering Department
Duncan Annex
Purdue University
West Lafayette, Indiana 47907

Mr. Edward L. Hill
Research Triangle Institute
Postoffice Box 12194
Research Triangle Park, N.C. 27709

Dr. Clarence R. Mehl
Division 1112
Sandia National Laboratories
Box 5800
Albuquerque, N. M. 87185

Mr. Chuck Wilton
Scientific Service, Inc.
517 East Bayshore
Redwood City, CA 94063

Dr. Richard K. Laurino
Center for Planning and Research, Inc.
2483 East Bayshore Rd. (Suite 209)
Palo Alto, CA 94303

Dikewood Industries, Inc.
1613 University Blvd., N. E.
Albuquerque, N.M. 87102

University of Florida
Civil Defense Technical Services Center
College of Engineering
Department of Engineering
Gainesville, Florida 32601

Mr. Jack C. Greene
Greenwood
Route 4, Box 85A
Bakersville, N. C. 28705

Dr. Anatole Longinow
IIT Research Institute
10 West 35th Street
Chicago, Illinois 60616

Mr. Ken Kaplan
30 White Plains Court
San Mateo, CA 94402

H. L. Murphy Associates
Box 1727
San Mateo, CA 94401

Emergency Technology Division
Oak Ridge National Laboratory
Postoffice Box X
Oak Ridge, Tenn. 37830
ATTN: Librarian

Disaster Research Center
Ohio State University
404B West 17th Avenue
Columbus, Ohio 43210

The RAND Corporation
ATTN: Document Library
1700 Main Street
Santa Monica, CA 90401

Sandia National Laboratory
Box 5800
Albuquerque, N.M. 87185

Science Applications, Inc.
1710 Goodridge Drive
Postoffice Box 1303
McLean, VA 22102

Technology & Management Consultants
1850 North Whitley Avenue (Suite 916)
Hollywood, CA 90028

DISTRIBUTION LIST (concluded)

Dr. F. J. Agardy
c/o URS Corporation
155 Bovet Road
San Mateo, CA 94402

Mr. Thomas P. Carroll
Carroll Associates
7910 Woodmont Av., Suite 1012
Bethesda, Maryland 20014

R. W. Hubenette, P.E.
Robert W. Hubenette and Associates
517 East Bayshore
Redwood City, CA 94063

National Forest Products Association
ATTN: Technical Director
1619 Massachusetts Avenue, N.W.
Washington, D.C. 20036 (2)

Mr. John R. Rempel
c/o Center for Planning and Research
2483 East Bayshore, Suite 209
Palo Alto, CA 94303

D. E. Leitner (2)
J. E. Trevor (1)
E. E. Duckstad (1)
SRI International
Menlo Park, CA 94025

American Plywood Association
ATTN: Wm. A. Baker, P.E., Head
Engineering Service
Applied Research Department
7011 South 19th Street
Postoffice Box 11700
Tacoma, Washington 98411 (2)

Dr. Wm. J. Hall
Civil Engineering Building
University of Illinois
Urbana, Illinois 61801

Mr. Jack R. Janney
330 Pfinsten Road
Northbrook, Illinois 60062

Ellis E. Pickering, P.E.
1015 Trinity Drive
Menlo Park, CA 94025

Carl K. Wiehle, P.E.
3311 Fallowfield Drive
Falls Church, VA 22042

UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS:
PREDESIGNED EXPEDIENT OPTIONS II

(UNCLASSIFIED)

By: H. L. Murphy*

SRI International (formerly Stanford Research Institute)
Menlo Park, California 94025, July 1980, 272 pages
Contract No. DCPA01-77-C-0227, FEMA Work Unit 1155C (SRI Project 6876)

This report covers the results of the latest phase of a 3-phase project, with the overall objective of developing a set of expedient and engineered techniques, for upgrading the air blast and related effects resistance potential of basements in existing buildings. The purpose of upgrading such basement spaces is to provide shelter when needed by persons in: host areas, where the bulk of the population is expected to be during an attack, that are located at and beyond the 2-psi air blast range, using selected target aiming points and Mt-range bursts; and, risk areas, where shelter is needed that is within 15-minutes travel time of each key worker's place of work and provides potential shelter for 30- to 50-psi air blast ranges, in terms of peak free field overpressure.

UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS:
PREDESIGNED EXPEDIENT OPTIONS II

(UNCLASSIFIED)

By: H. L. Murphy*

SRI International (formerly Stanford Research Institute)
Menlo Park, California 94025, July 1980, 272 pages
Contract No. DCPA01-77-C-0227, FEMA Work Unit 1155C (SRI Project 6876)

This report covers the results of the latest phase of a 3-phase project, with the overall objective of developing a set of expedient and engineered techniques, for upgrading the air blast and related effects resistance potential of basements in existing buildings. The purpose of upgrading such basement spaces is to provide shelter when needed by persons in: host areas, where the bulk of the population is expected to be during an attack, that are located at and beyond the 2-psi air blast range, using selected target aiming points and Mt-range bursts; and, risk areas, where shelter is needed that is within 15-minutes travel time of each key worker's place of work and provides potential shelter for 30- to 50-psi air blast ranges, in terms of peak free field overpressure.

UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS:
PREDESIGNED EXPEDIENT OPTIONS II

(UNCLASSIFIED)

By: H. L. Murphy*

SRI International (formerly Stanford Research Institute)
Menlo Park, California 94025, July 1980, 272 pages
Contract No. DCPA01-77-C-0227, FEMA Work Unit 1155C (SRI Project 6876)

This report covers the results of the latest phase of a 3-phase project, with the overall objective of developing a set of expedient and engineered techniques, for upgrading the air blast and related effects resistance potential of basements in existing buildings. The purpose of upgrading such basement spaces is to provide shelter when needed by persons in: host areas, where the bulk of the population is expected to be during an attack, that are located at and beyond the 2-psi air blast range, using selected target aiming points and Mt-range bursts; and, risk areas, where shelter is needed that is within 15-minutes travel time of each key worker's place of work and provides potential shelter for 30- to 50-psi air blast ranges, in terms of peak free field overpressure.

UPGRADING BASEMENTS FOR COMBINED NUCLEAR WEAPONS EFFECTS:
PREDESIGNED EXPEDIENT OPTIONS II

(UNCLASSIFIED)

By: H. L. Murphy*

SRI International (formerly Stanford Research Institute)
Menlo Park, California 94025, July 1980, 272 pages
Contract No. DCPA01-77-C-0227, FEMA Work Unit 1155C (SRI Project 6876)

This report covers the results of the latest phase of a 3-phase project, with the overall objective of developing a set of expedient and engineered techniques, for upgrading the air blast and related effects resistance potential of basements in existing buildings. The purpose of upgrading such basement spaces is to provide shelter when needed by persons in: host areas, where the bulk of the population is expected to be during an attack, that are located at and beyond the 2-psi air blast range, using selected target aiming points and Mt-range bursts; and, risk areas, where shelter is needed that is within 15-minutes travel time of each key worker's place of work and provides potential shelter for 30- to 50-psi air blast ranges, in terms of peak free field overpressure.

Chapters of this report's main text are devoted to discussions of:

background; general principles applicable to upgrading basements; closures for all basement shelter openings/apertures, in terms of principles for providing them; needs to be met in strengthening the structure over shelter candidate basements; some techniques and materials that can be used for such structure strengthening; and, shelters for key workers. In general, the main text of this report is intended for the artisan, the appendices having the more extensive, technical data and discussions.

The titles of the appendices are: Blast-Resistant Design/Analysis General Approach; Plywood Stressed-Skin Panels (Two-Sided Only) as Closures - Design and Fabrication; Plywood Stressed-Skin Panels (Two-Sided) as Beam-Columns; Plywood Use for Closures - Design; Wood Beam and Column Design - Simply Supported; Home Basements Upgrading in Host Areas; Blast-Resistant Design/Analysis of Steel Members; and, Structural Steel Local Availability and Use for Blast Shelter Upgrading.

The suggestions, guidance and technical help of M. A. Pachuta, G. N. Sisson, and D. W. Bensen, FEMA, are gratefully acknowledged, as are the contributions of former colleagues C. K. Wiehle, E. E. Pickering and J. E. Beck. #

* H. L. Murphy Associates, Box 1727, San Mateo, CA 94401 (415-348-2180)

James E. Beck and Associates, 4216 Los Palos Av., Palo Alto, CA 94306

Chapters of this report's main text are devoted to discussions of:

background; general principles applicable to upgrading basements; closures for all basement shelter openings/apertures, in terms of principles for providing them; needs to be met in strengthening the structure over shelter candidate basements; some techniques and materials that can be used for such structure strengthening; and, shelters for key workers. In general, the main text of this report is intended for the artisan, the appendices having the more extensive, technical data and discussions.

The titles of the appendices are: Blast-Resistant Design/Analysis General Approach; Plywood Stressed-Skin Panels (Two-Sided Only) as Closures - Design and Fabrication; Plywood Stressed-Skin Panels (Two-Sided) as Beam-Columns; Plywood Use for Closures - Design; Wood Beam and Column Design - Simply Supported; Home Basements Upgrading in Host Areas; Blast-Resistant Design/Analysis of Steel Members; and, Structural Steel Local Availability and Use for Blast Shelter Upgrading.

The suggestions, guidance and technical help of M. A. Pachuta, G. N. Sisson, and D. W. Bensen, FEMA, are gratefully acknowledged, as are the contributions of former colleagues C. K. Wiehle, E. E. Pickering and J. E. Beck. #

* H. L. Murphy Associates, Box 1727, San Mateo, CA 94401 (415-348-2180)

James E. Beck and Associates, 4216 Los Palos Av., Palo Alto, CA 94306

Chapters of this report's main text are devoted to discussions of: background; general principles applicable to upgrading basements; closures for all basement shelter openings/apertures, in terms of principles for providing them; needs to be met in strengthening the structure over shelter candidate basements; some techniques and materials that can be used for such structure strengthening; and, shelters for key workers. In general, the main text of this report is intended for the artisan, the appendices having the more extensive, technical data and discussions.

The titles of the appendices are: Blast-Resistant Design/Analysis General Approach; Plywood Stressed-Skin Panels (Two-Sided Only) as Closures - Design and Fabrication; Plywood Stressed-Skin Panels (Two-Sided) as Beam-Columns; Plywood Use for Closures - Design; Wood Beam and Column Design - Simply Supported; Home Basements Upgrading in Host Areas; Blast-Resistant Design/Analysis of Steel Members; and, Structural Steel Local Availability and Use for Blast Shelter Upgrading.

The suggestions, guidance and technical help of M. A. Pachuta, G. N. Sisson, and D. W. Bensen, FEMA, are gratefully acknowledged, as are the contributions of former colleagues C. K. Wiehle, E. E. Pickering and J. E. Beck. #

* H. L. Murphy Associates, Box 1727, San Mateo, CA 94401 (415-348-2180)

James E. Beck and Associates, 4216 Los Palos Av., Palo Alto, CA 94306

Chapters of this report's main text are devoted to discussions of: background; general principles applicable to upgrading basements; closures for all basement shelter openings/apertures, in terms of principles for providing them; needs to be met in strengthening the structure over shelter candidate basements; some techniques and materials that can be used for such structure strengthening; and, shelters for key workers. In general, the main text of this report is intended for the artisan, the appendices having the more extensive, technical data and discussions.

The titles of the appendices are: Blast-Resistant Design/Analysis General Approach; Plywood Stressed-Skin Panels (Two-Sided Only) as Closures - Design and Fabrication; Plywood Stressed-Skin Panels (Two-Sided) as Beam-Columns; Plywood Use for Closures - Design; Wood Beam and Column Design - Simply Supported; Home Basements Upgrading in Host Areas; Blast-Resistant Design/Analysis of Steel Members; and, Structural Steel Local Availability and Use for Blast Shelter Upgrading.

The suggestions, guidance and technical help of M. A. Pachuta, G. N. Sisson, and D. W. Bensen, FEMA, are gratefully acknowledged, as are the contributions of former colleagues C. K. Wiehle, E. E. Pickering and J. E. Beck. #

* H. L. Murphy Associates, Box 1727, San Mateo, CA 94401 (415-348-2180)

James E. Beck and Associates, 4216 Los Palos Av., Palo Alto, CA 94306

5-8